



Letter No. NEID-III/HQ-51/202021/ 1296-99

Date: 15.10.2020

NOTICE INVITING QUOTATION


For and behalf of the President of India, the Executive Engineer, NEID-III, CWC, Itanagar invites the sealed quotation for **"R&M of Dumka Sub Division: Repairing and painting of Dumka Sub Division Office, CWC, Dumka, Jharkhand"** from reputed and bonafide contractor as per the specifications in attached annexure-I and below mentioned terms & conditions:

Name of work: **"R&M of Dumka Sub Division: Repairing and painting of Dumka Sub Division Office, CWC, Dumka, Jharkhand"**

Terms and Conditions:

1. The rates quoted should be in figures as well as in words. Any overwriting and cutting should be initialed.
2. The quotation duly signed should reach this office on or before 15.00 hrs of 23.10.2020 and will be opened on same day i.e. 23.10.2020 at 16.00hrs in the presence of bidder/contractor or their authorized representative.
3. The sealed quotation cover should be super scribed with the words for **"R&M of Dumka Sub Division: Repairing and painting of Dumka Sub Division Office, CWC, Dumka, Jharkhand"**
4. On behalf of the President of India, undersigned reserves the right to reject any or all the quotations and to alter the quantity without assigning any reasons thereof.
5. The rates shall be valid for 90 days minimum from the date of opening of the quotation.
6. The works should be completed within 30 days from the date of issue of Work Order.
7. The payment will be made through PFMS.
8. Any other rules of CPWD codes and its amendment as applicable will be binding on the successful bidder.
9. All the corrections and over writings should be duly attested.
10. Taxes as applicable will be deducted from the bill at the time of payment.
11. Canvassing whether directly or indirectly is strictly prohibited.
12. Time allowed for completion will be essence of quotation. Extension of time will be allowed only after submission of sufficient reasons of delay.
13. The firm/agency may visit the Dumka Sub Division Office where mentioned works are to be executed completely/successfully.

पोस्ट ऑफिस बॉक्स सं - १४४, चिम्पू, ईटानगर
अरुणाचल प्रदेश - ७९११११
दूरभाष: 0360-2203510
ई मेल: eeneid3-cwc@gov.in
●जल संरक्षण-सुरक्षित भविष्य●



PO Box No. 144, Chimpur, Itanagar
Arunachal Pradesh - 791111
Tel: 0360-2203510
E-mail: eeneid3-cwc@gov.in
●Conserve Water- Save Life●

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
उत्तर - पूर्वी अन्वेषण मंडल - ३, ईटानगर



Government of India
Ministry of Jal Shakti
Department of Water Resources, RD & GR
Central Water Commission
North Eastern Investigation Division—III, Itanagar

14. In view of any unforeseen breakdown due to unavoidable circumstances, intended bidders may also send their sealed quotations through Registered Post/Speed post at the following correspondence address:

O/o the Executive Engineer,
North Eastern Investigation Division-III
Central Water Commission, Chimpu,
Near VKV School, Itanagar,
Arunachal Pradesh-791111

अखिल अखोरी
15/10/2020
(अखिल अखोरी)
अधिशायी अभियंता

प्रतिलिपि :-

1. Superintending Engineer, NEIC, CWC, Shillong for information.
2. Assistant Accounts Officer, NEID-III, CWC, Itanagar.
3. SDE(HQ), NEID-3, CWC, Itanagar
4. SDE, Dumka Sub Division, CWC, Dumka, Jharkhand

पोस्ट ऑफिस बॉक्स सं - १४४, चिम्पू, ईटानगर
अरुणाचल प्रदेश - ७९११११
दूरभाष: 0360-2203510
ई मेल: eeneid3-cwc@gov.in
●जल संरक्षण-सुरक्षित भविष्य●



PO Box No. 144, Chimpu, Itanagar
Arunachal Pradesh - 791111
Tel: 0360-2203510
E-mail: eeneid3-cwc@gov.in
●Conserve Water- Save Life●

To be quoted by bidder/firm/agency

S.No	Item	Quantity	Rate	Amount	Remarks
1	Rooftop repairing work including removing of swollen/blistered/loosen plaster and cleaning the surface: Providing and laying 1.5" PCC (1:2:4), 12mm plastering and Panning with water proofing admixture, all completed.	227.38sq m			
02	Removing loose or damaged plaster and Providing new plaster(Ceiling and Wall Both) all completed	160Sqm Lumpsum			
03	Providing and applying two coat of emulsion paint followed by one coat of Primer including cleaning by sand paper, smoothening of surface by applying wall putty where necessary,	670.43Sqm			
04	Providing and applying paints on doors and windows including cleaning the wooden surface with turpentine oil, sand paper, cotton cloth etc all complete	32.58Sqm			
	Total including material charges and labour charges				
	contingency@3%				
	Contractor Profit@10%				
	GST @				
	Total inclusive of all taxes and contractor's Profit				
	Total amount in Words				

Signature & Seal of bidder/agency/firm/contractor or their representative.

Sl. No.	Details of Work/Item/Location	No.	Measurements			Quantities	
			L	B	H		
01	Rooftop repairing work including removing of swollen/blistered/loosen plaster and cleaning the surface : Providing and laying 1.5" PCC(1:2:4), 12mm plastering and Panning with water proofing admixture all completed					227.38Sq M	
	a. Front Verandah						
	(i) North side.....	01	4.70	2.90		13.63	
	(ii) South side.....	01	4.70	2.90		13.63	
	(iii) Main Entrance.....	01	5.50	3.75		20.63	
	b. Porch.....	01	5.50	2.80		15.40	
	c. Roof Gutter	02	12.20	0.65		15.86	
	d. Room, Hall and Toilet.....	01	14.90	8.35		124.42	
		01	5.70	0.75		4.28	
		01	9.30	2.10		19.53	
Net Quantity						227.38SqM	
02	Removing loose or damaged plaster and Providing new plaster(Ceiling and Wall Both) all completed					160Sqm Lumpsum	
03	Providing and applying Two coat of emulsion paint followed by one coat of Primer including cleaning by sand paper, smoothening of surface by applying wall putty where necessary, of approved quality by E/I						
	a. Front Verandah (Wall Portion)	02	4.60		2.75	25.30	
		02	1.70		2.75	9.35	
		01	5.50		2.75	15.13	
		01	22.30		0.65	14.50	
	(Ceiling portion)	02	4.30	2.50		21.50	
		01	4.90	3.45		16.91	
		02	1.75	0.30		1.05	
	(Sunshade)	02	12.20	0.65		15.86	
	Porch	01	5.50	2.80		15.40	
	Deductions						
	Door	03	2.10		1.20	7.56	
	Window	04	1.35		1.20	6.48	
	Net Quantity						120.96
	b. 02 Rooms including Toilet (Wall Portion)	04	7.55		3.65	110.23	
		04	4.30		3.65	62.78	
		04	2.70		3.65	39.42	
		04	2.55		3.65	37.23	
	(Ceiling Portion)	02	7.55	4.25		64.18	
	(Sunshade)	02	3.50	0.65		4.55	
Deductions							
Door	02		1.20	2.10	5.04		

		02		0.90	2.10	3.78
		04		0.75	2.10	6.3
	Window	02		1.35	1.20	3.24
		02		1.80	1.20	4.32
	Net Quantity					295.71
	c. Hall					
	(Wall Portion)	02	10.40		3.65	75.92
		02		4.90	3.65	35.77
	(Ceiling portion)	01	10.40	4.90		50.96
	Deductions					
	Door	02		1.20	2.10	5.04
		02		0.90	2.10	3.78
		02		0.75	2.10	3.15
	Window	02		1.35	1.20	3.24
	Net Quantity					147.44
	d. Roof top wall (Porch and Verandah)					
			31.75		0.35	11.11
			25.00		0.75	18.75
			16.40		0.95	15.58
	Net Quantity					45.44
	e. Exterior Wall					
		02	8.15		4.00	65.20
	Deduction					
	Window	02	1.80		1.20	4.32
	Net Quantity					60.88
	Total of Net quantity (a+b+c+d+e)					670.43SqM
04	Providing and applying paints on doors and windows including cleaning the wooden surface with turpentine oil, sand paper, cotton cloth etc all complete.					
	Doors	04		1.20	2.10	10.08
		02		0.90	2.10	3.78
		04		0.75	2.10	6.30
	Windows	05		1.35	1.20	8.10
		02		1.80	1.20	4.32
	Net Quantity					32.58SqM