



No. SLG/T-7/2020-21/608-412

Dated: 19 / 02 / 2021

NOTICE INVITING QUOTATION

N.I.Q No-02/UTUMSD/SLG of 2020-21

Sealed quotations in prescribed pro-forma is hereby invited by the Sub-Divisional Engineer, UTUM Sub-Division, Central Water Commission, Ganesh Ghosh Colony, Champasari, Siliguri, PIN-734003 on Behalf of the President of India from bonafide/Govt. approved firm/Contractor for the construction of MTBM at Rangpo gauge site, P.O/P.S – Rangpo, West Bengal, Pin Code – 734315 under UTUM Sub-Division, CWC, Siliguri on or before **27.02.2021 at 15:00 hrs.** on the terms & conditions and schedule noted below. The quotations will be opened in the **same day at 15:30 hrs.**, during opening contractor or their authorized representative may attend.

Schedule:-

Sl No.	Description	Quantity	Unit	Rates		Amount
				In figure	In words	
1.	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete (a) Depth of excavation not exceeding 1,500 mm.	2.37	Cum			
2.	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	1.44	Sqm			
3.	Cement concrete with 30 mm down graded shingles excluding shuttering.N.B. Variety In ground floor (B) With N.B. Variety stone metal. (a) 1:3:6 proportion	2.35	Cum			
4.	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, In ground floor as per relevant IS codes. a) Pakur Variety	0.02	Cum			
5.	Reinforcement for reinforced concrete work in all sorts of structures including distribution					

	bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. a) For works in foundation, basement and upto roof of ground floor/upto 4 m (i) For steel/Mild Steel II. Other than SAIL/TATA/RINL	0.0023	MT			
6.	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	3.60	Sqm			
7.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (ground floor) (ii) With 1:4 cement mortar(b) 15 mm thick plaster.	8.64	Sqm			
8.	Providing and fixing white stone plate of size (0.1x0.1)m Granite on wall at top grey colour.	0.01	Sqm			
9.	Applying decorative cement based paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or concrete surface) as per manufacturer's specification (iii) Two coats.	8.64	Sqm			
10.	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	0.61	Cum			
11.	Total					
12.	GST					
13.	Total including GST					
14.	Labour Welfare cess on Sl. No. 14)					
15.	Grand Total					


NIQ dropping centre:- Office of The Sub –Divisional Engineer ,UTUM Sub-Division, Central Water Commission, Ganesh Ghosh Colony , Siliguri ,PIN-734003.

The terms and conditions of the NIQ are mentioned below:-

Terms and conditions

- 1) The rates are to be quoted for complete and satisfactory work at Rangpo gauge site, P.O/P.S – Rangpo, West Bengal, Pin Code – 734315 under UTUM Sub-Division, CWC, Siliguri.
- 2) The rates should be valid for 60 (Sixty) days from the date of opening of quotation.
- 3) Work should be completed within 20 (Twenty) days from the date of issue of work order with the satisfaction of competent authority which shall be final in this regards.

- 4) The rate must be quoted both in figure and words
- 5) The work shown above is tentative and may be increased/ decreased at the time of placing work order. Final measurement will be taken after completion of work and the payment will be made on the basis of actual work done.
- 6) Any accident during execution of work will be borne by the firms/agency.
- 7) No advance payment will be made before completion of work. The payment will be made by net banking on receipt of bills in triplicate after completion of full and satisfactory work.
- 8) Applicable tax as per rule will be deducted from bill.
- 9) The undersigned reserves the right to reject any part or whole of the quotation & without assigning any reason whatsoever.
- 10) The quotations should be attached with PAN card, GST certificate, trade license and credentials of firms for similar nature work.
- 11) Successful quotation will have to deposit @ 5 % of the total value of work order exceeding **Rs.1000/-** as security deposit/ performance guarantee before placing the order within 7 days of the formal letter of acceptance. The performance guarantee will be furnished in the form of deposit at call receipt of any schedule bank/ bankers cheque of any schedule bank/ Demand draft of any scheduled bank/ pay order of any schedule bank in accordance with the prescribed form in favor of Executive Engineer, lower Brahmaputra Division, Central Water Commission, Jalpiaguri – 735101, West Bengal. The performance guarantee should remain valid for a period of 60 days beyond the date of completion of all the contractual obligations of the bidder.
- 12) The envelope containing quotation should be super – scribed ‘ Quotation for Construction of MTBM at Coronation gauge site’’ mentioning due date of opening.
- 13) The quotation should be addressed to **Sub –Divisional Engineer, UTUM Sub-Division, Central Water Commission, Ganesh Ghosh Colony , Siliguri ,PIN-734003.**
- 14) This notice can also be seen on the website (<http://eprocure.gov.in/epublish/app>) & (<http://cwc.gov.in>)


 19/02/2021

Sub –Divisional Engineer
 UTUM Sub-Division, CWC, Siliguri.

Copy forwarded for kind information and wide circular to:-

- 1) The Superintending Engineer, Investigation Circle, CWC, Gangtok, Sikkim. This is with reference to AA& ES accorded by SE, IC, CWC, Gangtok vide e office file No. 9/143/2018-DB/IC/SKM/VOI-IV dated on 08.01.2021
- 2) The Director, SMDTE, CWC, New Delhi with request to kindly arrange to upload this NIQ in CWC's website (through EE, L.B.D).
- 3) The Executive Engineer, L.B. Division, CWC, Jalpaiguri with request to arrange to upload this NIQ in (<http://eprocure.gov.in/epublish/app>) website.
- 4) The AEE/SDE, JLT /TRS Sub-Division, CWC, Jalpaiguri / Coochbehar for wide publicity.
- 5) Office notice board. UTUM Sub-Division, CWC, Siliguri For wide publicity.
- 6) Website address: (<http://eprocure.gov.in/epublish/app>).

