



84/93-96, प्रताप नगर, सांगानेर, जयपुर -302033
फोन: 0141-2790065, ई-मेल: chambalcwc@yahoo.co.in

पत्रांक: चमज/ के.ज.आ./मु.-1/2024/2559-62

दिनांक: 30.09.2024

कोटेशन आमंत्रण सूचना (NOTICE INVITING QUOTATION)

भारत के राष्ट्रपति की ओर से अधिशाषी अभियंता, चम्बल मंडल, जयपुर द्वारा अधिकृत तथा योग्य बोलीदाताओं से “चम्बल मंडल, के.ज.आ., जयपुर के कार्यालय भवन के भूतल का मरम्मत कार्य हेतु कोटेशन” लिखा हुआ मुहरबंद कोटेशन आमंत्रित किये जाते हैं।

Sealed quotation super scribed as “**Quotation for Restoration/Repair of Ground Floor of office Building at Chambal Division, CWC, Jaipur**” are invited for and on behalf of the President of India by the Executive Engineer, Chambal Division, CWC, Jaipur from the authorized and eligible bidders.

नियम एवं शर्तें (Terms & Conditions)

1. हस्ताक्षरित व मुहरबंद कोटेशन अधिशाषी अभियंता, चम्बल मंडल, केन्द्रीय जल आयोग, जयपुर के कार्यालय में दिनांक 07.10.2024 पूर्वान्ह 10:00 बजे तक या उससे पूर्व प्राप्त हो जानी चाहिए, जो उसी दिन अर्थात् 07.10.2024 दोपहर 11:00 बजे अधोहस्ताक्षरी तथा बोली लगाने वाले या उसके प्रतिनिधि जो उपस्थित रहना चाहे की उपस्थिति में खोली जाएगी। निर्धारित तिथि एवं समय (दिनांक 07.10.2024 पूर्वान्ह 10:00 बजे) के बाद प्राप्त होने वाली कोटेशन स्वीकार नहीं की जाएगी।

The sealed & signed quotation shall reach to the office of Executive Engineer, Chambal Division, CWC, Jaipur on or before 07.10.2024 upto 10:00 A.M. and will be opened on the same day i.e. 07.10.2024 at 11:00 A.M. in the presence of undersigned and bidders or their representative who may likely to be present at the time of opening of quotations. Quotation received after specified date and time (upto 07.10.2024 at 10:00 A.M.) will not be accepted.

2. मुहरबंद कोटेशन के साथ रुपये 7980/- की ईएमडी केवल डिमांड ड्राफ्ट/बैंकर्स चेक/एफडीआर के रूप में अधिशाषी अभियंता, चम्बल मंडल, केजआ, जयपुर के पक्ष में संलग्न करना अनिवार्य है। बिना ईएमडी के प्राप्त कोटेशन को खारिज कर दिया जाएगा। MSE & Startup को ईएमडी जमा करने की छूट दी गई है।

The EMD of Rs. 7980/- in the form of Demand Draft/Bankers Cheque/FDR only, in favor of Executive Engineer, Chambal Division, CWC, Jaipur should be enclosed with sealed quotation. Quotations received without EMD will be summarily rejected. MSE & Startup are exempted from payment of EMD.

3. कोटेशन नोटिस (सभी अनुलग्नकों और मूल्य बोली सहित) के सभी पृष्ठों पर सील और हस्ताक्षर करना अनिवार्य है। बिना seal and sign (सभी पृष्ठों पर) के प्राप्त कोटेशन को खारिज कर दिया जाएगा।

The quotationer must seal and sign at all pages of the quotation notice including all annexures and price bid failing which the quotation will summarily rejected.

4. अंतिम तिथि व समय के पश्चात प्राप्त कोटेशन स्वीकार नहीं करी जाएगी और गैर-उत्तरदायी मानी जाएगी।
Quotation received after the last submission date & Time will not be accepted and will be treated as non-responsive.
5. ठेकेदार/फर्म/एजेंसी द्वारा पिछले तीन वर्षों में केंद्र सरकार के विभाग/राज्य सरकार के विभाग/पीएसयू के लिए पुराने भवन का रेट्रोफिटिंग/मरम्मत कार्य (राशि 3 लाख) सफलतापूर्वक पूरा किया होना चाहिए। पुराने भवन के रेट्रोफिटिंग/ मरम्मत कार्य का अनुभव प्रमाण पत्र (राशि 3 लाख) कोटेशन के साथ प्रस्तुत किया जाना चाहिए। अपेक्षित अनुभव (जैसा कि ऊपर बताया गया है) के बिना प्राप्त कोटेशन स्वीकार नहीं की जाएगी।
The contractor/firm/agency should have successfully completed retrofitting/restoration (of old building) work (of amount not less than 5 Lakhs) for Central Govt./State Govt./ PSU in previous three years. The experience certificate of retrofitting/restoration (of old building) work (of amount not less than 5 Lakhs) should be submitted with Quotation. Bids received without requisite experience (as mentioned above) will not be accepted.
6. कार्य करने की अवधि कार्यदिश जारी होने के बाद से 60 दिन की रहेगी।
Work shall be carried within 60 days after issue of work order.
7. कोटेशन में दर्शायी गयी राशि सभी प्रकार के टैक्स (GST etc.) के साथ होनी चाहिए तथा Annexure-1 में निर्धारित जगह पर ही राशि को दर्शाये।
Rates shall be quoted including of all Taxes (GST etc.) and rates should be mentioned in Annexure-1 at their shown place only.
8. दरें बिना किसी ओवर राइटिंग के सुपाठ्य रूप से लिखी जानी चाहिए। किसी भी सुधार के मामले में, इसे बोलीदाता द्वारा पूर्ण हस्ताक्षर के साथ सत्यापित किया जाना चाहिए। दर और राशि (दर और मात्रा को गुणा करके प्राप्त किया जाता है) के बीच किसी भी विसंगति के मामले में दर मान्य होगी और राशि की गणना तदनुसार (दर और मात्रा को गुणा करके) सही की जाएगी। राशि के योग में त्रुटि के मामले में, अलग-अलग मद की दरों का उपयोग करके निकाली गई कुल राशि को सही कुल राशि माना जाएगा।
The rates should be quoted legibly written without any over-writings. In case of any correction, the same must be attested by the bidder with a full signature. In case of any discrepancy between the rate and amount (obtained by multiplying rate and quantity), the rate shall prevail and the amount shall be calculated accordingly. In case of error in summation of amount, the total amount that is worked out using rates of individual item will be treated as corrected total amount.
9. इस कार्य हेतु इस्तेमाल में लिया गया सामान अच्छी गुणवत्ता (प्रतिष्ठित कंपनी) का एवं दिए गये विशेष विवरण के अनुसार तथा त्रुटी रहित होना चाहिए।
The material used for this work must be of standard quality (reputed brand) and as per specifications and free from all the defects.
10. कोटेशन में दर्शायी दरे, कोटेशन खुलने के दिन से कम से कम 40 दिन तक वैध होनी चाहिए।
Rates quoted should be valid at least for 40 days from date of opening.
11. उक्त कार्य चम्बल मंडल (प्रताप नगर, जयपुर, राजस्थान) पर होना हैं, जिनका दरें डालने से पूर्व निरीक्षण किया जा सकता हैं।
The above work is to be done at Chambal Division (Pratap Nagar, Jaipur, Rajasthan), which (Place) can be inspected before quoting the rates.

12. कोटेशनर के पास PAN/GST No. होना चाहिए (प्रतिलिपि संलग्न की जाए)। बिना PAN तथा GST No. प्रतिलिपि के प्राप्त कोटेशन को खारिज कर दिया जाएगा।
Quotationer must have Firm Registration certificate/PAN/TIN/GST No. (Copy to be enclosed). Quotations received without copy of PAN & GST No. will be summarily rejected.
13. अधोहस्ताक्षरी किसी एक या सभी कोटेशन को बिना कारण बताये स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता है।
Undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
14. कार्य की मात्रा कार्यदिश के समय या कार्य करने के दौरान बढ़ाई या कम की जा सकती हैं।
The quantity of work may be increased or decreased at the time of work order or during the time of execution.
15. कोटेशन स्वीकृत होने पर, फर्म/एजेंसी को किसी भी वाणिज्यिक बैंक से Account Payee D.D/ Fixed Deposit Receipt/ Banker's cheque or Bank Guaranty के रूप में निविदा राशि के 3% की दर से परफॉरमेंस गारंटी जमा करनी होगी जो की अधिशाषी अभियंता, चंबल मण्डल, के.ज.आ., जयपुर को देय होगी। परफॉरमेंस गारंटी कार्य समाप्त होने के 180 दिन बाद तक वैध होनी चाहिए।
On acceptance of the quotation, the Firm/Agency shall have to submit performance Guarantee @ 3% of the tendered amount in the form of an Account Payee D.D/ Fixed Deposit Receipt/ Banker's cheque or Bank Guaranty from any of the commercial bank in favour of Executive Engineer, Chambal Division, CWC, Jaipur payable at Jaipur. This should remain valid for a period of 180 days beyond the date of completion of work.
16. कार्य के संतोषजनक पूर्ण होने के बाद सम्पूर्ण भुगतान में से आवश्यक कटौती (2.5 % Security Deposit, 2 % GST, 2% TDS, 1% Labour Cess) पश्चात भुगतान को ECS/RTGS के द्वारा किया जायेगा। अमानत राशी (Security Deposit) का भुगतान कार्य समाप्त होने के 06 माह के पश्चात किया जायेगा।
Payment will be made through ECS/RTGS, only after satisfactory completion of work and deduction of necessary Deductions (2.5% Security Deposit, 2% GST, 2% TDS, 1% Labour Cess). Security Deposit amount will be given after 06 months of completion of work.
17. चोरी, दुर्घटना, प्राकृतिक आपदा या किसी भी अन्य कारण से उपकरण, सामग्री और जान-माल की क्षति/हानि या नुकसान के दावे किसी भी सूरत में विभाग द्वारा स्वीकृत नहीं किये जाएंगे।
Claim/claims of damage or loss of equipment & material and life due to theft, accident or natural calamity or any other reason whatsoever shall not be entertained by the department.

Sd/-

अधिशाषी अभियंता

चम्बल मंडल, के.ज.आ., जयपुर

प्रतिलिपि सूचनार्थ:

1. सहायक लेखाधिकारी, लेखा शाखा, चम्बल मंडल, जयपुर।
2. सहायक, पत्राचार शाखा, चम्बल मंडल, जयपुर।
3. सूचना पट्ट, चम्बल मंडल, जयपुर।
4. विभागीय वेबसाइट।

Schedule of Quantity

Name of work: Restoration/Repair of Ground Floor of office Building at Chambal Division, CWC, Jaipur

Item No.	Sub-head and items of work	Qty.	Unit	Rate in Rs. (Incl. GST)	Amount in Rs.
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead - For thickness of tiles 10 mm to 25 mm	33.02	Sqm		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	41.22	Sqm		
3	Dismantling W.C. Pan of all sizes including disposal of dismantled materials including malba all complete as per directions of Engineer-in-Charge.	2.00	each		
4	Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts all complete as per direction of Engineer-In-Charge. 25 mm average thickness	3.42	Sqm		
5	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust-free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. Bars upto 12 mm diameter	40.50	m		
6	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. Epoxy bonding adhesive having coverage 2.20 sqm/kg of approved make	3.42	Sqm		
7	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platform	6.84	Sqm		

8	<p>Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded coarse sand with polymer minimum 2% by wt. of cement used) as per specifications and directions of Engineer-in-charge.</p> <p>Note: Measurement and payment: The pre-measurement of thickness will be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and/or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N/Sqmm2). 25 mm average thickness in 2 layers</p>	3.42	Sqm		
9	<p>Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.</p>	6.84	Sqm		
10	<p>Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.</p>	26.18	Sqm		
11	<p>Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid</p>	1	Nos.		
12	<p>Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests</p>	1	Nos.		

13	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap	1	Nos.		
14	Providing and fixing brass stop cock of approved quality: 20 mm nominal bore	4	Nos.		
15	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible Pipe 40 mm dia	2	Nos.		
16	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings.	1	Nos.		
17	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	2	Nos.		
18	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms.	1	Nos.		
19	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	1	Nos.		
20	Providing and fixing trap of self-cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors: 100 mm inlet and 100 mm outlet Hubless centrifugally cast (spun) iron epoxy coated inside & outside as per IS:15905	4	Nos.		
21	12 mm cement plaster (IN FINE SAND) of mix: 1:4 (1 cement: 4 fine sand)	15.04	Sqm		
22	Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts all complete as per direction of Engineer-In-Charge. 25 mm average thickness	52	Sqm		

23	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. Bars upto 12 mm diameter	624	m		
24	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. Epoxy bonding adhesive having coverage 2.20 sqm/kg of approved make	52	Sqm		
25	Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded coarse sand with polymer minimum 2% by wt. of cement used) as per specifications and directions of Engineer-in-charge. Note: Measurement and payment: The pre-measurement of thickness will be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and/or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N/Sqmm2). 25 mm average thickness in 2 layers	52	Sqm		
26	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	24	Each		
27	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1cement: 4 Fine sand)	50	Sqm		
28	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platform	52	Sqm		
29	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	353.42	Sqm		

30	Providing and applying white cement-based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	438.93	Sqm		
31	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour: New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre	438.93	Sqm		
Grand Total in figures Rs.					
Grand Total in Words					

Note: Quotations received without mentioning Grand Total in Figures & words both will be summarily rejected.

Terms & conditions: - As per NIQ
Issuing Authority

Sd/-
Executive Engineer
Chambal Division

Signature of Contractor
Seal
Address