



मिसिल सं./File No. 102/06/NIQ/2024-25/150-154

दिनांक/Date: 21.01.2025

उद्धरण आमंत्रण सूचना/ NOTICE INVITING QUOTATION

कार्य का नाम/Name of Work:- “Repairing, Renovation work of existing Site Office of Pancheshwar GDS Site & Repairing of Existing Sand Filter of Pancheshwar Guest House, Central Water Commission, Champawat, Uttarakhand.”

भारत के राष्ट्रपति की ओर से, उपर्युक्त कार्य के लिए अधिकृत सेवा प्रदाताओं से नीचे दिये गए नियम एवं शर्तों के अनुसार मुहरबंद उद्धरण आमंत्रित किए जाते हैं।

On behalf of the President of India, Sealed quotations are invited from the Bonafide firms/agencies/contractors for the above-mentioned work subject to the terms and conditions mentioned below: -

Terms & Conditions: -

1. उपरोक्त कार्य पञ्चेश्वर जलविज्ञानिय प्रेक्षण (पी.एच.ओ) उपमंडल, टनकपुर, उत्तराखंड के अंतर्गत आने वाली पंचेश्वर स्थल पर किया जाना है।

Above works shall be executed at Pancheshwar site under Pancheshwar Hydrometeorological Observation (PHO) Sub-Division, Tanakpur, Uttarakhand.

2. उपरोक्त कार्य को अनुलग्नक-I में संलग्नित ड्राइंग के अनुसार पूर्ण करवाना होगा।

The above work will have to be completed as per the attached drawings in Annexure-I.

3. दरों को प्रत्येक item के सामने शब्दों और अंकों दोनों में उद्धृत किया जाना है।

The Rates are to be quoted both in words and figures against each item.

4. चोरी, दुर्घटना, प्राकृतिक आपदा अथवा अन्य किसी भी कारण से उपकरण/सामग्री एवं जान-माल के नुकसान के दावे किसी भी सूरत में विभाग द्वारा स्वीकृत नहीं किए जाएंगे।

Claim/claims of damages or loss of the equipment's & material and life due to theft, accident or natural calamity or any other reasons whatsoever shall not be entertained by the Department.

5. उपरोक्त कार्य के दौरान उपकरण/सामग्री तथा मजदूरों के बचाव एवं सुरक्षा की ज़िम्मेदारी पूर्ण रूप से आपूर्तिकर्ता/Bidder की होगी। किसी भी दुर्घटना के मामले में आवश्यक मुआवजा आपूर्तिकर्ता/Bidder द्वारा नियम के अनुसार वहन करना होगा। ऐसी किसी भी अप्रत्याशित घटनाओं के लिए विभाग को जिम्मेदार नहीं ठहराया जाएगा और किसी भी कीमत पर विभाग द्वारा कोई मुआवजा नहीं दिया जाएगा।

Responsibility of safety and security of equipment's, material and labour during above-mentioned work will entirely rest with the Supplier/Bidder. Necessary compensation in case of any accident will have to be borne by the supplier as per rule. Department will not be held responsible for any such unforeseen events and no compensation shall be paid by the Department at any cost.

6. सभी कोटेशन करने वालों को दरों को उद्धृत करने से पहले कार्यस्थल पर जाने की सलाह दी जाती है। एक बार जमा किए गए उद्धरण को बाद में किसी भी परिवर्तन की अनुमति नहीं दी जाएगी।



All quotations are advised to visit the work site before quoting the rates. Quotation once submitted will not be allowed any changes later on.

7. उपरोक्त कार्य, प्रभारी अभियंता या उसके अधिकृत प्रतिनिधि के दिशा निर्देशों के अनुसार पूरा किया जाएगा।
Work shall be executed as per the direction of Engineer in Charge or his representative to his full satisfaction.
8. उद्घरण सील बंद लिफाफे में रखी जानी चाहिए तथा लिफाफे पर कार्य का नाम Quotation for **“Repairing, Renovation work of existing Site Office of Pancheshwar GDS Site & Repairing of Existing Slow Sand Filter of Pancheshwar Guest House, Central Water Commission, Champawat, Uttarakhand”** लिखा होना चाहिए।

The sealed quotation cover should be super-scribed with the name of work as Quotation for **“Repairing, Renovation work of existing Site Office of Pancheshwar GDS Site & Repairing of Existing Sand Filter of Pancheshwar Guest House, Central Water Commission, Champawat, Uttarakhand”**

9. हस्ताक्षरित व सील बंद उद्घरण इस कार्यालय (पता: अधिशासी अभियंता, योजना एवं अन्वेषण मंडल, क्वार्टर नं. 1064, टाइप –V, एनएच IV, एन.आई.टी.केंद्रीय जल आयोग के कार्यालय, फरीदाबाद, हरियाणा-121001) में दिनांक 28.01.2025 को दोपहर 15:00 बजे तक या उससे पूर्व प्राप्त हो जानी चाहिए जिसे उसी दिन दोपहर 15:30 बजे अधोहस्ताक्षरी अथवा प्राधिकृत प्रतिनिधि द्वारा आपूर्तिकर्ता या उनके प्रतिनिधि की उपस्थिति में खोला जाएगा।

The Quotation confirming to specifications duly signed should reach this office (at Address: Executive Engineer, Planning & Investigation Division, Quarter No. 1064, Type-V, NH IV, NIT, Central Water Commission, Faridabad, Haryana – 121001) on or before 28.01.2025 (15:00 hours) and shall be opened on the same day at 15:30 hours. All the quotations or their authorized representatives are advised to be physically present during opening of the Bid at above-mentioned address.

10. कार्य आदेश जारी होने के 30 दिन के भीतर उपरोक्त कार्य पूर्ण करना होगा, तत्पश्चात जी०सी०सी० के खंड 2 के अनुरूप जुर्माना लगाया जाएगा जो कि आपूर्तिकर्ता/कांट्रैक्टर के बिल भुगतान से काट लिया जाएगा। जुर्माना 1 % प्रतिमाह की दर से विलंब प्रतिदिन के आधार पर कांट्रैक्टर के द्वारा की गयी देरी की वजह से हुई क्षति को देखते हुए मापा जाएगा जो कि अधिकतम स्वीकृत धनराशि के 10% मूल्य तक हो सकता है।

The work will have to be completed within 30 days from the date of issuance of the work order, failing in which; appropriate penalty as per Clause 2 of GCC may be deducted from the payment with maximum rate @ 1% (one percent) per month of delay to be computed on per day basis based on quantum of damage suffered due to stated delay on the part of Contractor, subjected to maximum of 10% of the accepted Tendered Value

11. सामान की सुरक्षा की पूर्ण ज़िम्मेदारी फ़र्म की होगी। सामान की टूट-फूट/ खोने या नुकसान की स्थिति में अधोहस्ताक्षरी द्वारा निर्धारित क्षतिपूर्ति राशि, फ़र्म को होने वाले भुगतान राशि से काट ली जाएगी।

The firm shall have full responsibility for the safety of the goods and accessories. In the event of wear and tear or loss, the compensation amount appropriately determined by the undersigned will be deducted from the amount paid to the firm.

12. भारत के राष्ट्रपति की ओर से अधोहस्ताक्षरी न्यूनतम या किसी अन्य उद्धरणकर्ता को बिना कारण बताए अस्वीकार और मात्रा में परिवर्तन का अधिकार सुरक्षित रखते हैं।
On behalf of President of India, the undersigned reserves the right to reject the lowest or any quotation and to alter the quantity without assigning any reason thereof.
13. उद्धरण दरें उद्धरण खोले जाने वाली दिनांक से 90 दिनों तक वैध होंगी।
The rates shall be valid for minimum of 90 days from the date of opening of the quotation.
14. फर्म GST पंजीकृत होनी चाहिए एवं GST संख्या अनिवार्य रूप से कोटेशन में दर्शायी होनी चाहिए।
The firm should be GST registered and the GST number should mandatorily be indicated in quotation.
15. उपरोक्त कार्य हेतु जारी किया गया कार्यदिश 10 दिन के नोटिस उपरांत कभी भी निरस्त किया जा सकता है।
The work order issued for the above work may be cancelled at any time after 10 days' notice period without assigning any reason or thereof.
16. CPWD वर्क्स मैनुअल 2022 के अनुसार NIQ के साथ रु. 5402.00 (रुपए पांच हजार चार सौ दौ रूपये मात्र) (अनुमानित लागत रु. 270105/- का 2%) की राशि Earnest Money Deposit (EMD) के रूप में Executive Engineer, Planning and Investigation Division, Central Water Commission के पक्ष में DD/FDR बना कर जमा करना होगी। कोटेशनकर्ताओं की EMD, CPWD Work manual 2022 के Clause संख्या 5.1.4 के अनुसार वापस कर दी जाएगी।
- केंद्रीय जल आयोग के पत्र संख्या टी-36074/(ii)/3/2020-आर.डी-1 डी.टी.ई दिनांक 05.08.2022 के अनुसार समान प्रकार के कार्यों के लिए MSEs के साथ पंजीकृत ठेकेदार (उसका वैध प्रमाण बिड में संलग्न होना चाहिए) को EMD भुगतान की छूट दी गई है।
- निर्दिष्ट Earnest Money के बिना जमा किए गए NIQ को सरसरी तौर पर खारिज कर दिया जाएगा और संबंधित बोली नहीं खोली जाएगी।
- The NIQ shall be accompanied by Earnest Money Deposit (EMD) of **Rs. 6029.00 (Rupees Six Thousand Twenty-Nine only)** (2% of Estimated Cost Rs. 270105/-) in form of DD/FDR in favor of **Executive Engineer, Planning and Investigation Division, Central Water Commission** as per CPWD works manual 2014 clause 19.4. Quotations EMD shall be returned as per the CPWD Work manual 2022 Clause No. 5.1.4.
- Contractor registered with MSEs for similar type of works (Valid proof of the same must be enclosed in bid) are exempted from payment of EMD as per CWC letter No T-36074/(ii)/3/2020-RD-1 Dte dated 05.08.2022.
- The NIQ submitted without specified Earnest Money, shall be summarily rejected and the corresponding bid shall not be opened.
17. सफल quotationors को स्वीकृत अनुबंध मूल्य के 3% की राशि Performance guarantee के रूप कार्य स्वीकृत होने के 7 कार्य दिवसों के भीतर Executive Engineer, Planning and Investigation Division, Central Water Commission at Faridabad के पक्ष में ISR/DD/FDR/e-Bank Guarantee बना कर जमा करना होगा जोकि अनुबंध की समाप्ति की तारीख से 120 दिनों तक वैध होगा।



Successful quotationors have to submit performance guarantee within 7 working days of acceptance of work, amounting to 3% of accepted contract value in the form of ISR/DD/FDR/e-Bank Guarantee in favor of **Executive Engineer, Planning and Investigation Division, Central Water Commission** valid upto 120 days beyond the date of expiry of contract.

18. कार्यालय आदेश जारी होने के पश्चात यदि कोई निविदाकार विदित समय में कार्य करना शुरू नहीं करता है तो इस बात की जानकारी लिखित में कार्य प्रभारी अभियंता को देनी होगी। कार्य प्रभारी अपने विवेक पर प्राप्त प्रतिक्रिया के आधार पर फर्म के खिलाफ कोई आवश्यक कार्रवाई (निलंबन, ब्लैकलिस्टिंग आदि) करने का पूर्ण अधिकार रखता है।
Even after the award of the work, if firm fails to take up the work within the stipulated time frame; the reasons of the same shall be furnished to Engineer-in-Charge in writing. The Engineer In-Charge at its discretion has full authority to take any necessary action against the firm (suspension, blacklisting etc.) based on the response received.
19. केंद्रीय लोक निर्माण विभाग 2022 व समय समय पर उसके आगामी सभी संशोधनों के सभी नियम सारे निविदाकारों / सफल निविदाकारों के लिए बाध्य होंगे।
Rules/provisions of CPWD Works Manual 2022 and its subsequent amendments from time to time will be applicable/binding on all bidders and on successful bidder.
20. निविदाकार को आस पास के सभी घरों, इलाकों में कोई बाधा उत्पन्न न हो इसका पूर्ण एहतियात बरतना होगा और किसी भी संपत्ति में कोई क्षति न होगा इसका विशेष ध्यान रखना होगा।
The contractor shall take all necessary precautions to prevent any nuisance or inconvenience to the owners, tenants of adjacent properties and to the public in general and to prevent any damage to such properties.
21. कार्य प्रभारी अभियंता द्वारा कार्य पूर्ण होने से पहले समय-2 पर कार्य की स्थिति व कार्य के मानकों की जांच की जाएगी, यदि निरीक्षण के दौरान कार्य प्रभारी अभियंता व उनसे ऊपर किसी अधिकारी द्वारा अवमानक सामग्री या अनुचित कारीगरी पायी गयी तो उसको उसी समय सही कर ऐसा करने की स्पष्ट वजह की लिखित में व्याख्या करनी होगी।
The Engineer-in-Charge will examine the work executed from the point of view of scope of work and specifications for the various items before the work is finalized. If during any of the visit improper workmanship is noted by the Engineer-in-Charge or his superiors, the same shall also be promptly rectified on getting a written notice to do so.
22. भुगतान प्रभारी इंजीनियर द्वारा किए गए कार्य से संतुष्टि के बाद PFMS (NEFT / RTGS) के माध्यम से किया जाएगा। जिस बैंक खाते में भुगतान किया जाना है, उस खाते का Self-attested Bank Mandate फॉर्म अनिवार्य रूप से कोटेशन के साथ लगाना है।
The payment will be made through PFMS mode only (NEFT/RTGS) after satisfactory completion of work. Self-attested Bank Mandate form where payment is to be credited shall be mandatorily attached.
23. सरकार के नवीनतम आदेशों के अनुसार जीएसटी एवं आयकर पर TDS भुगतान के समय बिल से काट लिया जाएगा। अतः उद्धरण के साथ PAN और जीएसटी पंजीकरण की प्रतियां संलग्न करना अनिवार्य है अन्यथा उद्धरण को अस्वीकार कर दिया जाएगा।





TDS on income tax as per latest govt. orders / GST @ applicable rates will be deducted from the bill at the time of payment. Therefore, copies of the PAN and GST registration to be enclosed along with quotation, failing in which the quotation will be rejected.

24. निर्धारित तिथि एवं समय के उपरान्त प्राप्त होने वाले उद्धरण स्वीकार नहीं किये जाएंगे।

Quotation received after specified date and Time will not be accepted.

25. निविदाकार द्वारा किसी भी प्रकार का प्रत्यक्ष या अप्रत्यक्ष प्रेरण, कपटपूर्ण व्यवहार निविदा को किसी भी समय निरस्त करने की दिशा में ले जा सकता है एवं निविदाकार को भविष्य में केंद्रीय जल आयोग के सभी कार्यों से blacklist भी किया जा सकता है।

Canvassing, soliciting, fraud practices, suppression of facts, stating wrong facts and fraudulent practice by the tenderer may lead to rejection of the tender at any stage of the work and may lead to blacklisting for all future CWC works.

26. कोटेशन अनिवार्य रूप से **अनुलग्नक-II** के रूप में संलग्न प्रोफॉर्मा के अनुसार भरा हुआ होना चाहिए तथा फर्म के letter head पर मुद्रित होना चाहिए।

Quotations shall mandatorily be filled as per the proforma enclosed at Annexure-II and to be printed on the letter head of the firm.

विस्तृत जानकारी के लिए वेबसाइट <https://www.cwc.gov.in> एवं <https://www.eprocure.gov.in> देखें।

For more information, please visit <https://www.cwc.gov.in> and <https://www.eprocure.gov.in>

अधिशायी अभियंता/Executive Engineer

यो० एवं अ० मण्डल, के.ज. आ., फरीदाबाद /P&I Division, CWC, Faridabad

प्रतिलिपि/Copy to:

1. अधीक्षण अभियंता, योजना परिमंडल, के.ज.आ., फरीदाबाद।
Superintending Engineer, Planning Circle, CWC Faridabad.
2. उपमंडल अभियंता (मुख्यालय), योजना एवं अन्वेषण मण्डल, के.ज.आ., फरीदाबाद।
Sub-divisional Engineer (HQ), P&I Division, CWC, Faridabad.
3. उपमंडल अभियंता, पञ्चेश्वर जलविज्ञानिय प्रेक्षण उपमंडल, के.ज.आ., टनकपुर।
Sub-divisional Engineer, PHO Sub-Division, CWC, Tanakpur.
4. लेखा शाखा, योजना एवं अन्वेषण मण्डल, के.ज.आ., फरीदाबाद।
Account Branch, P&I Division, CWC, Faridabad.
5. सूचनापट्ट, योजना एवं अन्वेषण मण्डल, फरीदाबाद।
Notice Board, P&I Division, CWC, Faridabad





अनुलग्नक -II/Annexure-II

(फर्म के Letter Head पर मुद्रित किया जाना है)
(TO BE PRINTED ON LETTER HEAD OF THE FIRM)

सेवा में/To

अधिशासी अभियंता/The Executive Engineer,
योजना एवं अन्वेषण मण्डल,/Planning & Investigation Division,
केंद्रीय जल आयोग/ Central Water Commission,
फरीदाबाद / Faridabad -121001

विषय /Subject:- Quotation for “Repairing, Renovation work of existing Site Office of Pancheshwar GDS Site & Repairing of Existing Sand Filter of Pancheshwar Guest House, Central Water Commission, Champawat, Uttarakhand”

महोदय /Sir

आपके कार्यालय के कोटेशन न० 102/06/NIQ/2024-25/.....दिनांक 21.01.2025 के संदर्भ उपरोक्त विषयक कार्य के लिए निम्नलिखित दरें quote की जा रही हैं:-

With reference to your quotation no. 102/06/NIQ/2024-25/.....dated 21.01.2025 for above cited subject work we are quoting the rates as under:

Name of Work: Repairing, Renovation work of existing Site Office of Pancheswar GDS Site, Champawat, UK.							
Sr. No.	Description of work	Unit	Qty	Rate (in Rs.)		Amount (in Rs.)	
				in Figure	In Word	in Figure	in Word
1	Providing & fixing in position Super heavy PVC panel (ISI Mark) used for wall cladding at all height in approved color, texture and finish with necessary profiled edges fixed with 40mm SS screws & Aluminum Square Frames requirement in each Panel and fixed with all other fixing item as per requirement of Super heavy PVC panel All complete as per direction of the Engineer in-Charge.	sqm	84.44				
2	Providing & fixing in position Super heavy PVC panel (ISI Mark) used for ceiling, in approved color, texture and finish with necessary profiled edges fixed with 40mm SS screws & Aluminum Square Frame as requirement in each Panel and fixed With all other fixing item as per requirement of Medium heavy PVC panel. All complete as per direction of the Engineer in-Charge.	sqm	26.61				





3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:						
	1:4:8 (1 Cement: 4 coarse sand (zone-III): 8 graded stone aggregate 40 mm nominal size)	Cum	1.59				
4	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colors, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	sqm	15.93				
5	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:						
	White Vitreous China Angle back wash basin size 400 x 400 mm with single 15 mm C.P. brass pillar tap.	No.	1.00				
6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.						
	15 mm nominal Dia Pipes	mtr	5.00				
7	Providing and fixing brass bib cock of approved quality:						
	15 mm nominal bore	No.	1.00				



8	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) completes with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	No.	1.00				
Electricity Work							
9	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.						
	3 x 1.5 sq. mm	Mtr	30.00				
10	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.						
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtr	30.00				
11	Supplying and fixing 10-Watt Ceiling Light on the existing PVC Ceiling Panel including connections etc. as required.	Each	10.00				
12	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.						
	5/6 amps switch	Each	20.00				
13	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.						
	15/16-amp switch	Each	6.00				
14	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	Each	2.00				
15	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.						
	3 pins 5/6-amp socket outlet	Each	4.00				



16	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.						
	6 pins 15/16-amp socket outlet	Each	4.00				
17	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.						
	3 Module (100mmX75mm)	Each	4.00				
18	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.						
	8 Module (125mmX125mm)	Each	2.00				
19	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.						
	12 Module (200mmX75mm)	Each	2.00				
20	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.						
	Single pole	Each	6.00				
21	Supplying and fixing Cable End Box (Loose wire box) (IP 43) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with testing and commissioning etc. as required.						
	For 10-way, Double door SPN MCBDB	Each	1.00				
Part 2: Name of Work: Repairing of Existing Slow Sand Filter of Pancheshwar Guest House, Central Water Commission, Champawat, Uttarakhand.							
1	Coarse sand (zone III)	CUM	2.594				
2	Providing, Filling & Ramming of Coarse sand (zone III) (20 cm thick) as Per drawing.	Job	1				



3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :						
	1:4:8 (1 Cement: 4 coarse sand (zone-III): 8 graded stone aggregate 40 mm nominal size)	CUM	2.86				
4	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.						
	12mm cement plaster	sqm	90.000				
	Total (Part1 & Part 2)						
	GST						
	Grand Total including GST (in Rs.)						

मैंने उद्धरण केस भी नियम और शर्तें पढ़ ली हैं तथा उनका पालन करने के लिए सहमत हूं। मैंने पैन कार्ड, जीएसटी पंजीकरण की प्रतियां संलग्न की हैं।

I have read all the terms and conditions of the quotation and agreed to abide by the same. I have attached copies of PAN card, GST Registration.

(a) GST No.....

(b) PAN No.....

(c) Bank Account Details (Name, A/c No, IFSC, MICR Code).....

संलग्नपत्रादी:- उपरोक्त अनुसार

Enclosures: As above

आपका आभारी /Yours sincerely

(व्यक्ति का नाम एवं पद) /(Name and Designation of Person)

फर्म की Rubber Stamp /Rubber Stamp of the Firm





SCHEDULE-A

Schedule of Quantities

Name of Work: Repairing: Renovation work of existing Site Office of Pancheswar GDS Site, Champawat, UK.			
Sr. No	Description of work	Unit	Qty
1	Providing & fixing in position Super heavy PVC panel (ISI Mark) used for wall cladding at all height in approved color, texture and finish with necessary profiled edges fixed with 40mm SS screws & Aluminum Square Frames requirement in each Panel and fixed with all other fixing item as per requirement of Super heavy PVC panel All complete as per direction of the Engineer in-Charge.	sqm	84.44
2	Providing & fixing in position Super heavy PVC panel (ISI Mark) used for ceiling, in approved color, texture and finish with necessary profiled edges fixed with 40mm SS screws & Aluminum Square Frame as requirement in each Panel and fixed With all other fixing item as per requirement of Medium heavy PVC panel. All complete as per direction of the Engineer in-Charge.	sqm	26.61
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:		
	1:4:8 (1 Cement: 4 coarse sand (zone-III): 8 graded stone aggregate 40 mm nominal size)	Cum	1.59
4	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	sqm	15.93
5	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:		
	White Vitreous China Angle back wash basin size 400 x 400 mm with single 15 mm C.P. brass pillar tap.	No.	1.00
6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.		
	15 mm nominal dia Pipes	meter	5.00

Quarter No 1061-64, Type V,
NH-IV, N.I.T. Faridabad,
Haryana -121001
Telephone: 0129-2412576
E-mail : pi-cwc@nic.in



क्वार्टरसं 1061-64, टाइपV, एन.
एच. -IV, एन.आई.टी., फरीदाबाद
हरियाणा- 121001
दूरभाष : 0129-2412576
ईमेल : pi-cwc@nic.in



7	Providing and fixing brass bib cock of approved quality:		
	15 mm nominal bore	No.	1.00
8	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) completes with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	No.	1.00
Electricity Work			
9	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.		
	3 x 1.5 sq. mm	Meter	30.00
10	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.		
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Meter	30.00
11	Supplying and fixing 10-Watt Ceiling Light on the existing PVC Ceiling Panel including connections etc. as required.	Each	10.00
12	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.		
	5/6 amps switch	Each	20.00
13	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.		
	15/16-amp switch	Each	6.00
14	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	Each	2.00
15	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.		
	3 pin 5/6 amp socket outlet	Each	4.00
16	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.		
	6 pin 15/16 amp socket outlet	Each	4.00
17	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.		

Quarter No 1061-64, Type V,
NH-IV, N.I.T. Faridabad,
Haryana -121001
Telephone: 0129-2412576
E-mail : pi-cwc@nic.in



क्वार्टरसं 1061-64, टाइपV, एन.
एच. -IV, एन.आई.टी., फरीदाबाद
हरियाणा- 121001
दूरभाष : 0129-2412576
ईमेल : pi-cwc@nic.in



	3 Module (100mmX75mm)	Each	4.00
18	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.		
	8 Module (125mmX125mm)	Each	2.00
19	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.		
	12 Module (200mmX75mm)	Each	2.00
20	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.		
	Single pole	Each	6.00
21	Supplying and fixing Cable End Box (Loose wire box) (IP 43) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with testing and commissioning etc. as required.		
	For 10-way, Double door SPN MCBDB	Each	1.00

Part 2

Name of Work: Repairing of Existing Sand Filter of Pancheshwar Guest House, Central Water Commission, Champawat, Uttarakhand.

Si. No.	Particulars	Unit	Quantity
1	Coarse sand (zone III)	CUM	2.594
2	Providing, Filling & Ramming of Coarse sand (zone III) (20 cm thick) as Per drawing.	Job	1
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:		
	1:4:8 (1Cement: 4 coarse sand (zone-III): 8 graded stone aggregate 40 mm nominal size)	CUM	2.86
4	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.		
	12mm cement plaster	sqm	90.00



(अनुलग्नक –I/Annexure-I)

Picture Diagram of Sand Filter Water Tank:

