

GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
LOWER GODAVARI SUB DIVISION-I
Opp.Sub Collector's Office
BHADRACHALAM - 507111

NO: LGSD-I / A - 12 / 2012/ 739-47

Dated: 3/12/2012

To,

Subject:- Notice Inviting Quotations for laying of Cement Concrete road at LGSD-I,Bcm- reg

Sirs,

Sealed quotations are invited for laying of Cement Concrete approach road from gate to office building at LGSD-I,CWC, Bhadrachalam. The sealed quotations should reach this office by 1430hrs on Dt. 17/12/2012. The quotations will be opened on the same day at 15.00 Hrs. You are requested to be present yourself or sent your authorized representative to this office at the time of opening of quotations.


Sl. No.	Description of work	Unit	Quantity.	Rate	Amount
As enclosed					

Terms & Conditions:

1. The sealed envelope contained quotations should be super scribed "**Quotations for the work of laying of Cement Concrete road at LGSD-I,CWC Bhadrachalam**" due for opening on 22.12.2012 at 1600 hrs.
2. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
3. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment, etc.
4. An EMD of 2% on quoted total amount shall be enclosed in the form of DD in favor of Executive Engineer, LGD, CWC, Hyderabad payable at Hyderabad. The EMD of unsuccessful bidder will be returned back immediately after finalization of bids. The EMD of the successful bidder will be released on completion of the work in all respect.
5. Successful Bidder need to submit the Security Deposit @ 10% of Quotation amount. Security Deposit will be release after 6 months from the date of completion of the work.
6. All the debris and un-used materials etc. should be removed from the work site as soon as the work is completed. No extra charges will be paid for this purpose.
7. No T&P materials for any work including scaffolding/shuttering etc, will be provided by this department for the above said works.
8. The curing of the cement works should be done as per the standards by the contractor.
9. Materials to be used in the construction must be standard and approved ISI Code. The work should be standard and as per our description. The defective and sub-standard work is liable for rejection and same


should be made good as per our requirement by contractor himself on his own expenditure, for which no extra payment will be made.

10. The work should be completed within the 45 days of work order placed. No time extension will be given for completion of work until and unless beyond control of human beings.
11. The work will be inspected by the authorized representative of this Department and get himself satisfied.
12. After satisfactory completion of the works in all respects, the bill in triplicate may be submitted for payment to the undersigned.
13. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
14. However payment will be made on actual measurements only.
15. VAT 5%, Income Tax 2.0%, (3% Educational Cess on IT) and Labour Cess 1% and other taxes, if any shall be deducted from the bill.
16. The Contractor must submit the proper Registration and work permit, Pan/Tan number.
17. This Department is not responsible for any accidents/losses to workers engaged in this work.
18. This office reserves the right to reject any one or all quotations without assigning any reasons there of.


Sub-Divisional Engineer
(R.N. RAMESH BABU)
Sub-Divisional Engineer
LGSD. 1/CWC/Bhadrachalam

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimates/2012-13/ 3598 - 02, dated 31.10.2012.
3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO web site.
4. O/o The Sub Collector, Bhadrachalam, for wide publicity.
5. O/o The Mandal Revenue Officer, Bhadrachalam, for wide publicity.
6. O/o The Project Officer, ITDA, Bhadrachalam, for wide publicity.
7. Notice Board.


Sub-Divisional Engineer
Sub-Divisional Engineer
LGSD. 1/CWC/Bhadrachalam

DETAILED ESTIMATE

NAME OF WORK : CC approach road from gate to office building at LGSD-I,Bhadrachalam

LOWER GODAVARI SUB-DIVISION NO.1, BHADRACHALAM

S.No	DESCRIPTION	No	L	B	D	QUANTITY	UNITS
1	Preparation and consolidation of sub grade with power roller of 8 to 10 tonne capacity after excavating earth to an average of 22.5 cm depth,dressing to camber and consolidating with road roller including making good the undulations etc. and re rolling the sub grade and disposal of surplus earth with lead upto 50 metres. (DSR page: 263 Code: 16.1) Earth work excavation for laying CC road a) From bore well to cellar	1	39.0	3.70		144.30	Sq.mts
	TOTAL					144.30	Sq.mts
2	Laying,spreading and compacting stone aggregate of specified sizes to WBM specification in uniform thickness, hand picking rolling,watering and compacting to the required density. (DSR page: 263 Code: 16.4)	1	39.0	3.70	0.23	33.19	Cum
	TOTAL					33.19	Cum
3	Supply and laying of 125 micron thick polythene film over surface of WBM. (Not in DSR)	1	95.0	3.70		351.50	Sq.mts
	TOTAL					351.50	Sq.mts
4	Providing and laying design mix cement concrete of M-30 grade using cement content as per design mix,using coarse sand and graded stone aggregate of 40mm size laying at site, spreading and compacting mechanically,levelling to required slope/camber, finishing with required texture,including steel form work,curing,making provision for contraction/expansionjoints. Cement concrete prepared with batch mixing machine (DSR page: 269 Code: 16.43.1)	1	95.0	3.50	0.15	49.875	Cum
	TOTAL						Cum
5	Providing and laying in position bitumen hot sealing compound for expansion joints etc. (one for every three mts.length) using grade A sealing compound. (DSR page: 269 Code: 16.46.1)	31	3.5	15cm		1627.50	per cm depth per cm width per m length
6	VAT @ 5%						
7	ST @ 4.95%						