## GOVT. OF INDIA CENTRAL WATER COMMISSION WAINGANGA DIVISION

GRAM: HYDRONET, NAGPUR TEL/FAX: (0712) 2510156

CGO COMPLEX BLOCK "C" I I nd FLOOR SEMINARY HILLS, NAGPUR – 440 006

No. WD/NAG/HQJE/JE-34/2014-15/275-77

NOTICE INVITING QUOTATION

Date: 22-02-2015

Sealed quotations are hereby invited from registered firms/reputed parties to carry out the following works as per the terms and conditions described below:

Sl No.	Description of works	Quantity	Estimated cost	Time of 1 d
1.	Construction of Compound Wall at Site no.117, Salebardi under UWSD,CWC, Nagpur	As per enclosed schedule		Time of completion 30 days

## Terms and conditions:

1. The rates must be quoted for each item separately.

2. The rates should be inclusive of all taxes. No extra payment on any account will be made.

3. The work should be completed as per the drawing and specifications, otherwise liable for rejection.

4.Income tax as per prevailing rates will be deducted at source. PAN no. must be informed for submission of TDS return to I.T.Deptt.

5.Pre-receipted bill in triplicate as per actual quantity of work will have to be submitted for making payment after satisfactory completion of the work.

6.Payment will be made by Cheque / Demand Draft.

7.Earnest money deposit of Rs.10000/- in the form of Demand Draft payable in favour of Ex.Engr.Wainganga Dn.CWC Nagpur should be enclosed alongwith the quotation.Quotations without required EMD will not be considered and rejected.

Sealed quotation duly super scribed "Construction of Compound Wall at Site no.117
Salebardi under UWSD CWC, Nagpur" will be received by the undersigned till 15.00 hours of 07-032015 and will be opened on the same day at 15.30 hours in the presence of parties. Quotations received
after the schedule time of opening will not be considered. The undersigned reserves the right to reject any
or all the quotations without assigning any reasons thereof.

(A.S.Banode)
Executive Engineer

Copy to :- 1. The Superintending Engineer (C), M.C.O. C.W.C. Nagpur for uploading on CWC website.

The Assistant Engr. UWSD/LWSD/WSD/PGSD, CWC, Nagpur/Chandrapur/Yavatmal for information and publicity.

3. Office Notice Board.

AQ: 12.3

2/3

## SCHEDULE OF ITEMS & QUANTITY

Name of work: Construction of compound wall at site 117, Salebardi.

SI. No	Description of Item	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1.	Site clearance such as dismantling of old fencing & barbed wire etc.	135.00	1.0		
2.	Earth work excavation for foundation in all kinds of soil for R.C.C Columns	20.56	L.S.		
3.	Filling available excavated earth in trenches.	14.02	m <sup>3</sup>		
-4.	Providing and laying coping for foundation with P.C.C. 1:3:6 using 40mm HBG excluding the cost of centering and shuttering etc. complete	2.42	m³		
5.	Reinforcement for the RCC works including straightening, cutting, bending, placing in position and binding all complete.	1349.40	kg		
6.	Reinforcement Cement concrete work in CC 1:2:4 with 20 mm size stone aggregate for footing for pillars.	14.68	m³		
7.	Centering and shuttering including strutting  propping etc. and removal of form.  d) For RCC column  e) For plinth beam  f) For coping over wall	86.24 62.10 37.59	m <sup>2</sup>		
8.	Providing Brick work in C.M. 1:6, with F.P.S bricks of class designation 75 in foundation and plinth.	21.58	m³		
9.	Providing and laying coping for compound wall with P.C.C. 1:3:6 using 20mm HBG excluding the cost of centering and shuttering etc. complete	1.55	m <sup>3</sup>		
10.	Finishing / laying cement plastering 1:6  Brick wall of 15 mm thick  Coping of 12 mm thick	405.00 42.53	m²		
	Laying cement plaster for Plinth beam in CM 1:3 of 6mm thick	77.63	m <sup>2</sup>		

(Ru	pees			

Signature Of Contractor

## CTAILS OF COMPOUND WALL AT STIE-117, SALEBARDI

