

Fax: 0364-2521226

TEL : 0364-2521713



GOVERNMENT OF INDIA  
CENTRAL WATER COMMISSION  
MEGHNA INVESTIGATION DIVISION  
MEGHALAYA STATE HOUSING FINANCING CO-OPERATIVE  
SOCIETY Ltd. BUILDING, 4<sup>TH</sup> FLOOR, NONGRIM HILLS,  
SHILLONG-793 003

No. MID/JE(HQ)/NIQ/2015-16/1412-17

Dated: 19<sup>th</sup> June, 2015

### **NOTICE INVITING QUOTATION**

Sealed quotations are hereby invited by the undersigned on behalf of the President of India for following works as detailed below. **The quotations should reach in the office of the undersigned on or before 09.07.2015 up to 15.00 hrs** and will be opened on the same day i.e. **09.07.2015 at 15.30 hrs** in the presence of quotationers or their authorized representatives, if any.

The undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.

Sl. No.	Description and specifications of item	Quantity	Unit
1.	Construction of Approach path/CC step at Dholai site as per the drawing attached as Annexure- 1	1	no

**Estimated cost:** Rs.26,800/-(Rupees Twenty six thousand eight hundred) only.

### **Terms & Conditions:**

1. The quotations duly signed should be properly sealed and dropped in quotation Box in the office of the Executive Engineer, Meghna Investigation Division, CWC, Nongrim hills, Shillong-793003. The sealed envelope should be superscribed **"Construction of Approach path/CC step at Dholai site due on 09.07.2015"**.
2. In the event of the date of opening of quotation being a holiday, quotations will be opened on the next working day with timings unchanged .
3. A bid security of Rs. 550/- (Rupees Five hundred fifty) only shall be deposited in the form of an Account payee demand Draft/Banker's cheque from a schedule bank in the favour of "Executive Engineer, MID, CWC, Shillong.
4. Quotationers must have PAN/TIN/Service Tax number/VAT.
5. The undersigned does not bind himself to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.
6. All materials required for the work are to be supplied by the contractor. The material must be of standard quality and as per specifications and free from all defects. The material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges.
7. Before starting the work, material shall be got approved from the Sub Divisional Engineer, MISD-III, CWC, Shillong.
8. The material shall have a warranty period of minimum one year from the date of installation.
9. The work is estimated to cost Rs.26800/-(Rupees Twenty six thousand eight hundred) only. This estimate however, is given merely as rough guide.
10. The quantity of materials may be increased or decreased at the time of work order without assigning any reason thereof.

11. The work of Construction of Approach path/CC step at site location in all respects should be completed within 20 days from the date of issue of work order. The rate quoted should be inclusive of all duties, taxes and other levies (except octroi and sales tax/VAT) as applicable.
12. The validity of quotation for acceptance shall be 90 days and rate quoted should be remain valid for 180 days from the date of opening.
13. The rate should be quoted both in words and in figures. Corrections/ overwriting in the quotation, if any, shall be made by initialing, dating and re-writing.
14. The payment will be made by account payee cheque for local supplier or by Demand Draft for outstation supplier on production of pre-receipted bill in triplicate only after satisfactory supply of the materials in good condition and as per specification.
15. TDS shall be deducted from the bill at the time of payment as per latest Govt. orders.

**Sd/-**  
**Executive Engineer**  
**MID, CWC, Shillong**

**Copy to:**

1. The Superintending Engineer, Meghna Circle, CWC, Panchayat Road, Silchar(Assam).
2. The Executive Engineer, Meghna Division, CWC, Silchar.
3. The Sub Divisional Engineer, MISD-III, CWC, Silchar.
4. The AAO, Accounts Branch, Meghna Investigation Division, CWC, Nongrim hills, Shillong-793003 with the request to present at the time of opening of quotation.
5. Notice board of office of Executive Engineer, Meghna Investigation Division, Nongrim hills, Shillong-793003.
6. Drawing Branch, MID, CWC, Shillong.

## Schedule of Quantity

**State: Central**

**Sub Division: MISD-III, CWC, Silchar**

**Branch: CWC**

**Division : MID, CWC Shillong**

**NAME OF WORK:- Construction of Approach path/CC step at Dholai site (Dist. Cachar)**

Sl No.	Description and specification of item	Unit	Qty	Rate (Rs)	Amount (Rs)
1.SR -1.1 (b) P-45	Earthwork in excavation for foundation trenches of walls, retaining walls, footing of column, steps, septic tank etc. including refilling (return filling ) the quantity as necessary after completion of work breaking clods in return filling, dressing watering and ramming etc, and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified.(a) Up to a depth of 2.00m below the existing G.L. in hard/dense soil	cum	8.393		
2.SR -4.1.1 P-71(b)	Providing brick soling in foundation & under layer with stone/best quality picked jhama bricks, sand packed and laid to level and in panel after preparing the sub grade as directed including all labour & materials and if necessary dewatering complete. (b) Brick on edge soling.	Sq.m	12.54		
3.SR 3.1.1 (i)P-59	Providing form work of ordinary timber planking so as to give a rough finish including centering, shuttering, strutting and propping etc. height of propping and centering below supporting floor to ceiling not exceeding 4.0 m and removal of the same for in-situ reinforced concrete and plain concrete work in using 38 mm thick plank.	Sq.m	8.302		
4.SR -2.1.1 (a)P-51	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brickworks etc. as directed and specified including dewatering if necessary, and curing complete( shuttering where necessary shall be measured and paid separately) in proportion 1:3:6.	cum	2.876		
5.SR -6.2.3 (a), P-108	15 mm thick cement plaster in single coat on rough side of single or brick wall for interior plastering up to 1 <sup>st</sup> floor level including arises, internal rounded angles, not exceeding 80 mm girth & finished even & smooth including curing complete as directed (as per APWD SOR-2010-11). a) In cement mortar 1:3.	Sq.m	15.566		
	<b>Total</b>				

(Rupees )

**Signature of contractor**

**Ex. Engineer**