Phone: 040-23308649

Fax-040-23308652

GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
LOWER GODAVARI DIVISION
OFFICE OF THE EXECUTIVE ENGINEER

Krishna Godavari Bhawan,
H.No 11-4-648, III Floor,A.C. Guards,
Hyderabad-500004.

No: LGD/DB/Est /2013-14/ 199-207

Date: 29/01/2014

Notice Inviting Quotations

Sealed quotations are hereby invited by the undersigned on behalf of the President of India for "**Providing Civil Works for restoration of Telemetry Stations under LGSD-I/Bhadrachalam**" from the approved and eligible contractors of CPWD/State Irrigation/PWD Departments. The quotations should reach in the office of the undersigned on or before at 10-02-2014 up to 1500 hrs and will be opened on the same day at 1530 hrs.

Sl. No.	Name of work and location	Estimated cost	Time allowed
1.	**Providing Civil Works for restoration of Telemetry Stations under LGSD-I/Bhadrachalam** (Schedule of Quantities enclosed)	**Rs.3,64,000 (Rupees three lakh Sixty four thousands only)**	**45 Days**

Terms & Conditions:

1. The quotations duly signed, should be properly sealed and dropped in quotation box in the office of the Executive Engineer, Lower Godavari Division, Central Water commission, Krishna Godavari Bhavan, AC Guards, Hyderabad-500004. The sealed envelops should be super scribed "Providing civil works for restoration of telemetry stations under LGSD-I/Bhadrachalam."
2. In the event of opening of quotation being a holiday will be opened on the next working day with timings unchanged.
3. Quotationers must have PAN number and the copy of the same is to be submitted.
4. The undersigned does not bind him self to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.
5. No tools and plants shall be issued to the contractor.
6. Before starting the work, material shall be got approved from the concerned SDE.
7. The time of completion shall be strictly adhered.
8. The date of start shall be reckoned from the day of date of issue of work order.

9. All materials required for the work are to be supplied by the contractor. The material must be standard quality and as per specifications and free from all defects. The material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges. The work shall have a warranty period of minimum six months from the date of completion.
10. Before starting the work, material shall be got approved from SDE.
11. The quantity of work may be increased or decreased at the time of order without assigning any reason thereof.
12. The rate quoted should be inclusive of all duties, taxes and other levies as applicable. No other incidental charge, whatsoever will be entertained.
13. The validity of quotation for acceptance shall be 90 days and rates quoted should remain valid for 180 days from the date of opening.
14. The rate should be quoted both in words and in figures. Correction/overwriting in the quotation if any shall be made by initialing, dating and re-writing.
15. The payment will be made by Account payee cheque drawn on SBI, Red hills Branch, Hyderabad on production of pre-receipted bill in triplicate only after satisfactory completion of the work as per specifications.
16. TDS shall be deducted from the bill at time of payment as per latest Govt. orders.
17. The security Deposit @ 10% of bill amount will be deducted from the bill and will be released after 6 months from the date of completion of work and on satisfaction of the work done.

Encl: - Schedule of quantities

Executive Engineer
Lower Godavari Division

Copy for information to:-

1. The superintending Engineer, Godavari Circle, CWC, Hyderabad with a request to arrange to publish the same in CPP portal.
2. The Deputy Director, O/o The Chief Engineer, KGBO, CWC, Hyderabad for updating the same in KGBO website.
3. Executive Engineer, Upper Godavari Division, CWC, Hyderabad for information.
4. The Sub Divisional Engineer ,ISD/Jagdalpur
5. The Sub Divisional Engineer,LGSD-1/Bhadrachalam
6. The Sub Divisional Engineer, LGSD-II /Rajahmundry
7. The AAO, Accounts Branch, LGD, CWC, Hyderabad.
8. Notice Board.

Schedule Of Quantities

Name of work: Restoration of Telemetry Stations at various sites under LGSD I Bhadrachalam

S.No	Description of Item	Qty	Unit	Rate	Per	Amount in Figures	Amount in Words
1 a)	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.All kinds of soil						
	For foundation block accommodating solar panel						
	For site Dummugudem	0.396	Cum				
	For site Taliperu	0.396	Cum				
	For site Eturunagaram	0.396	Cum				
	For site sangam	0.396	Cum				
	For site Bhadrachalam	0.396	Cum				
	Total Quantity	**1.980**	**Cum**		**Cum**		
1(b)	Excavating trenches of required width for pipes, cables, etc including eaxcavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m. Pipes, cables etc. exceeding 80 mm dia but not exceeding 300 mm dia						
	For site Dummugudem	120.00	meter				
	For site Taliperu	100.00	meter				
	For site Eturunagaram	100.00	meter				
	For site sangam	110.00	meter				
	For site Bhadrachalam	40.00	meter				
	For site Perur	100.00	meter				
	Total Quantity	**570.00**	**meter**		**meter**		

Signture of the Contractor

Date

.No	Description of Item	Qty	Unit	Rate	Per	Amount in Figures	Amount in Words
2	Providing and fixing GI pipes complete with GI fittings item no 18.12.4 DSR 2013 32 mm dia nominal bore						
	For site Dummugudem	120.00	meter				
	For site Taliperu	100.00	meter				
	For site Eturunagaram	100.00	meter				
	For site Perur	40.00	meter				
	Total Quantity	**360.00**	**meter**		**meter**		
3	Filling available excavated earth (excluding rock) in trenches, plinth,sides of foundatios etc. in layers not exeeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50m and lift upto 1,5m						
	For site Dummugudem	120.00	meter				
	For site Taliperu	100.00	meter				
	For site Eturunagaram	100.00	meter				
	For site sangam	110.00	meter				
	For site Bhadrachalam	40.00	meter				
	For site Perur	100.00	meter				
	Total Quantity	**570.00**	**meter**		**meter**		
4	Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete.						
	For foundation block accommodating solar panel						
	For site Dummugudem	0.036	Cum				
	For site Taliperu	0.036	Cum				
	For site Eturunagaram	0.036	Cum				
	For site sangam	0.036	Cum				
	For site Bhadrachalam	0.036	Cum				
	Total Quantity	**0.180**	**Cum**		**Cum**		

Signture of the Contractor
Date

.o	Description of Item	Qty	Unit	Rate	Per	Amount in Figures	Amount in Words
5	Providing and laying cement concrete in retaining walls, return walls,(any tnickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., upto floor five level, excluding the cost of centering, shuttering and finishing. 1:2:4 (1 Cement: 2 Coarse sand; 4 graded stone aggregate 20 mm nominal size)						
	For site Dummugudem	2.632	Cum				
	For site Taliperu	1.868	Cum				
	For site Eturunagaram	0.524	Cum				
	For site sangam	0.515	Cum				
	For site Bhadrachalam	0.524	Cum				
	Total Quantity	**6.063**	**Cum**		**Cum**		
6	Providing 101.6mm (4 Inches) Φ GI Pipe - Class'B' of ISI Mark						
	For site Dummugudem	6.00	meter				
	For site Taliperu	6.00	meter				
	For site Eturunagaram	6.00	meter				
	For site sangam	6.00	meter				
	For site Bhadrachalam	6.00	meter				
	Total Quantity	**30.00**	**meter**		**meter**		
7	Providing M.S. End plate at top and bottom including welding charges - Complete						
	For site Dummugudem	2	Nos				
	For site Taliperu	2	Nos				
	For site Eturunagaram	2	Nos				
	For site sangam	2	Nos				
	For site Bhadrachalam	2	Nos				
	Total Quantity	**10**	**Nos**		**Nos**		
8	Providing M.S.hold fasts at bottom including welding charges - Complete						
	For site Dummugudem	4	Nos				
	For site Taliperu	4	Nos				
	For site Eturunagaram	4	Nos				
	For site sangam	4	Nos				
	For site Bhadrachalam	4	Nos				
	Total Quantity	**20**	**Nos**		**Nos**		

Signture of the Contractor
Date

o	Description of Item	Qty	Unit	Rate	Per	Amount in Figures	Amount in Words
9	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, Pillars, Piers, Abutments, Posts and Struts						
	For site Dummugudem	0.90	Sqm				
	For site Taliperu	0.90	Sqm				
	For site Eturunagaram	0.90	Sqm				
	For site sangam	0.90	Sqm				
	For site Bhadrachalam	0.90	Sqm				
	Total Quantity	**4.50**	**Sqm**		**Sqm**		
10	18 mm Cement Plaster in two coats under 12 mm thick cement plaster 1:5 (1 cement 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement 6 fine sand)						
	For site Dummugudem	1.095	Sqm				
	For site Taliperu	1.095	Sqm				
	For site Eturunagaram	1.095	Sqm				
	For site sangam	1.095	Sqm				
	For site Bhadrachalam	1.095	Sqm				
	Total Quantity	**5.475**	**Sqm**		**Sqm**		
11	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm)						
	For site Dummugudem	1.095	Sqm				
	For site Taliperu	1.095	Sqm				
	For site Eturunagaram	1.095	Sqm				
	For site sangam	1.095	Sqm				
	For site Bhadrachalam	1.095	Sqm				
	Total Quantity	**5.475**	**Sqm**		**Sqm**		
12	Providing and fixing solar panel mounting hardware with necessary clamps etc .						
	For site Dummugudem	1	No				
	For site Taliperu	1	No				
	For site Eturunagaram	1	No				
	For site sangam	1	No				
	For site Bhadrachalam	1	No				
	Total Quantity	**5**	**Nos**		**Nos**		

Signture of the Contractor
Date

No	Description of Item	Qty	Unit	Rate	Per	Amount in Figures	Amount in Words
13	Supplying, assembling, lowering, and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer - in - charge. 150 mm nominal size (for bubbler termination block)						
	For site Eturunagaram	4.00	meter				
	For site sangam	2.00	meter				
	For site Bhadrachalam	4.00	meter				
	For site Perur	4.00	meter				
	Total Quantity	**14.00**	**meter**		**meter**		
14	Supplying and laying of cement concrete pipes of height 1 feet and 3 feet dia in vertical position for bubler termination block as directed by the engineer in charge						
	For site Dummugudem	8	Nos				
	For site Taliperu	4	Nos				
	Total Quantity	**12**	**Nos**		**Nos**		
	Grand Total						

Signture of the Contractor
Date