



No. LGSD-II / AC- 24 / 2013 - 14/1276-88  
 Government of India  
 Central Water Commission  
 Lower Godavari Sub Division No-II



Phone: 0883 2468753  
 FAX: 0883 2468753  
 Email: aecwc\_rjy@yahoo.com

Opp. RTC Bus Complex,  
 Danavaiah Pet Post.  
 Rajahmundry -533 103.  
 Date: 23.12.2013

**NOTICE INVITING QUOTATIONS**

**Sub: Quotation for the work of Erection of steel gate & Fencing on river side premises at Site Potteru, Malkangiri District, Odisha.**

Sir(s)

Sealed quotations are invited on behalf of President of India for the work of "Erection of steel gate & Fencing on river side premises at site Potteru, Malkangiri District, Odisha", so as to reach this office by 15:30 hrs on 08.01.2014. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus soil as directed within a lead of 50m All kinds of soil. (Code2.8.1) Net Quantity	2.106		Cum	
2	Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete. - For gate pillars (Code2.27) Net Quantity	0.162		Cum	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) - For foundation bed concrete - For gate pillars (Code: 4.1.6) Net Quantity	0.324		Cum	
4	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in : Cement mortar 1:4 (1 cement : 4 coarse sand) - For 1 <sup>st</sup> footing - For gate pillars (Code: 6.1.1) Net Qty	0.504		Cum	
5	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor block 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) (Code: 4.2.3) Net Quantity	0.729		Cum	
	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in :				



	Cement mortar 1:4 (1 cement : 4 coarse sand) - For pillar - (Code: 6.4.1) <b>Net Quantity</b>	0.608		Cum	
7	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. as required - complete.(code: 16.19) <b>Net Quantity</b>	75.60		Kg	
8	1.2m high fencing with 1.8m angle iron 40x40x6mm posts placed every 3m centre to centre embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire 9.38 kg per 100 m (minimum) between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately) With G.I. barbed wire Code:16.18.1) <b>Net Quantity</b>	150.00		m	
9	12 mm cement plaster of mix :1:6 (1 cement : 6 coarse sand) (code: 13.4.2) <b>Net Quantity</b>	7.965		Sqm	
10	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth: consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m (code: 2.25) Net Quantity =Item No. 1a - (Sum of Item No.s 2 +3+4) <b>Net Quantity</b>	0.630		Cum	
11	Finishing walls with water proofing cement of required shade New work (Two or more coats applied @3.84 kg/10 sqm (Code 13.44.1) <b>Net Quantity</b>	7.965		Sqm	
12	Applying priming coat : With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel work (second coat) (Code :13.50.4) For fencing poles and struts & For small gate on river side <b>Net Quantity</b>	4.021		Sqm	
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work (Code : 13.61.1) For fencing poles and struts & For small gate on river side - Same as Item No. 12 <b>Net Quantity</b>	4.021		Sqm	
	<b>Total</b>				

**Terms & Conditions:**

1. The sealed envelope contained quotations should be super scribed "Erection of steel gate & Fencing on river side premises at site Potteru, Malkangiri District, Odisha."
2. The work will be carried out at Site No. 123, Potteru, Malkangiri District, Odisha State, and executed by the Site - in-charge in all stages.
3. The Security Deposit of 10% may be deducted from the bill and will be released after six months completion of the work satisfactorily. If, any damage/penalty to the Government property, it will be adjusted from the security deposit.
4. The work should be completed within 25 days of work order placed. No time extension will be given for completion of the work until and unless beyond the control of human beings.
5. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment etc.



6. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
7. No T&P materials for any work including scaffolding/shuttering will be provided by this department for the above works.
8. The curing of the cement works should be done as per the standards by the contractor.
9. After satisfactory completion of the work in all respects, bill in triplicate may be submitted for payment.
10. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
11. However payment will be made on actual measurements only.
12. This office reserves the right to reject any one or all quotations without assigning any reasons there of.

Sd/-  
Sub-Divisional Engineer

To  
M/s.

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimate/2013-14/ 3366 - 68, dated 10.12.2013.
- ✓ 3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO Web site.
4. O/o The Superintending Engineer, Irrigation Circle, Dowlaiswaram, for wide publicity.
5. O/o The Assistant Engineer, Investigation Sub Division, Gandhipuram-3, N.W.D.A., Rajahmundry, for wide publicity.
6. O/o The Assistant Engineer, CPWD, Income Tax Office Complex, Rajahmundry for wide publicity.
7. O/o The Mandal Revenue Officer, Rajahmundry, for wide publicity.
8. The Junior Engineer, Site 73, Saradaput for information and for wide publicity.
9. The Sit-in-Charge, Site-123, Potteru for information and for wide publicity.
10. Notice Board

Sd/- 20/12  
Sub-Divisional Engineer