



No. LGSD-II / AC- 24 / 2013 - 14/1289-99

Government of India

Central Water Commission

Lower Godavari Sub Division No-II



Phone: 0883 2468753

FAX: 0883 2468753

Email: aecwc\_rjy@yahoo.com

Opp. RTC Bus Complex,

Danavaiah Pet Post.

Rajahmundry -533 103.

Date: 23.12.2013

**NOTICE INVITING QUOTATIONS**

**Sub: Distempering, White washing & Painting of Sub-Division Office building & Front Side Compound wall at LGSD-II, CWC, Rajahmundry.**

Sir(s)

Sealed quotations are invited on behalf of President of India from the registered contractors/ firms for the work of "Distempering, White washing & Painting of Sub-Division Office building & Front side compound wall at LGSD-II, CWC, Rajahmundry", so as to reach this office by 15.30 hrs on 08.01.2014. The quotations will be opened by the undersigned on the same day at 16.00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
I	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete - For ceiling (Code : 14.43) Total ceiling area	217.488		Sqm	
II	Removing dry or oil bound distemper, water proofing cement pain and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. (Code : 14.46) Total area = {Total inside area + Total outside area }	1116.910		Sqm	
III	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats) (Code : 14.45.1) Total inside area	793.730		Sqm	
IV	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat. (Code : 14.64.1) Total area = Total outside area = 540.668 Sqm	540.668		Sqm	
V	Finishing walls with Acrylic Smooth exterior paint of required shade : For Compound wall				

	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) (Code : 13.46.1)	353.873		Sqm	
VI	Painting with synthetic enamel paint of approved brand and brand and manufacture of required colour to give an even shade : One or more coats on old work (Code : 14.54.1)				
	Total painting area	94.555		Sqm	
	Total				

**Terms & Conditions:**

1. The sealed envelope contained quotations should be super scribed "Distempering, White washing & Painting of Sub Division Office building & Front side compound wall at LGSD-II, CWC, Rajahmundry"
2. An EMD of 2% on quoted total amount shall be enclosed in the form of DD in favor of Executive Engineer, LGD, CWC, Hyderabad payable at Hyderabad. The EMD of unsuccessful bidder will be returned back immediately after finalization of bids. The EMD of the successful bidder will be released on completion of the work in all respect.
3. 2% Income Tax & other taxes as applicable shall be deducted from the total amount.
4. The work will be carried out at Lower Godavari Sub Division No. - II Office, CWC, Rajahmundry, and will be inspected by the by the authorised representative of this Department and get himself be satisfied in all stages.
5. The Security Deposit of 10% may be deducted from the bill and will be released after six months completion of the work satisfactorily. If, any damage/penalty to the Government property, it will be adjusted from the security deposit.
6. The work should be completed with in 25 days of work order placed. No time extension will be given for completion of the work until and unless beyond the control of human beings.
7. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment etc.
8. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
9. No T&P materials for any work including scaffolding/shuttering will be provided by this department for the above works.
10. The curing / watering work should be done as per the standards by the contractor.
11. After satisfactory completion of the work in all respects, bill in triplicate may be submitted for payment.
12. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
13. However payment will be made on actual measurements only.
14. This Department is not responsible for any accidents / losses to the workers engaged in this work.
15. This office reserves the right to reject any one or all quotations without assigning any reasons there of.

sd/-  
Sub-Divisional Engineer

To  
M/s.



Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimate/2013-14/ 3366 - 68, dated 10.12.2013.
- ✓ 3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO Web site.
4. O/o The Superintending Engineer, Irrigation Circle, Dowlaiswaram, for wide publicity.
5. O/o The Assistant Engineer, Investigation Sub Division, Gandhipuram-3, N.W.D.A., Rajahmundry, for wide publicity.
6. O/o The Assistant Engineer, CPWD, Income Tax Office Complex, Rajahmundry for wide publicity.
7. O/o The Mandal Revenue Officer, Rajahmundry, for wide publicity.
8. Notice Board

*[Signature]*  
23/12/13  
Sub-Divisional Engineer