

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
हिमालयी गंगा मंडल हरिद्वार



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Himalayan Ganga Division, Haridwar

कोटेशनआमंत्रण सूचना

भारत के राष्ट्रपति की ओर से, अधिशासी अभियंता, हिमालयी गंगा मंडल, केन्द्रीय जल आयोग, हरिद्वार द्वारा "भागीरथी उपमंडल, केन्द्रीय जल आयोग, टिहरी के अंतर्गत स्थल देवप्रयाग में टारगेट पोस्ट तथा लकड़ी के गेज पोस्ट की स्थापना, पेंटिंग व मार्किंग" के सम्बन्ध में अनुभवी एवं योग्य एजेंसियों से नीचे उल्लेखित नियम व शर्तों के अनुसार दिनांक 22.05.2023 (यदि अवकाश है तो अगला कार्य दिवस) को 15:00 बजे तक मुहरबंद कोटेशन आमंत्रित की जाती है। कोटेशन उसी दिन फर्मों के प्रतिनिधि (यदि कोई हो तो) की उपस्थिति में 16:00 बजे खोली जायेगी।

क्र. सं.	कार्य का विवरण	मात्रा	मात्रा	राशि (Rs.)	कुल राशि
1	Demolishing R.C.C. work manually/mechanical means including stacking of steel bars, disposal of unserviceable material within 50 meters lead as per direction of Engineer - in- charge.	3.69	cum		
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sq m on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in charge. The Soil is Ordinary	12.08	cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources). Leveling of gauge post to keep required level including proper overlapping as per direction of Engineer - in- charge.	9.60	cum		
4	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns	46.8	sqm		
5	Surface dressing of the ground including removing vegetation and in equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift up to 1.5 m. All kinds of soil as per direction of Engineer - in- charge.	100	sqm		
6	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. 7.2.1 Cement mortar 1:6 (1 cement : 6 coarse sand) as per direction of Engineer - in- charge.	2	cum		



भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
हिमालयी गंगा मंडल हरिद्वार



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Himalayan Ganga Division, Haridwar

7	Painting and marking of gauge post 1.8 m long with synthetic enamel of approved brand & manufacture to give an even shade by two or more coats and marking the gauge with japan paint, Red, Black and White with standard metric gradation marking of 10mm thickness in black & white alternately & red synthetic enamel of width 10mm at every 100mm etc complete. as per direction of Engineer - in- charge.	40	nos		
8	Painting and marking with synthetic enamel of approved brand & manufacture to give an even shade by two more coats.	11.02	Sqm		
8	Structure steel work riveted bolted or weld in built up section, trusses and framed work, including cutting hoisting ,fixing in position and applying a priming coat of approved steel primer all complete	360.57	Kg		
9	Gauge Transportation Charge	25	Nos		
			Total		
	GST @ 12% (for Sl. No. 1 to 9)				
			G. Total		

नियम एवं शर्तें -

- दरे आकड़ों एवं शब्दों दोनों में उद्धृत किया जाना चाहिए, किसी भी प्रकार की overwriting एवं cutting हस्ताक्षरित होना चाहिए।
- कोटेशन के लिफाफे के ऊपर "भागीरथी उपमंडल, केन्द्रीय जल आयोग, टिहरी के अंतर्गत स्थल देवप्रयाग में टारगेट पोस्ट तथा लकड़ी के गेज पोस्ट की स्थापना, पेंटिंग व मार्किंग" लिखा होना चाहिए।
- कोटेशन अधिशासी अभियंता, हिमालयी गंगा मंडल, हरिद्वार, एन-81, शिवालिक नगर, हरिद्वार के पते पर संबोधित होना चाहिए।
- केवल GST नंबर वाली फर्म ही कोटेशन प्रस्तुत करने के पात्र है।
- समान कार्यों में अनुभव होना चाहिए।
- बोलीदाता द्वारा किसी भी कार्य दिवस में सुबह 09:00 बजे से शाम 05:00 बजे के मध्य, स्थल (देवप्रयाग) पर उपस्थित होकर स्थलों की स्थिति का जायजा ले सकते हैं इसके लिये बोलीदाता स्थलों से सम्बंधित किसी भी जानकारी के लिये 'भागीरथी उपमंडल, केन्द्रीय जल आयोग, भागीरथी पुरम टिहरी (उत्तराखंड) से संपर्क कर सकता है। स्थलवार कार्यों का विवरण अनुलग्नक-1 में संकलित है।
- बयाना राशि रुपये 4000/- (चार हजार मात्र) अधिशासी अभियंता, हिमालयी गंगा मंडल, केन्द्रीय जल आयोग, हरिद्वार के पक्ष में एफ.डी.आर. के रूप में NIG के साथ जमा किया जाना चाहिए अन्यथा कोटेशन पर विचार नहीं किया जायेगा।
- सफल L1 बोलीदाता को अधिशासी अभियंता, हिमालयी गंगा मंडल, केन्द्रीय जल आयोग, हरिद्वार के पक्ष में एफ.डी.आर. के रूप में 3% प्रदर्शन गारंटी जमा करनी होगी।
- उपरोक्त मात्रा आवश्यकतानुसार 25 प्रतिशत तक (Within permissible limit of AA&ES) घटाई या बढ़ाई जा सकती है।



भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
हिमालयी गंगा मंडल हरिद्वार



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Himalayan Ganga Division, Haridwar

10. भारत के राष्ट्रपति की ओर से, किसी भी या सभी कोटेशन को बिना कारण बताये अधोहस्ताक्षरी के पास अस्वीकार या मात्रा में परिवर्तन करने का अधिकार है।
11. कोटेशन खोलने की तारीख से न्यूनतम 60 दिनों के लिए Rates मान्य होने चाहिए।
12. मूल्य केवल भारतीय रुपये में उद्धृत किया जाएगा।
13. उद्धृत दरों में जीएसटी को छोड़कर सभी कर/शुल्क शामिल होने चाहिए जिनका अलग से उल्लेख किया जाएगा उपरोक्त के अलावा कोई अतिरिक्त शुल्क का भुगतान नहीं किया जाएगा।
14. कार्य आदेश जारी करने की तिथि से 10 दिनों के भीतर कार्य पूर्ण होना चाहिए।
15. कार्य का भुगतान कार्य संपादन के आधार पर किया जायेगा।
16. कार्य में निष्पादित वास्तविक मात्रा को पूरा करने के बाद इसके भुगतान के लिए दो प्रतियों में बिल प्रस्तुत किया जा सकता है।
17. कोटेशन पर मुहर के साथ मालिक द्वारा विधिवत हस्ताक्षर किए जाने चाहिए।
18. सभी बोली लगाने वाली फर्मों के पास जीएसटी नंबर और पैन कार्ड होना चाहिए और कोटेशन के साथ उपरोक्त दस्तावेज की फोटो कॉपी संलग्न होनी चाहिए
19. समय से कार्य पूर्ण न होने की स्थिति में ठेके के मूल्य का 1.5% प्रति सप्ताह (सीमित 10% तक) बिल से काट लिया जाएगा।
20. अधिशासी अभियंता, हिमालयी गंगा मंडल, केन्द्रीय जल आयोग, हरिद्वार प्राप्त कोटेशन में एल-1या अन्य किसी भी बिड बोलीदाता को स्वीकार करने के लिए बाध्य नहीं होंगे।

अधिशासी अभियंता

प्रतिलिपि:

1. अधीक्षण अभियंता, जल विज्ञानीय प्रेक्षण परिमंडल, केन्द्रीय जल आयोग, देहरादून।
2. सहायक लेखा अधिकारी, हिमालयी गंगा मंडल, केन्द्रीय जल आयोग, हरिद्वार।
3. केन्द्रीय जल आयोग पोर्टल पर अपलोड करने के लिये।
4. गार्ड फाईल।



भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
हिमालयी गंगा मंडल हरिद्वार



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Himalayan Ganga Division, Haridwar

Notice Inviting Quotation

For and on behalf of the President of India, the Executive Engineer, Himalayan Ganga Division, Central Water Commission, Haridwar invites the sealed quotation for **"Installation of Target Post & Wooden gauge post with painting and marking at sites under Bhagirathi Sub-Division, Central Water Commission, Tehri"** from experienced and eligible agencies as per the terms and conditions mentioned below up to 15:00hrs dated 22.05.2023 (or on next working day in case of holiday) and the quotations will be opened on the same day at 16:00 hrs in presence of representative of the firms if any.

S. No.	Items	Qty	Qty	Amount (Rs.)	Total Amount
1	Demolishing R.C.C. work manually/mechanical means including stacking of steel bars, disposal of unserviceable material within 50 meters lead as per direction of Engineer - in- charge.	3.69	cum		
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sq m on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in charge. The Soil is Ordinary	12.08	cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources). Leveling of gauge post to keep required level including proper overlapping as per direction of Engineer - in- charge.	9.60	cum		
4	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundations, footings, bases for columns	46.8	sqm		
5	Surface dressing of the ground including removing vegetation and in equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil as per direction of Engineer - in- charge.	100	sqm		

एन-81 शिवालिक नगर, हरिद्वार, उत्तराखंड)
दूरभाष: 1334-235882,
ई मेल: hgdcwc@gmail.com, eehgd-cwc@nic.in
जलसंरक्षण-सुरक्षितभविष्य



N-81, Shivalik Nagar, Haridwar-(UK)
Tel: 1334-235882 ,
E-mail: hgdcwc@gmail.com, eehgd-cwc@nic.in
Conserve Water- Save Life

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
हिमालयी गंगा मंडल हरिद्वार



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Himalayan Ganga Division, Haridwar

6	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. 7.2.1 Cement mortar 1:6 (1 cement : 6 coarse sand) as per direction of Engineer - in- charge.	2	cum		
7	Painting and marking of gauge post 1.8 m long with synthetic enamel of approved brand & manufacture to give an even shade by two or more coats and marking the gauge with japan paint, Red, Black and White with standard metric gradation marking of 10mm thickness in black & white alternately & red synthetic enamel of width 10mm at every 100mm etc complete. as per direction of Engineer - in- charge.	40	nos		
8	Painting and marking with synthetic enamel of approved brand & manufacture to give an even shade by two more coats.	11.02	Sqm		
8	Structure steel work riveted bolted or weld in built up section, trusses and framed work, including cutting hoisting ,fixing in position and applying a priming coat of approved steel primer all complete	360.57	Kg		
9	Gauge Transportation Charge	25	Nos		
			Total		
	GST @ 12% (for Sl. No. 1 to 9)				
			G. Total		

Terms & Conditions:-

1. The rates should be quoted both in figures and words any over writing and cutting should be initialed.
2. The envelope containing quotation should be super scribed "Installation of Target Post & Wooden gauge post with painting and marking at sites under Bhagirathi Sub-Division, Central Water Commission, Tehri".
3. The quotation should be addressed to the **Executive Engineer, Himalayan Ganga Division, Central Water Commission, N-81, Shivalik Nagar, Haridwar-249403 (Uttarakhand).**
4. Firm having GST numbers are only eligible to submit their quotation.
5. Must be experience in similar works.
6. Before quoting the rate, bidder may visit the site Devprayag (Alaknanda, Bhagirathi and Ganga) during any working day from 09:00 AM to 05:00 PM and check the condition of sites for the above work. The bidder may contact Bhagirathi Sub Division, Central Water Commission,

एन-81 शिवालिक नगर, हरिद्वार, उत्तराखंड)
दूरभाष: 1334-235882,
ई मेल: hgdcwc@gmail.com, eehgd-cwc@nic.in
जलसंरक्षण-सुरक्षितभविष्य



N-81, Shivalik Nagar, Haridwar-(UK)
Tel: 1334-235882 ,
E-mail: hgdcwc@gmail.com, eehgd-cwc@nic.in
Conserve Water- Save Life

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
हिमालयी गंगा मंडल हरिद्वार



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Himalayan Ganga Division, Haridwar

Bhagirathipuram, Tehri (U.K) for any information regarding sites. Side wise work details are enclosed at Annexure-1.

7. Earnest money of ₹4000/- (Four Thousand Only) in form of FDR in favor of Executive Engineer, Himalayan Ganga Division, CWC, Haridwar must be submitted with the NIQ otherwise quotation will not be entertained.
8. Successful L1 bidder has to submit 3% Performance Guarantee in form of FDR in favor of Executive Engineer, Himalayan Ganga Division, CWC, Haridwar.
9. Above mentioned quantities may increase or decrease by 25% (within the permissible limit of AA & ES) as per our requirement.
10. On the behalf of the President of India, undersigned reserves the right to reject any or all the quotations and to alter the quantity without assigning any reason thereof.
11. The rates should be valid for 60 days minimum from the date of opening of the quotation.
12. The price shall be quoted in Indian rupees only.
13. The rates quoted should be inclusive of all taxes except GST which shall be mentioned separately No additional charge other than above will be paid.
14. Work should be completed within **10 days** from the date of issue of work order.
15. Payment will be made based on actual quantities executed in work.
16. After completing the actual quantity executed in the work, the bill may be presented in duplicate for its payment.
17. Quotations should be duly signed by the proprietor long with the firm seal.
18. All the bidding firms should have GST No. And Pan Card and must enclose photo copies of above document along with the quotation.
19. In case of non-completion of the work within time 1.5% of the contract value per week (limited to 10%) will be deducted from the bill.
20. Executive Engineer, HGD, CWC, will not be bound to accept L-1 or any other bidder in the quotation received.

Sd/-
Executive Engineer

Copy to:

1. Superintending Engineer, Hydrology Observation Circle, CWC, Dehradun.
2. Assistant Account Officer, Himalayan Ganga Division, CWC, Haridwar.
3. For uploading on CWC portal.
4. Guard File

एन-81 शिवालिक नगर, हरिद्वार, उत्तराखंड)
दूरभाष: 1334-235882,
ई मेल: hgdcwc@gmail.com, eehgd-cwc@nic.in
जलसंरक्षण-सुरक्षितभविष्य



N-81, Shivalik Nagar, Haridwar-(UK)
Tel: 1334-235882 ,
E-mail: hgdcwc@gmail.com, eehgd-cwc@nic.in
Conserve Water- Save Life

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
हिमालयी गंगा मंडल हरिद्वार



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Office of the Executive Engineer
Himalayan Ganga Division, Haridwar

Annexure-1

Sl. No.	Name of site	Dismantling of old useless gauge (Nos.)	Installation of new wooden gauge (Nos.)	Painting / marking work (Nos.)	Target Pole (Nos.)
1	Alaknanda Devprayag	8	16	22	1.00
2	Bhagirathi Devprayag	2	3	8	1.00
3	Ganga Devprayag	2	6	10	1.00

