

## No. LGSD-II / AC- 24 / 2013 – 14/516 - 529 Government of India Central Water Commission Lower Godavari Sub Division No-II

Opp. RTC Bus Complex, Danavaiah Pet Post. Rajahmundry -533 103.

Phone: 0883 2468753 FAX: 0883 2468753

Email: aecwc\_rjy@yahoo.com

Date: 12.06.2013

## **NOTICE INVITING QUOTATIONS**

SUB: Quotation for the work of restoration of Telemetry Bubbler line at site Koida (V), Velarupadu Mandal, Khammam District.

Sir(s)

Sealed quotations are invited on behalf of President of India from the registered Contractors/firms for the work of Restoration of Telemetry Bubbler line at site Koida, so as to reach this office by 15-30 hrs on 20.06.2013. The quotations will be opened by the undersigned on the same day at 16:00 hrs. Intended bidders or their authorized representative may present at the time of opening of quotation, if they wish so.

Sl.No.	Description of work	QTY.	RATE	UNIT	AMOUNT
1	Earth work in excavation by mechanical means	~			
	(Hydraulic excavator) / manual means in				
	foundation trenches or drains (not exceeding				
	1.5 m in width or 10 sqm on plan) including				
	dressing of sides and ramming of bottoms, lift				
	upto 1.5 m, including getting out the excavated				
	soil and disposal of surplus soil as directed within a lead of 50m- All kinds of soil.				
	(code2.8.1)				
a	For Bubbler line checking				
b	For Termination block				
C	For Termination block cut water portion				
	Net Quantity	26.138		Cum	
		20.100		Cum	
2	Providing and fixing G.I. pipes complete with				
	G.I. fittings including trenching and refilling				
	etc.40 mm dia nominal bore (external work) 40				
	mm dia nominal bore (code18.12.5)				
	For damaged portion of Bubbler line	36.000		m	
2					
3	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and				
	making long screws etc. complete (new work)				
	40 mm nominal bore (code18.46.5)				
	For damaged portion of Bubbler line	4 Nos.		Each	
	0 1				
4	Providing I-Section of 1.50m length at the				
	Ttermination block for better support to				
	Bubbler line	1 Nos.		L.S.	

		1		
5	Centering and shuttering including strutting,			
	propping etc. and removal of form work for			
	Foundations, footings, bases of Columns			
	(Code: 4.3.1)			
a	For Termination block			
b	For Termination block cut water portion			
	Net Quantity	1.105	Sqm	
6	Providing and laying in position cement			
	concrete of specified grade excluding the cost of			
	centering and shuttering - All work upto plinth			
	level. CC 1:2:4 (1 Cement : 2 coarse sand : 4			
	graded stone aggregate 20 mm nominal size)			
	(Code: 4.2.3)			
a 1.				
b	For Termination block cut water portion			
	Net Quantity	1.250	Cum	
7	20mm cement plaster finished with a floating			
	coat of neat cement of mix: 1:4 (1 cement: 4			
	fine sand) (code13.3.1)			
a	For Termination block - sides			
	For Termination block - Top			
b	For Termination block cut water portion - sides			
	For Termination block cut water portion - Top			
	Net Quantity	2.355	Sqm	
8	Providing Telemetry Bubbler cable			
	(Local rate)	200.000	m	
0	Re fitting charges of the checked G.I.bubbler	160,000	1.0	
9	line	160.000	L.S.	
10	Filling available averaged couth (avaluation			
10	Filling available excavated earth (excluding			
	rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth:			
	consolidating each deposited layer by ramming			
	and watering, lead up to 50 m and lift upto 1.5			
	m (code: 2.25)			
	Net Quantity = Item No. 1a	25.200	Cum	
	The Quality Hemi 140. It	20.200	Cum	
	Total			
1	Total			

## Terms & Conditions:

- 1. The sealed envelope contained quotations should be super scribed as "Quotations for work of restoration of Telemetry Bubbler line at site Koida".
- 2. An EMD of 2% on quoted total amount shall be enclosed in the form of DD in favour of Executive Engineer, Lower Godavari Division, CWC, Hyderabad payable at Hyderabad. The EMD of unsuccessful bidder will be returned back immediately after finalization of bids.
- 3. 2% Income tax & other taxes as applicable shall be deducted from the total amount.
- 4. The work will be carried out at site 46A, Koida, and executed by the Site in charge in all stages.
- 5. The Security Deposit of 10% may be deducted from the Bill and will be released after six months completion of the work satisfactorily. Any damage/penalty to the Govt. property it will be adjusted from the security deposit.
- 6. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment, etc.

- 7. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
- 8. No T&P materials for any work including scaffolding/shuttering etc, will be provided by this department for the above said works.
- 9. The curing of the cement works should be done as per the standards by the contractor.
- 10. After satisfactory completion of the works in all respects, the bill in triplicate may be submitted for payment to the undersigned.
- 11. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
- 12. However payment will be made on actual measurements only.
- 13. This office reserves the right to reject any one or all quotations without assigning any reasons there of.

Sd/-Sub-Divisional Engineer

To M/s.

## Copy for information to:-

- 1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
- 2. The Executive Engineer, Lower Godavari Division, CWC, Hyderabad, w.r.t Lr.No. LGD/DB/Estimate/ 2013-14/848-51; dated: 10.06.2013.
- 3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO web site.
- 4. O/o The Superintending Engineer, Irrigation Circle, Dowlaiswaram, for wide publicity.
- 5. O/o The Assistant Engineer, Investigation Sub Division, Gandhipuram-3, N.W.D.A., Rajahmundry, for wide publicity.
- 6. O/o The Assistant Engineer, CPWD, Income Tax Office Complex, Rajahmundry for wide publicity.
- 7. The Junior Engineer, Site 46A, Koida for wide publicity.
- 8. The Junior Engineer, Site 47, Polavaram for wide publicity
- 9. O/o The Mandal Revenue Officer, Valerupadu, for wide publicity.
- 10. O/o The Mandal Revenue Officer, Rajahmundry, for wide publicity.
- 11. Notice Board.

Sd/-Sub-Divisional Engineer