

GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
LOWER GODAVARI SUB DIVISION-I
Opp.Sub Collector's Office
BHADRACHALAM - 507111

Notice Inviting Quotation

NO: LGSD-I / A - 12 / 2013/18-24

Dated: 7/1/2013

To,

Subject: - Notice Inviting Quotations for laying of Cement Concrete road at LGSD-I, Bcm- reg
Sirs,

Sealed quotations are invited for laying of Cement Concrete approach road from gate to office building at LGSD-I, CWC, Bhadrachalam. The sealed quotations should reach this office by 15.30hrs on Dt. 21/01/2013. The quotations will be opened on the same day at 16.00 Hrs. You are requested to be present yourself or sent your authorized representative to this office at the time of opening of quotations.

Sl. No.	Description of work	Unit	Quantity.	Rate	Amount
As enclosed					

Terms & Conditions:

1. The sealed envelope contained quotations should be super scribed "**Quotations for the work of laying of Cement Concrete road at LGSD-I, CWC Bhadrachalam**" due for opening on 21/01/2013 at 1600 hrs.
2. The rates quoted should be valid at least for a period of six months from the date of opening of the quotation.
3. Rates should be mentioned, inclusive of all taxes, levies, transportation, loading, unloading, and stacking of materials and providing necessary labour, materials, equipment, etc.
4. An EMD of 2% on quoted total amount shall be enclosed in the form of DD in favor of Executive Engineer, LGD, CWC, Hyderabad payable at Hyderabad. The EMD of unsuccessful bidder will be returned back immediately after finalization of bids. The EMD of the successful bidder will be released on completion of the work in all respect.
5. Successful Bidder need to submit the Security Deposit @ 10% of Quotation amount. Security Deposit will be release after 6 months from the date of completion of the work.
6. All the debris and un-used materials etc. should be removed from the work site as soon as the work is completed. No extra charges will be paid for this purpose.
7. No T&P materials for any work including scaffolding/ shuttering etc, will be provided by this department for the above said works.
8. The curing of the cement works should be done as per the standards by the contractor.

Materials to be used in the construction must be standard and approved ISI Code. The work should be standard and as per our description. The defective and sub-standard work is liable for rejection and same should be made good as per our requirement by contractor himself on his own expenditure, for which no extra payment will be made.

10. The work should be completed within the 45 days of work order placed. No time extension will be given for completion of work until and unless beyond control of human beings.
11. The work will be inspected by the authorized representative of this Department and get himself be satisfied.
12. After satisfactory completion of the works in all respects, the bill in triplicate may be submitted for payment to the undersigned.
13. The payment will be made generally by Demand draft on SBI after completion of work satisfactorily and on submission of bill in triplicate.
14. However payment will be made on actual measurements only.
15. VAT 5%, Income Tax 2.0%, (3% Educational Cess on IT) and Labour Cess 1% and other taxes, if any shall be deducted from the bill.
16. The Contractor must submit the proper Registration and work permit, Pan/Tan number.
17. This Department is not responsible for any accidents/losses to workers engaged in this work.
18. This office reserves the right to reject any one or all quotations without assigning any reasons there of.
- 19.


Sub-Divisional Engineer
Sub-Divisional Engineer
LGSD.1/CWC/Bhadrachalam.

Copy for information to:-

1. The Superintending Engineer, Godavari Circle, CWC, Hyderabad along with soft copy for uploading the same in CPP.
2. The Executive Engineer, LGD, CWC, Hyderabad, w.r.t Lr. No. LGD/DB/Estimates/2012-13/ 3598 - 02, dated 31.10.2012.
3. Smt. Rekha Rani, AD, CE'S Office, KGBO, CWC, Hyderabad along with soft copy for uploading the same in KGBO web site.
4. O/o The Sub Collector, Bhadrachalam, for wide publicity.
5. O/o The Mandal Revenue Officer, Bhadrachalam, for wide publicity.
6. O/o The Project Officer, ITDA, Bhadrachalam, for wide publicity.
7. Notice Board.


Sub-Divisional Engineer
Sub-Divisional Engineer
LGSD.1/CWC/Bhadrachalam.

ABSTRACT OF COST

NAME OF WORK : CC approach road from gate to office building at LGSD-I, Bhadrachalam

LOWER GODAVARI SUB-DIVISION NO.1, BHADRACHALAM

S.No	DESCRIPTION	Qty	Rate	Unit	Amount
1	Preparation and consolidation of sub grade with power road roller of 8 to 10 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re rolling the sub grade and disposal of surplus earth with lead upto 50 metres. Earth work excavation for laying CC road a) From bore well to cellar				
	TOTAL	144.30		Sq.mts	
2	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking rolling, watering and compacting to the required density.				
	TOTAL	33.19		Cum	
3	Supply and laying of 125 micron thick polythene film over surface of WBM.				
	TOTAL	351.50		Sq.mts	
4	Providing and laying cement concrete of 1:2:4 (1 cement, 2 Coarse sand, 4 graded stone aggregate of 40mm nominal size) in pavements laid to required slope / camber, finishing with required and compacting mechanically, levelling to required slope/camber, finishing with required texture, including steel form work, curing, making provision for contraction/expansion joints. Cement concrete prepared with batch mixing machine				
	TOTAL	49.875		Cum	
5	Providing and laying in position bitumen hot sealing compound for expansion joints etc. (one for every three mts.length) using grade A sealing compound.			per cm depth per cm width per m length	
		1627.50			
				Say Rs.	
6	VAT @ 5%				
7	ST @ 4.95%				
8	Contingency @ 3%				
9	Miscellaneous				

TOTAL Rs.