



भार्गव नर्सिंग होम के पास, बाँदा (उ. प्र.) - 210001,

दूरभाष /telephone : 05192-224298

Beside Bhargav Nursing Home Banda (U.P.)- 210001 ई-मेल/E-mail:ksd_banda@rediffmail.com

Letter No. के.उ.म./बाँदा/01/कार्य/~~655-701~~ 675-81


दिनांक : 11/08/2023

Corrigendum

Reference NIQ No. पत्राक-: 16-मुख्या/के0उ0म0/बाँदा/म/2023/651-652 दिनांक: 07/08/2023, an NIQ was issued for the work "Construction of Musto Type Bench (MTBM) at site Madla on river Ken under KSD, Banda." Due to administrative reason date of opening of NIQ is being changed as per following details:-

Quotation submission closing/end date	21.08.2023 at 14.00 hrs
Quotation opening date	21.08.2023 at 14.30 hrs

The remaining conditions of earlier NIQ will remain same.


Sub Divisional Engineer
KSD, Banda

Copy for information and vide publicity to :-

1. The Executive Engineer, LYD, CWC, Agra.
2. The Subdivisional Engineer, LYSD-3, CWC, Hamirpur.
3. Account Section, LYD, CWC, Agra.
4. Junior Engineer (HQ), KSD, Banda.
5. Notice Board, KSD, CWC, Banda.



16/8/2023
मुख्यालय
जल शक्ति विभाग
आगरा

भारत सरकार
जल शक्ति मंत्रालय
जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग
केन्द्रीय जल आयोग
केन उपमंडल, बाँदा



Government of India
Ministry of Jal Shakti
Dept. of Water Resources, RD&GR
Central Water Commission
Ken Sub Division, Banda

पत्रांक: 16-मु.प्र.डि.030/म.बाँदा/म.2023/651-52

दिनांक: 07/08/2023

NOTICE INVITING QUOTATION

Sealed/closed quotations are hereby invited by the undersigned on behalf of President of India from the contractors for the following work **Construction of Musto Type Bench Mark (MTBM) at GDSQT site Madla on river Ken under Ken Sub Division, CWC, Banda (U.P.)**. As per schedule of quantity enclosed.

The quotation should reach in the office of the undersigned on or before 07.08.2023 up to 14:00 hrs and will be opened on the same day at 14:30 hrs in the presence of authorized representatives who may desire to be present at the time of opening the quotations. If quotation could not be opened on aforesaid date due to unavoidable circumstances, then same will be opened on next working day without any further notice. The following details are given below regarding aforesaid work :

S.No.	Name of Work	Est. Cost
1.	Construction of Musto Type Bench Mark (MTBM) at GDSQT site Madla on river Ken under Ken Sub Division, CWC, Banda (U.P.)	Rs. 39115/-
2.	Earnest Money Deposit (2% of Estimated Cost)	Rs. 782/-

Terms & Conditions

1. The work should be done as per CPWD specification & direction of Engineer in-charge.
2. Rates should be quoted both in figure and words.
3. Signed copy of GST Registration number, PAN No and Experience certificate any civil work should be attached.
4. Income tax & other tax etc. shall be deducted from the bill as per rule.
5. 5% of PG for quoted amount has to be submitted to this office by successful bidder before commencing of aforesaid work. The demand draft/Banker's Cheque of Schedule Bank should be payable to "The Executive Engineer, LYD, CWC, Agra.
6. The work should be completed within thirty days from the date of issue of work order.
7. The payment will be made by Online/PFMS after satisfactory completion of work.
8. No advance payment shall be made.

Enclose: Schedule of Quantity

Sub Divisional Engineer

Copy for information and vide publicity to:

1. The Executive Engineer, Lower Yamuna Division, CWC, Agra
2. Account Section, Lower Yamuna Division, CWC, Agra
3. Junior Engineer (HQ), KSD, Banda
4. Notice Board of KSD, CWC, Banda.

1. भार्गव नर्सिंग होम के पास, कटरा

बाँदा (उ.प्र.) - 210001

दूरभाष सं०: 05192-224298

ई-मेल: ksd_banda@rediffmail.com

जल संरक्षण-सुरक्षित भविष्य



Near Bhargav Nursing Home, Katra
Banda (U.P.) -210001

Tel: 05192-224298

E-mail: ksd_banda@rediffmail.com

conserve water-save life

Schedule of Quantity

Name of work: Construction of Musto Type Bench Mark at site Macila on river Ken under Ken Subdivision Banda

It. no.	Description of work	Qty	Unit	Rate	Amount (In figure)	Amount (In words)
Part A (Musto Type Benchmark)						
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.					
	Musto type bench mark	2.025	cum		0.00	
2	Centering and shuttering including strutting, propping etc. and removal of form work for: foundation, footings, bases for column.					
	Musto type bench mark	5.400	sqm		0.00	
3	Providing & laying in position cement concrete of specified grade excluding the cost of centering & shuttering. All work up to plinth level 1:5:10 (1 cement : 5 coarse sand (Zonell)) : 10 graded stone aggregated 40 mm nominal size.					
	Musto type bench mark	0.338	cum		0.00	
4	Providing & laying in position cement concrete of specified grade excluding the cost of centering & shuttering. All work up to plinth level 1:2:4 (1 cement : 2 coarse sand (Zonell)) : 4 graded stone aggregated 40 mm nominal size.					
	Musto type bench mark	1.634	cum		0.00	
5	Stone work ashlar sunk or moulded or sunk and moulded upto floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) including pointing with white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade : White sand stone.					
	Musto type bench mark	0.077	cum		0.00	
6	Brick work with common burnt clay FPS (non modular) bricks					
	Musto type bench mark	1.208	cum		0.00	
7	Providing and filling of stone aggregate (single size) 20 mm nominal size 15 cm over the top of white stone, inside the musto type bench mark.					
	Musto type bench mark	0.233	cum		0.00	
8	Providing and filling of sand (35 cm over the filled stone rubbles) upto top of Musto type bench mark.					
	Musto type bench mark	0.224	cum		0.00	
9	12 mm cement plaster finished with a floating coat of neat cement of mix 1:4 (1 cement : 4 fine sand).					
	Musto type bench mark	8.510	sqm		0.00	
10	Providing & fixing of GI pipe 25 mm diameter for drainage purpose on downhill.					
	Musto type bench mark	0.350	metre		0.00	
11	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.					
	Musto type bench mark	8.510	sqm		0.00	
12	Finishing walls with Premium Acrylic Smooth exterior paint with silicone additives of required shade : New work (two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)					
	Musto type bench mark	8.510	sqm		0.00	
					0.00	
Total amount (in figures) (incl. GST)						
Total amount (in words):						

Signature of Contractor with Seal