



84/93-96, प्रताप नगर, सांगानेर, जयपुर -302033
फोन: 0141-2790065, ई-मेल: chambalcwc@yahoo.co.in

पत्र क्रमांक: चमज/के.ज.आ./मु.-1/2023/4735-39

दिनांक: 27/12/2023

कोटेशन आमंत्रण सूचना (NOTICE INVITING QUOTATION)

भारत के राष्ट्रपति की ओर से अधिशाषी अभियंता, चम्बल मंडल, जयपुर द्वारा अधिकृत तथा योग्य बोलीदाताओं से “मध्य चम्बल उपमंडल, कोटा के अधीनस्थ अकलेरा स्थल पर रैंप, इंटरलॉकिंग टाइल्स एवं बाउंड्री वाल पर फेंसिंग का कार्य हेतु कोटेशन” लिखा हुआ मुहरबंद कोटेशन आमंत्रित किये जाते हैं।

Sealed quotation super scribed as “**Quotation for construction of Ramp, Interlocking Tiles & fencing work on boundary wall at site Aklera under Middle Chambal Sub-division, CWC, Kota**” are invited for and on behalf of the President of India by the Executive Engineer, Chambal Division, CWC, Jaipur from the authorized and eligible bidders.

नियम एवं शर्तें (Terms & Conditions)

- हस्ताक्षरित व मुहरबंद कोटेशन अधिशाषी अभियंता, चम्बल मंडल, केन्द्रीय जल आयोग, जयपुर के कार्यालय में दिनांक 08.01.2024 पूर्वान्ह 11:00 बजे तक या उससे पूर्व प्राप्त हो जानी चाहिए, जो उसी दिन अर्थात् 08.01.2024 दोपहर 12:00 बजे अधोहस्ताक्षरी तथा बोली लगाने वाले या उसके प्रतिनिधि जो उपस्थित रहना चाहे की उपस्थिति में खोली जाएगी।

The sealed & signed quotation shall reach to the office of Executive Engineer, Chambal Division, CWC, Jaipur on or before 08.01.2024 upto 11:00 A.M. and will be opened on the same day i.e. 08.01.2024 at 12:00 P.M. in the presence of undersigned and bidders or their representative who may likely to be present at the time of opening of quotations.

- मुहरबंद कोटेशन के साथ रुपये 5160/- की ईएमडी डिमांड ड्राफ्ट/बैंकर्स चेक/एफडीआर के रूप में अधिशाषी अभियंता, चम्बल मंडल, केजआ, जयपुर के पक्ष में संलग्न करना अनिवार्य है। बिना ईएमडी के प्राप्त कोटेशन को खारिज कर दिया जाएगा। MSE & Startup को ईएमडी जमा करने की छूट दी गई है।
The EMD of Rs. 5160/- in the form of Demand Draft/Bankers Cheque/FDR in favor of Executive Engineer, Chambal Division, CWC, Jaipur should be enclosed with sealed quotation. Quotations received without EMD will be summarily rejected. MSE & Startup are exempted from payment of EMD.

- कोटेशन नोटिस (सभी अनुलग्नकों और मूल्य बोली सहित) के सभी पृष्ठों पर सील और हस्ताक्षर करना अनिवार्य है। बिना seal and sign (सभी पृष्ठों पर) के प्राप्त कोटेशन को खारिज कर दिया जाएगा।
The quotationer must seal and sign at all pages of the quotation notice including all annexures and price bid failing which the quotation will summarily rejected.

- अंतिम तिथि व समय के पश्चात प्राप्त कोटेशन स्वीकार नहीं करी जाएगी और गैर-उत्तरदायी मानी जाएगी।

Quotation received after the last submission date & Time will not be accepted and will be treated as non-responsive.

5. कार्य करने की अवधि कार्यदिश जारी होने के बाद से 30 दिन की रहेगी।
Work shall be carried within 30 days after issue of work order.
6. कोटेशन में दर्शायी गयी राशि सभी प्रकार के टैक्स (GST etc.) के साथ होनी चाहिए तथा Annexure-1 में निर्धारित जगह पर ही राशि को दर्शाये।
Rates shall be quoted including of all Taxes (GST etc.) and rates should be mentioned in Annexure-1 at their shown place only.
7. दरें अंकों और शब्दों दोनों में उद्धृत की जानी चाहिए और बिना किसी अधिलेखन के सुपाठ्य रूप से लिखी जानी चाहिए। किसी भी सुधार के मामले में, इसे बोलीदाता द्वारा पूर्ण हस्ताक्षर के साथ सत्यापित किया जाना चाहिए। अंकों और शब्दों में दरों के बीच कोई अंतर होने पर शब्दों में लिखी दरों को सही माना जाएगा।
The rates should be quoted both in figures and words and legibly written without any over-writings. In case of any correction, the same must be attested by the bidder with a full signature. In case of any discrepancy between the rates in figures and that in words, the rate in words will be accepted as correct.
8. इस कार्य हेतु इस्तेमाल में लिया गया सामान अच्छी गुणवत्ता का एवं दिए गये विशेष विवरण के अनुसार तथा त्रुटी रहित होना चाहिए।
The material used for this work must be of standard quality and as per specifications and free from all the defects.
9. कोटेशन में दर्शायी दरे, कोटेशन खुलने के दिन से कम से कम 60 दिन तक वैध होनी चाहिए।
Rates quoted should be valid at least for 60 days from date of opening.
10. उक्त कार्य अकलेरा स्थल (जिला-झालावाड़, राजस्थान) पर होना हैं, जिनका दरें डालने से पूर्व निरीक्षण किया जा सकता हैं।
The above work is to be done at site Aklera (Dist.- Jhalawar, Rajasthan), which (Place) can be inspected before quoting the rates.
11. कोटेशनर के पास PAN/GST No. होना चाहिए (प्रतिलिपि संलग्न की जाए)। बिना PAN तथा GST No. प्रतिलिपि के प्राप्त कोटेशन को खारिज कर दिया जाएगा।
Quotationer must have Firm Registration certificate/PAN/TIN/GST No. (Copy to be enclosed).
Quotations received without copy of PAN & GST No. will be summarily rejected.
12. अधोहस्ताक्षरी किसी एक या सभी कोटेशन को बिना कारण बताये स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता हैं।
Undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
13. कार्य की मात्रा कार्यदिश के समय या कार्य करने के दौरान बढ़ाई या कम की जा सकती हैं।
The quantity of work may be increased or decreased at the time of work order or during the time of execution.
14. कोटेशन स्वीकृत होने पर, फर्म/एजेंसी को किसी भी वाणिज्यिक बैंक से Account Payee D.D/ Fixed Deposit Receipt/ Banker's cheque or Bank Guaranty के रूप में निविदा राशि के 3% की दर से परफॉर्मेंस गारंटी

जमा करनी होगी जो की अधिशाषी अभियंता, चंबल मण्डल, के.ज.आ., जयपुर को देय होगी। परफॉरमेंस गारंटी कार्य समाप्त होने के 60 दिन बाद तक वैध होनी चाहिए।

On acceptance of the quotation, the Firm/Agency shall have to submit performance Guarantee @ 3% of the tendered amount in the form of an Account Payee D.D/ Fixed Deposit Receipt/ Banker's cheque or Bank Guaranty from any of the commercial bank in favour of Executive Engineer, Chambal Division, CWC, Jaipur payable at Jaipur. This should remain valid for a period of sixty days beyond the date of completion of work.

15. कार्य के संतोषजनक पूर्ण होने के बाद सम्पूर्ण भुगतान में से आवश्यक कटौती (2.5 % Security Deposit, 2 % GST, 2% TDS, 1% Labour Cess) पश्चात भुगतान को ECS/RTGS के द्वारा किया जायेगा । अमानत राशी (Security Deposit) का भुगतान कार्य समाप्त होने के 06 माह के पश्चात किया जायेगा ।

Payment will be made through ECS/RTGS, only after satisfactory completion of work and deduction of necessary Deductions (2.5% Security Deposit, 2% GST, 2% TDS, 1% Labour Cess). Security Deposit amount will be given after 06 months of completion of work.

Sd/-
अधिशाषी अभियंता
चम्बल मंडल, के.ज.आ., जयपुर

प्रतिलिपि सूचनार्थः

1. सहायक लेखाधिकारी, लेखा शाखा, चम्बल मंडल, जयपुर।
2. उप मंडलीय अभियंता, उ.च.उ.मं., इंदौर।
3. सहायक, पत्राचार शाखा, चम्बल मंडल, जयपुर।
4. सूचना पट्ट, चम्बल मंडल, जयपुर।
5. विभागीय वेबसाइट।

Schedule of Quantity

Name of work: Construction of Ramp, Interlocking Tiles & fencing work on boundary wall at site Aklera under Middle Chambal Sub-division, CWC, Kota

Item No.	Sub-head and items of work	Qty.	Unit	Rate in Rs. (Incl. GST)	Amount in Rs.
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	3.88	cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.43	cum		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement: 4 coarse sand).	1.897	cum		
4	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand).	7.220	sqm		
5	Brick Aggregate (Single size) : 40 mm nominal size.	1.55	cum		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).	4.64	cum		
7	Supplying and stacking at site. 63 mm to 45 mm size stone aggregate	9.07	cum		
8	Supplying and stacking at site:Moorum	9.07	cum		
9	Providing and laying 60mm thick factory-made cement concrete interlocking paver block of M -30 grade made by block making machine with strongvibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	90.68	sqm		
10	12 mm cement plaster of mix: 1:4 (1 cement: 4 fine sand)	16.18	sqm		
11	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	0.07	cum		

12	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete. (40 X 40 X 5 mm M S Angle) - 3 kg/m	294.00	kg		
13	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 4.2.3 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.07	cum		
14	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire	1627.40	Meters		
Grand Total in figures Rs.					
Grand Total in Words					

Note: Quotations received without mentioning Grand Total in Figures & words both will be summarily rejected.

Terms & conditions: - As per NIQ

Issuing Authority

Sd/-
Executive Engineer
Chambal Division

Signature of Contractor
Seal
Address