



GOVERNMENT OF INDIA
CENTRAL WATER COMMISSION
LOWER WAINGANGA SUB-DIVISION

PH/FAX : 07172-258967
E-Mail: sdecwc123 @ gmail.com

Near Dist. Stadium,
Civil Line, Chandrapur-442401.

NO. LWSD/CWC/ A-9/ 2019/236-43

DATE : 17/6/2019

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited from registered firms/ reputed parties to carry out the civil work "Installation of gauge posts (S/G Line,D/S Line,U/S Line) at new sites Markandadeo, Dhanora and Kurkheda under LWSD,CWC, Chandrapur", as per details given in Annexure -I, as per terms and conditions described below:-

Terms and conditions:-

1. दरों को एफ.ओ.आर. संतुष्ट पैकिंग, अग्रेषण, माल, बीमा, यदि कोई हो, के समावेशी उपमंडलीय अभियंता, जोअर वैनगंगा उपमंडल, के.ज. आ., चंद्रपुर के अन्तर्गत साईट कार्य स्थल तक होना चाहिए जो कि Annexure -I, में दिया गया है।
2. कोटेशन के खुलने की तारीख से न्यूनतम 30 दिनों के लिए दरें मान्य होंगी।
3. गेज पोस्टों की स्थापना कार्य आवेष्ट से 25 दिनों के भीतर की जानी चाहिए।
4. दरों में सभी करों और लेवी को शामिल किया जाना चाहिए किसी भी छाते पर कोई अतिरिक्त भुगतान नहीं किया जायेगा।
5. कोटेशन राशि का 5% बिल से रखा जायेगा क्योंकि छः महीने की वारंटी अवधि तक प्रदर्शन की गारंटी होगी जो कि फाइनल बिल से काटा जायेगा।
6. गेज पोस्टों की स्थापना को विनिर्देशों के अनुसार कड़ाई से होना चाहिए, अन्यथा अस्वीकृति के लिए उत्तरदायी होगा।
7. तीन प्रतियों में पूर्व-प्राप्त बिल को सामग्री के संतोषजनक वितरण के बाद भुगतान करने के लिए प्रस्तुत करना होगा तथा पूरे में पिएफएमएस ऑनलाइन पोर्टल द्वारा भुगतान किया जायेगा, इसके लिए बिल की रसीद पूरी तरह से जमा करनी होगी।
8. बोलीदाताओं को इस दस्तावेज में उल्लेखित सभी नियम और शर्तों को ध्यान में रखते हुए दरों को उद्धरण करना चाहिए।
9. NIQ को एक मोहरबंद बड़े लिफाफे में जमा किया जाना चाहिए।
10. बिडर को जीसटी पंजीकरण प्रमाणपत्र प्रस्तुत करना चाहिए।
11. बिडर को पी. डब्ल्यू. डी. या सी. पी. डब्ल्यू. डी. से प्राप्त रजिस्ट्रेशन प्रमाणपत्र प्रस्तुत करना होगा।

Sealed quotation duly superscribed "Quotation for Installation of gauge posts (S/G Line, D/S Line, U/S Line) at new sites Markandadeo, Dhanora, and Kurkheda under LWSD, CWC, Chandrapur" will be received by the undersigned till **11.00 Hrs** on **28.06.19** and will be opened on **28.06.19** at **12.30 hrs** in the presence of interested parties. Quotation received after schedule time will not be considered.

Undersigned reserves the right to reject any or all the quotation without assigning any reason therefore.

Signature
21/6/19
JECNA

Copy for information and publicity to:-

1. The Superintending Engineer(C), M.C.O. CWC Nagpur.
2. The Executive Engineer, Wainganga Division, CWC, Nagpur.
3. Account branch, WD, CWC, Nagpur.
- ✓ 4. Junior Engineer, WD, CWC, Nagpur, to upload on CWC Tender portal.
5. The SDEs UWSD Nagpur/WSL Chandrapur/ PGSD Yavatmal
6. Office Notice Board.

(N.R.RAMTEKE)
SDE,LWSD,CWC,Chandrapur

Signature
(N.R.RAMTEKE)
SDE,LWSD,CWC,Chandrapur

BILL OF QUANTITY

ANNEXURE-I

Installation of gauge posts at new sites Markandadeo(25 gauge posts) ,Dhanora(4 gauge posts) and Kurkheda (5 gauge posts) under LWSD, CWC, Chandrapur.

Division: Wainganga Division, CWC, Nagpur.

Item No.	Sub head and items of work	Qty./ No	Unit	Rate Rs	Amount Rs	Total Rs
1	2.6.1 Earthwork in excavation by mechanical means (Hydraulic excavator)/Manual means over areas (Exceeding 30 cm in depth, 1.5m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50m and lift up to 1.5m, as directed by Engineer in charge. All kind of soils.	0.216	Cum			
2	4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	0.216	Cum			
3	4.3.1 Centring and shuttering including strutting, propping etc. and removal of form work for : 4.3.1 Foundations, footings, bases for columns	0.16	Sqm			
4	4.1.4 Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size)	0.016	Cum			
5	S.O.R 2012 CWC Painting of gauge post 1.8 m long with synthetic enamel approved brand & manufacture to give an even shade by two or more coats and making the gauge with japan paint red, black and white with standard metric graduation making of 5 mm thickness in black and white alternately & red synthetic enamel of width 5 mm at every 50 mm.	1	Per day			
Total cost for installation of 1 gauge post						
For 34 gauge posts						
Transportation of RCC gauge post from Chandrapur to new sites Markandadeo, Dhanora and Kurkheda (Dist. Gadchiroli, M.S.) (total distance- 430 km) @ Rate of Rs. Per km						
Total						

(Rupees ----- only)

Signature:-

Name:-

Address:-