

GOVERNMENT OF INDIA  
CENTRAL WATER COMMISSION  
LOWER WAINGANGA SUB-DIVISION

PH/FAX : 07172-258967  
E.Mail: sdecwc123 @ gmail.com

Near Dist. Stadium,  
Civil Line, Chandrapur-442401.

NO. LWSD/CWC/ A-9/ 2019/3/8-26

DATE: 22/7/2019

**NOTICE INVITING QUOTATION**


Sealed quotations are hereby invited from registered firms/ reputed parties to carry out the civil work "Construction of MTBM at 4 new sites Kurkheda, Bagdi, Sakoli Bridge & Wadsa under LWSD,CWC,Chandrapur", as per details given in Annexure -I, as per terms and conditions described below:-

**Terms and conditions:-**

1. दरों को एफ.ओ.आर. गंतव्य पैकिंग, अग्रेषण, माल, बीमा, यदि कोई हो, के समावेशी उपमंडलीय अभियंता, योश्वर वैनगंगा उपमंडल, के.ज. आ., चंद्रपुर के अन्तर्गत साईट कार्य स्थल तक होना चाहिए जो कि Annexure -I, में दिया गया है।
2. कोटेशन के खुलने कि तारीख से न्यूनतम 30 दिनों के लिए दरें मान्य होंगी।
3. गेज पोस्टो कि स्थापना कार्य आदेश से 25 दिनों के भीतर कि जानी चाहिए।
4. दरों में सभी करों और लेवी को शामिल किया जाना चाहिए किसी भी खाते पर कोई अतिरिक्त भुगतान नहीं किया जायेगा।
5. कोटेड राशि का 5% बिल से रखा जायेगा क्योंकि छः महीने कि वारंटी अवधि तक प्रदर्शन कि गारंटी होंगी जो कि फाइनल बिल से काटा जायेगा।
6. गेज पोस्टो कि स्थापना को विनिर्देशों के अनुसार कड़ाई से होना चाहिए, अन्यथा अस्वीकृति के लिए उत्तरदायी होगा।
7. तीन प्रतियों में पूर्व-प्राप्त बिल को सामग्री के संतोषजनक वितरण के बाद भुगतान करने के लिए प्रस्तुत करना होगा तथा पुरे मे पिएफएमएस ऑनलाइन पोर्टल द्वारा भुगतान किया जायेगा, इसके लिए बिल कि रसीद पूरी तरह से जमा करनी होंगी।
8. बोलीदाताओं को इस दस्तावेज में उल्लेखित सभी नियम और शर्तों को ध्यान में रखते हुए दरों को उद्धरण करना चाहिए।
9. NIQ को एक मोहरबंद बड़े लिफाफे में जमा किया जाना चाहिए।
10. बिडर को जीसटी पंजीकरण प्रमाणपत्र प्रस्तुत करना चाहिए।
11. बिडर को पी. डब्ल्यू. डी. या सी. पी. डब्ल्यू. डी से प्राप्त रजिस्ट्रेशन प्रमाणपत्र प्रस्तुत करना होगा।

Sealed quotation duly superscribed "Quotation for "Construction of MTBM at 4 new sites Kurkheda, Bagdi, Sakoli Bridge & Wadsa under LWSD,CWC,Chandrapur" " will be received by the undersigned till **11.00 Hrs** on **01.08.19** and will be opened on **01.08.19** at **12.30 hrs** in the presence of interested parties. Quotation received after schedule time will not be considered.

Undersigned reserves the right to reject any or all the quotation without assigning any reason therefore.

  
22/7/19

(N.R. RAMTEKE)

SDE, LWSD, CWC, Chandrapur

Copy for information and publicity to:-

1. The Superintending Engineer(C), M.C.O. CWC Nagpur.
2. The Executive Engineer, Wainganga Division, CWC, Nagpur.
3. Account branch, WD, CWC, Nagpur.
4. Junior Engineer, WD, CWC, Nagpur, to upload on CWC Tender portal.
5. The SDEs UWSD Nagpur/WSD Chandrapur/ PGSD Yavatmal
6. Office Notice Board.

(N.R. RAMTEKE)

SDE, LWSD, CWC, Chandrapur

**BILL OF QUANTITY**

**Construction of MTBM at 4 new sites Kurkheda, Bagdi, Sakoli Bridge & Wadsa under LWSD,CWC,Chandrapur**

**Division: Wainganga Division, CWC, Nagpur.**

Item No.	Sub head and item of work	Qty./ No	Unit	Rate Rs	Amount Rs.	Total Rs.
1	DSR 2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.All kinds of soil	3.688	cum			
2	DSR 4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	0.256	sqm			
3	DSR 5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	2.3005	cum			
4	DSR 6.26.2 Brick work with common burnt clay selected F.P.S. (non modular) bricks of class designation 7.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand Above plinth level upto floor V level	1.080	cum			
5	DSR 13.11 18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand	8.64	Sqm			
6	DSR 0.3 Materials,1160 Supply of good quality Masonry Stone (0.3x0.3x1 m)	.09	cum			
7	DSR 13.44.4 Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @3.84 Kg/10 sqm)	8.94	Sqm			
8	DSR 0.3 Materials,0982 Coarse sand III (sand filling inside of MTBM)	0.3825	cum			
	Total amount for one MTBM					
	Total amount for four MTBM (Four sites (Kurkheda(Gadchirolli), Bagdi (Bhandara), Sakoli bridge (Bhandara), Wadsa (Gadchirolli)					
	Contingencies Charges (3%)					
	<b>Total</b>					

( Rupees -----only)

**Signature :-**

**Name :-**

**Address:-**