

**भारत सरकार  
केन्द्रीय जल आयोग  
ऊपरी यमुना मण्डल**

कालिंदी भवन, बी-5, तारा क्रिसेंट रोड,  
कुतुब संस्थानिक क्षेत्र, नई दिल्ली-110016

क्रमांक: 01/03/08/2020/UYD/Staircase/YashwantNagar/6028-34 दिनांक: 8/12/2021

**कोटेशन आमंत्रण सूचना**

(NIQ-13/2020-21/UYD/Delhi)

भारत के राष्ट्रपति के और से अधोहस्ताक्षरी द्वारा संलग्न विवरण के **Construction of Staircase at GDSQ Site Yashwant Nagar, Sirmaur (H.P.)** में कार्य हेतु कोटेशन आमंत्रित किए जाते हैं। इच्छुक प्रतिष्ठित फ़र्म संलग्न निर्धारित प्रपत्र में अपनी कोटेशन बंद लिफ़ाफ़े में दिनांक 17.12.2021 को अपराहन 15:00 बजे तक जमा करा सकते हैं। कोटेशन उसी दिन अपराहन 15:30 बजे इच्छुक कोटेशनदाताओं या उनके प्रतिनिधि की उपस्थिति में खोली जाएगी।

कार्य की सूची एवं विशिष्टियाँ (Specifications): संलग्न विवरण के अनुसार।

**नियम एवं शर्तें:**

1. उपरोक्त कार्य **Construction of Staircase at GDSQ Site Yashwant Nagar, Sirmaur (H.P.)** कार्य कराने के लिए है।
  2. कार्य विशिष्टियों (Specifications) के अनुसार कार्य आदेश जारी होने के 30 दिनों के अंदर पूरा करना अनिवार्य होगा।
  3. मुहरबंद लिफ़ाफ़े पर कार्य का नाम एवं कोटेशन संख्या आदि लिखा होना चाहिए।
  4. कोटेशन संलग्न निर्धारित प्रपत्र में फ़र्म के लेटर पैड पर होनी चाहिए।
  5. कोटेशन आमंत्रण सूचना नंबर एवं खोलने की तारीख लिफ़ाफ़े के ऊपर लिखी होनी चाहिए।
  6. दरों को शब्दों एवं संख्या दोनों में लिखा होना चाहिए।
  7. दरें सभी कर तथा अन्य प्रभार आदि यदि कोई हो तो इसका विवरण अलग से दिया जाना चाहिए।
  8. सभी कटिंग्स एवं ओवर राइटिंग्स प्रतिष्ठान के अधिकृत व्यक्ति द्वारा हस्ताक्षरित होने चाहिए।
  9. कोटेशन में दर्शायी गयी दरें 90 दिन तक लागू होगी इस मुद्दे पर किसी कोटेशनदाता की चुप्पी उसकी सहमति मानी जाएगी।
  10. कार्य आदेश जारी होने के बाद प्रभारी अभियंता के दिशा निर्देशों के साथ पूरा करना अनिवार्य होगा। कार्य को बीच में छोड़कर जाने की स्थिति में अथवा संतोषजनक न होने की स्थिति में अथवा किसी शर्त के ना पालन करने पर फ़र्म को विभाग में ब्लैकलिस्टेड/बैन कर दिया जाएगा एवं ऐसी स्थिति में अधोहस्ताक्षरी द्वारा तय की गयी पेनल्टी फ़र्म को मान्य करनी होगी।
  11. कार्य का भुगतान वास्तविक कार्य के आधार पर जाँच उपरांत किया जाएगा।
  12. कार्य पूरा होने पर इस कार्यालय में पूर्व प्राप्ति बिल (प्री-रिसिटेड बिल) दो प्रतियों में भेजना होगा। बिल में धनराशि अंको तथा शब्दों दोनों में लिखा होना चाहिए। तत्पश्चात भुगतान PFMS के माध्यम से किया जाएगा।
  13. मात्रा की अनुसूची फॉर्म संख्या-2 में दिया गया है।
  14. शर्तों के साथ भेजे गए कोटेशन स्वीकार नहीं किए जाएंगे।
  15. कार्य आदेश की मात्रा घटाने या बढ़ाने का अधिकार अधोहस्ताक्षरी के पास सुरक्षित है। इस संबंध में अधोहस्ताक्षरी का निर्णय अंतिम एवं बाध्यकारी होगा।
  16. अधोहस्ताक्षरी के पास बिना कोई कारण बताए किसी अथवा सभी कोटेशन को स्वीकृत/अस्वीकृत करने एवं सम्पूर्ण कोटेशन प्रक्रिया को निरस्त करने का अधिकार सुरक्षित है। इस संबंध में उनका निर्णय अंतिम एवं बाध्यकारी होगा।
  17. निर्धारित तिथि एवं समय के उपरांत प्राप्त होने वाला कोटेशन को स्वीकार नहीं किया जाएगा।
  18. फ़र्म GST पंजीकृत होनी चाहिए एवं GST संख्या कोटेशन में दर्शायी होनी चाहिए।
  19. कोटेशन फॉर्म-1 एवं 2 को पूर्णतया भरकर ही जमा करना होगा, संशयात्मक स्थिति एवं अधूरी सूचना की स्थिति में कोटेशन को अस्वीकार कर दिया जाएगा।
- विस्तृत जानकारी के लिए वेबसाइट <https://www.cwc.gov.in> देखें।

संलग्नक: उपरोक्तानुसार।



अधिशाली अभियंता  
ऊपरी यमुना मंडल

प्रतिलिपि:

1. अधीक्षण अभियंता (समन्वय), यमुना बेसिन संगठन, के.ज.आ., नई दिल्ली।
2. अधीक्षण अभियंता, जल विज्ञानीय प्रेक्षण परिमंडल, केन्द्रीय जल आयोग, वैशाली।
3. वेतन एवं लेखाधिकारी, केन्द्रीय जल आयोग, सेवा भवन, नई दिल्ली।
4. सॉफ्टवेयर प्रबंधन निदेशालय को के.ज.आ. की वेबसाईट पर कोटेशन आमंत्रण सूचना को अपलोड करने हेतु।
5. उपमंडलीय अभियंता (.मु), ऊपरी यमुना मण्डल, के.आ.ज., नई दिल्ली।
6. लेखानुभाग।
7. सूचना पट्ट।

**कार्य का नाम: Construction of Staircase at GDSQ Site Yashwant Nagar, Sirmaur (H.P.)**

1	Name of Company/ Firm / Agency (Attach certificate of registration):	
2	Name of proprietor / Director of Company / Firm / agency:	
3	Full Address of Reg. Office :	
4	Telephone No.	
5	FAX No.	
6	E-Mail Address :	
7	Full address of Operating/ Branch Office :	
	Telephone No.	
	FAX No.	
	E-Mail Address :	
8	PAN No. (Attach attested copy)	
9	GST Registration No. (Attach attested copy)	
10	Give details of the major similar contracts handled by the tendering Company/Firm/Agency during the last five years (attach copy)	
11	Additional information, if any (Attach separate sheet, if required)	

स्थान:

अधिकृत व्यक्ति के हस्ताक्षर:

दिनांक:

अधिकृत व्यक्ति का नाम:

एजेंसी/ फ़र्म की सील:

## मात्रा की अनुसूची

कार्य का नाम: Construction of Staircase at GDSQ Site Yashwant Nagar, Sirmaur (H.P.)

S. No.	Description of Items	Qty.	Unit	Rate in Rs.		Amount in Rs.
				Figures	Words	
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m.	16.50	sqm			
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of Soil	4.16	cum			
3	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	1	cum			
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	2.76	cum			
5	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	2.82	cum			
6	12 mm cement plaster finished with a floating coat of neat cement of mix 1:3 (1 cement : 1 fine sand).	18.08	sqm			

7	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	202.12	kg			
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	18.08	sqm			
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars	92.08	kg			
					राशि (रूपये में)	
					जी.एस.टी. @..... %	
					सकल योग	
					कुल राशि (रूपये में)	

अधिसासी अभियंता  
ऊपरी यमुना मण्डल