

NEID-II/HQ/NIQ/2021-22 634-36

Date: 16/9/22

NOTICE INVITING QUOTATION

For and on behalf of the President of India, sealed quotations are invited by the undersigned from the authorized / reputed contractor/firms for the work of "Repair and Maintenance of Guest House under NEID-II, CWC, Aizawl for the financial year 2022-23." The Sealed Quotation will be received in the office of undersigned i.e. O/o Executive Engineer, NEID-II, CWC, Aizawl during working hours up to 15:30 hrs. on or before 23/09/2022 & shall be opened on same day by 16:30 hrs. by the undersigned/authorized official in presence of interested quotations or their authorized representatives who desired to remain present at the time of opening of quotations.

Description of the work.	Estimate cost	Last date & time for receiving quotation.	Date & time for opening quotation	Location
Repair and Maintenance of Guest House under NEID-II, CWC, Aizawl.	1,98,237/-	23/09/2022 15:30	23/09/2022 16:30	NEID-II, CWC, Aizawl

Terms and Conditions :-

1. The work should be done as per the schedule of quantity within 15 days from the date of issue of work order.
2. The material using for the work should be of standard quality and free from all defects and if found not suitable the same shall be asked for replacement at his own cost.
3. The rates shall be kept valid for minimum period of 60 days from the date of opening of quotation.
4. The rates should be inclusive of all local taxes such as Service Tax/GST etc.

जलशक्तिपुरम, जोमाबोक,
आईजोल, मिजोराम-796017
दूरभाष: 0389-2352266,
ई मेल: neid2-cwc@gov.in




Jalshaktipuram, Zemabawk
Aizawl, Mizoram-796017
Tel: 0389-2352266.
E-mail: neid2-cwc@gov.in

♣जल संरक्षण-सुरक्षित भविष्य♣

♣Conserve Water- Save Life♣

5. Rates of Service tax/GST should be mentioned as applicable.
6. The rate of works should be quoted both in figures as well as in words.
7. The quotation number with date of its opening has to be clearly mentioned on the top of the quotation and sealed cover.
8. The quantities mentioned are likely to increase or decrease at the time of placing of work order.
9. Any correction in the quotation should be clearly attested.
10. Request for any advance payment will not be entertained.
11. The work carried out by the firm shall be guaranteed. The undersigned reserves the right to cancel/reject in part or full or any/all the quotation without assigning any reason thereof and without any financial involvement from either side.
12. Payment will generally be made via online mode through PFMS directly on the bank account of the bidder on production of bills.
13. Only those firms having PAN/GST etc. can be eligible to submit their quotation.
14. In case of any dispute, the decision of The Executive Engineer, NEID-II, CWC, Aizawl shall be final and binding on all concerned.


(Awdhesh Kumar)
Executive Engineer
NEID-II, CWC, Aizawl

Copy along with copies of quotation for information and wide circulation to:

1. The SDE(HQ), NEID-II, CWC, Aizawl.
2. The Accounts Branch, NEID-II, CWC, Aizawl.
3. Notice Board.

Schedule of Qunatity

Name of Work- Repair and Maintenance of Guest House under NEID-II, CWC, Aizawl.

S.No.	Description	Nos	Length (m)	Breadth (m)	Height (m)	Qty.	Units
1	Doors - Providing 1st class teak wood dressed in frames of chaukhat for doors, windows, clerestory windows fixed in position (size 2.10*1.20)						
	Room-1	1.00	7.00	0.08	0.10	0.06	
	Room-2	1.00	7.00	0.08	0.10	0.06	
	Room-3	1.00	7.00	0.08	0.10	0.06	
	Total=					0.18	m ³
2	Windows- Providing 1st class teak wood dressed in frames of chaukhat for doors, windows, clerestory windows fixed in position. window (1.60mx1.2m)						
	Hall of Guest House	5.00	6.00	0.08	0.08	0.19	
	Room-2	1.00	6.00	0.08	0.08	0.04	
	Room-3	1.00	6.00	0.08	0.08	0.04	
	Room-4	1.00	6.00	0.08	0.08	0.04	
	Room-5	3.00	6.00	0.08	0.08	0.12	
	Total=					0.43	m ³
3	Doors- Providing and fixing 1st class teak wood panelled shutters for doors etc. including M.S. butt hinges with necessary screws, etc. complete.						
	Room-1	1	1.9		1	1.90	
	Room-2	1	1.9		1	1.90	
	Room-3	1	1.9		1	1.90	
	Total=					3.80	m ²
4	Windows- Providing and fixing 1st class teak wood glazed shutters using 4mm thick plate sheet glass for doors, windows, etc. including M.S. butt hinges with necessary screws complete (D) 25 mm thick.						
	Hall of Guest House	5	1.44		1.04	7.49	
	Room-2	1	1.44		1.04	7.49	
	Room-3	1	1.44		1.04	7.49	
	Room-4	1	1.44		1.04	7.49	
	Room-5	3	1.44		1.04	7.49	
	Total=					37.45	m ²

5	Dismantling of Doors- Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc.complete and stacking within 50 metres lead (a) Of area 3 sq. metres and below						
	Room-1	1.00	1.90		1.00	1.90	
	Room-2	1.00	1.90		1.00	1.90	
	Room-3	1.00	1.90		1.00	1.90	
	Total=					3.80	m ²
6	Dismantling of Windows- Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc.complete and stacking within 50 metres lead (a) Of area 3 sq. metres and below						
	Hall of Guest House	5.00	1.44		1.04	7.49	
	Room-2	1.00	1.44		1.04	7.49	
	Room-3	1.00	1.44		1.04	7.49	
	Room-4	1.00	1.44		1.04	7.49	
	Room-5	3.00	1.44		1.04	7.49	
	Total=					37.45	m ²
7	Tile Works- Providing and ceramic glazed floor tiles of size 300x300mm or more (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make in all colours,shades, except white,ivory,greys,fume red brown, laid on 20mm thick cement mortar 1 : 4 (1cement : 4 course sand) including pointing the joints with white cement and matching pigments etc. complete. as per designed colour. (B) Matt/Antiscratch						
	Room-1						
	Long Wall	2.00	2.10		0.50	2.10	
	Short Wall	2.00	1.70		0.50	1.70	
	Room-2						
	Long Wall	2.00	2.02		0.50	2.02	
	Short Wall	2.00	1.60		0.50	1.60	
	Room-3						
	Long Wall	2.00	1.25		0.50	1.25	
	Short Wall	2.00	1.00		0.50	1.00	
	Room-4						
	Long Wall	2.00	2.10		0.50	2.10	

	Short Wall	2.00	1.70		0.50	1.70	
	Total=					13.47	m ²
8	Dismantling of Tile Works- Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. (A) For thickness of tiles 10 mm to 25 mm						
	Room-1						
	Long Wall	2.00	2.10		0.50	2.10	
	Short Wall	2.00	1.70		0.50	1.70	
	Room-2						
	Long Wall	2.00	2.02		0.50	2.02	
	Short Wall	2.00	1.60		0.50	1.60	
	Room-3						
	Long Wall	2.00	1.25		0.50	1.25	
	Short Wall	2.00	1.00		0.50	1.00	
	Room-4						
	Long Wall	2.00	2.10		0.50	2.10	
	Short Wall	2.00	1.70		0.50	1.70	
	Total=					13.47	m ²
9	Water Supply- Providing and fixing G.I. pipes complete with G.I. fitting and clamps, including cutting and making good the walls etc. (internal works- exposed on wall). (A) 20mm dai. Normal bore						
	Room-4	1.00	3.00			3.00	Rm

Rupees.....

(Signature of contractor with seal)