



84/93-96, प्रताप नगर, सांगानेर, जयपुर -302033
फोन: 0141-2790065, ई-मेल: chambalcwc@yahoo.co.in

पत्र क्रमांक: चमज/के.ज।आ/मु.-1/2022/ 3126-30

दिनांक: 10/08/2022

कोटेशन आमंत्रण सूचना (NOTICE INVITING QUOTATION)

भारत के राष्ट्रपति की ओर से अधिशाषी अभियंता, चम्बल मंडल, जयपुर द्वारा अधिकृत तथा योग्य बोली लगाने वालों से "मध्य चम्बल उप मंडल कोटा के अधीनस्थ GDQ स्थल मंडावारा में कार्यालय भवन की मरम्मत का कार्य का कोटेशन" लिखा हुआ मुहरबंद कोटेशन आमंत्रित किये जाते हैं।

Sealed quotation super scribed as "Quotation for Repairing work of Office Building at GDQ Site Mandawara under MCSD, CWC, Kota" are invited for and on behalf of the President of India by the Executive Engineer, Chambal Division, CWC, Jaipur from the authorized and eligible bidders.

नियम एवं शर्तें (Terms & Conditions)

- मुहरबंद कोटेशन अधिशाषी अभियंता, चम्बल मंडल, केन्द्रीय जल आयोग, जयपुर के कार्यालय में दिनांक 19.08.2022 अपरान्ह 15:00 बजे तक या उससे पूर्व प्राप्त हो जानी चाहिए, जो उसी दिन अर्थात् 19.08.2022 अपरान्ह 15:30 बजे अधोहस्ताक्षरी तथा बोली लगाने वाले या उसके प्रतिनिधि जो उपस्थित रहना चाहे की उपस्थिति में खोली जाएगी।
The sealed quotation shall reach to the office of Executive Engineer, Chambal Division, CWC, Jaipur on or before 19.08.2022 upto 15:00 Hrs and will be opened on the same day i.e. 19.08.2022 at 15:30 Hrs in the presence of undersign and bidders or their representative who may likely to be present at the time of opening of quotations.
- मुहरबंद कोटेशन के साथ रुपये 3995/- की ईएमडी डिमांड ड्राफ्ट/बैंकर्स चेक/एफडीआर के रूप में अधिशाषी अभियंता, चम्बल मंडल, केजआ, जयपुर के पक्ष में संलग्न करना अनिवार्य है। बिना ईएमडी के प्राप्त कोटेशन को खारिज कर दिया जाएगा।
The EMD of Rs. 3995/- in the form of Demand Draft/Bankers Cheque/FDR in favor of Executive Engineer, Chambal Division, CWC, Jaipur should be enclosed with sealed quotation. Quotations received without EMD will be summarily rejected.
- कोटेशन की स्वीकृति पर, सफल बोलीदाता को उद्धृत राशि के 3% की दर से PG जमा करना आवश्यक है। पीजी जमा करने पर कार्य प्रारंभ करने के लिए आवश्यक पत्र जारी किया जाएगा।
On acceptance of quotation, the successful bidder is required to submit PG @ 3% of Quoted amount. On submission of PG necessary letter for commencement of work will be issued.
- कार्य करने की अवधि कायदिस जारी होने के बाद से 30 दिन की रहेगी।
Work shall be carried within 30 days after issue of work order.
- कोटेशन में दर्शायी दरे अंको तथा शब्दों दोनों में लिखा होना चाहिए।
Rates shall be quoted both in figure as well as words also in the quotation.

6. उक्त कार्य हेतु इस्तेमाल में लिया गया सामान अच्छी गुणवत्ता का एवं दिए गये विशेष विवरण के अनुसार तथा त्रुटी रहित होना चाहिए।
The material used for above mentioned work must be of standard quality and as per specifications and free from all the defects.
7. कोटेशन में दर्शायी दरे के कोटेशन खुलने के दिन से कम से कम 60 दिन तक वैध होनी चाहिए।
Rates quoted should be valid at least for 60 days from date of opening.
8. कोटेशनर के पास PAN/TIN/Service Tax Number/GST No. होना चाहिए।
Quotationers must have PAN/TIN/Service Tax Number/GST No.
9. अधोहस्ताक्षरी किसी एक या सभी कोटेशन को बिना कारण बताये स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता हैं।
Undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
10. कार्य की मात्रा कार्यदेश के समय या कार्य करने के दौरान बढ़ाई या कम की जा सकती हैं।
The quantity of work may be increased or decreased at the time of work order or during the time of execution.
11. कार्य के संतोषजनक पूर्ण होने के बाद सम्पूर्ण भुगतान को ECS/RTGS के द्वारा किया जायेगा।
Payment will be made through ECS/RTGS, only after satisfactory completion of work.
12. आवश्यक कटौती, यदि कोई हैं तो, को नियमानुसार बीजक में से कर ली जाएगी।
Necessary deduction, if any, as per rules will be made from the bill.



आधेशाषी अभियंता
चम्बल मंडल, के.ज.आ., जयपुर

प्रतिलिपि सूचनार्थ:

1. अधीक्षण अभियंता, ज.वि.प्रे.परि., के.ज.आ., वैशाली।
2. उप मंडलीय अभियंता, म.च. उ.मं., कोटा।
3. आशुलिपिक चम्बल मंडल, जयपुर।
4. सूचना पट्ट, चम्बल मंडल, जयपुर।
5. सीडबल्यूसी वेब पोर्टल।

Schedule of Quantity

Name of Work : Quotation for Repairing work of Office Building at GDQ Site Mandawara under MCSD, CWC, Kota

S. No.	Description of items	Qty.	Unit	Rate (incl. GST)	Amount (incl. GST)
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections. power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm. at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.5 mm thick tapered edge Glass Reinforced Gypsum (GRG) board conforming to IS: 2095- (Part 3):1996 (Boards with BIS certification marks)	56.61	sqm		
2	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 meters lead	13.47	sqm		
3	12 mm cement plaster finished with a floating coat of neat cement of mix 1:4 (1 cement : 4 fine sand).	43.15	sqm		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work upto plinth level: 1:4:8 (1 cement : 4 coarse sand (zone III):8 graded stone aggregate 40 mm nominal size)	0.67	cum		

5	Providing and laying vitrified floor tiles in different sizes(thickness to be specified by the manufacturer) with water absorption less than 0.08% and confirming to IS:15622, of approved make,in all colors and shades ,laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc complete Size of Tile 500x500 mm	11.09	sqm		
6	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc.. complete.	4.10	sqm		
7	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required: Size 450x300x150 mm	1.000	No.		
8	Providing and fixing CP Brass bib cock of approved quality confirming to IS :8931 15 mm nominal bore	3	no		
9	Polyethylene water storage tank with cover and suitable locking arrangement: 500 litre	1	no		
10	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622(thickness to be specified by the manufacturer) of approved make in all colors ,shades except burgundy ,bottle green ,black of any size as approved by Engineer in charge ,in skirting ,risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including painting with white cement mixed with pigment of matching shade complete.	6.57	sqm		
11	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	419.48	sqm		
12	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion,(i) Single socketed pipes.110 mm diameter	28	meter		
13	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 110 mm Bend	10	no		
14	Chlorinated Polyvinyl - chloride (CPVC) pipe 25 mm nominal dia	20	meter		

15	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	6	points		
16	Supplying and fixing PVC batten/ angle holder including connections etc. as required.	6	Each		
17	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
I	5/6 A switch	7	Each		
II	15/16 A switch	2	Each		
III	3 pin 5/6 A socket outlet	3	Each		
IV	6 pin 15/16 A socket outlet	2	Each		
V	Telephone socket outlet	1	Each		
18	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2	Each		
19	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	40	meter		
Total Amount					
Total in words					

* Terms & conditions: - As per NIQ

Issuing Authority

Sd/-

Executive Engineer
Chambal Division

Signature of Contractor

Seal
Address