



सत्यमेव जयते

पत्रांक:- नि.य.उप-2/आगरा/2023/को.आ.सू./202-05

दिनांक :- 12/05/2023

कोटेशन आमंत्रण सूचना

भारत के राष्ट्रपति की ओर से अधोहस्ताक्षरी द्वारा निचली यमुना अनुमंडल-2, आगरा के अंतर्गत क्वारी नदी पर नैपरी स्थल पर मस्टो टाइप बेंच मार्क (एमटीबीएम) के निर्माण के लिए निम्न कार्य हेतु मुहरबंद/बंद कोटेशन आमंत्रित किए जाते हैं। (संलग्न मात्रा के बिल के अनुसार)


कोटेशन 22.05.2023 को 15:00 बजे तक या उससे पहले अधोहस्ताक्षरी के कार्यालय में पहुंच जाना चाहिए। और उसी दिन 15:30 बजे खोली जाएगी। इच्छुक कोटेशन दाताओं की उपस्थिति में, यदि कोई हो। यदि उक्त तिथि को अपरिहार्य कारणों से कोटेशन नहीं खोला जा सका तो अगले कार्य दिवस को बिना किसी सूचना के खोला जायेगा।

नियम एवं शर्तें

1. काम सीपीडब्ल्यूडी के विनिर्देशों और प्रभारी अभियंता के निर्देश के अनुसार किया जाना चाहिए।
2. दरें अंको एवं शब्दों दोनों में अंकित की जानी चाहिए।
3. जीएसटी पंजीकरण संख्या, पैन संख्या और किसी भी सिविल कार्य का अनुभव प्रमाण पत्र की हस्ताक्षरित प्रति संलग्न करें।
4. नियमानुसार बिल से आयकर एवं अन्य कर आदि की कटौती की जायेगी।
5. कार्यदेश जारी होने की तिथि से तीस दिनों के भीतर कार्य पूरा किया जाना चाहिए।
6. काम संतोषजनक ढंग से पूरा होने पर भुगतान ऑनलाइन/ पीएफएमएस द्वारा किया जाएगा।
7. कोई अग्रिम भुगतान नहीं किया जाएगा।

संलग्न: मात्रा की अनुसूची।



  
12/05/23  
दौलत राम बैरवा  
उपमंडलीय अभियंता

प्रतिलिपि :-

- ✓ 1. श्रीमान् अधिशासी अभियन्ता, निचली यमुना मंडल आगरा को सूचनार्थ एवं CWC Tender Website पर अपलोड करने हेतु प्रेषित है।
2. लेखा शाखा, निचली यमुना मंडल आगरा।
3. नोटिस बोर्ड निचली यमुना उपमंडल-2 आगरा।
4. कनिष्ठ अभियन्ता, निचली यमुना उपमंडल-2 आगरा।







पत्रांक:- नि.य.उप-2/आगरा/2023/NIQ/ २०२-०५

दिनांक :- १२/०५/२०२३

कोटेशन आमंत्रण सूचना


Sealed/closed quotations are hereby invited by the undersigned on behalf of President of India from the contractors for the following work **Construction of Musto Type Bench Mark (MTBM) at Naipri Site at river Kwari under Lower Yamuna Sub Division-2, Agra.** (As per Schedule of quantity enclosed.)

The quotation should reach in the office of the undersigned on or before 22.05.2023 up to 15:00 hrs. and will be opened on the same day at 15:30 hrs. in the presence of intending quotationers, if any. If quotation could not be opened on aforesaid date due to unavoidable circumstances, then same will be opened on next working day without any further notice.

Terms & Conditions

1. The work should be done as per CPWD specification & direction of Engineer in-charge.
2. Rates should be quoted both in figure and words.
3. Signed copy of GST Registration number, PAN No and Experience certificate any civil work should be attached.
4. Income tax & other tax etc. shall be deducted from the bill as per rule.
5. The work should be completed within thirty days from the date of issue of work order.
6. The payment will be made by Online/PFMS after satisfactory completion of work.
7. No advance payment shall be made.

Enclosed: Schedule of quantity.

  
12/05/23  
(दौलत राम बैरवा)  
उपमंडलीय अभियंता

प्रतिलिपि :-

1. श्रीमान् अधिशासी अभियन्ता, निचली यमुना मंडल आगरा को सूचनार्थ एवं CWC Tender Website पर अपलोड करने हेतु प्रेषित है।
2. लेखा शाखा, निचली यमुना मंडल आगरा।
3. नोटिस बोर्ड निचली यमुना उपमंडल-2 आगरा।
4. कनिष्ठ अभियन्ता, निचली यमुना उपमंडल-2 आगरा।





## Schedule of Quantity

NAME OF WORK: Construction of Musto Type Bench Mark (MTBM) at Naipari Site at river Kwari under Lower Yamuna Sub Division-II, Agra

| It. no.                                  | Description of work  | Qty   | Unit  | Rate | Amount (in figure) | Amount (in words) |
|--|--|-------|-------|------|--------------------|-------------------|
| <b>Part A (Musto Type Benchmark)</b>     |  |       |       |      |                    |                   |
| 1  | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. |       |       |      |                    |                   |
|  | Musto type bench mark  | 2.025 | cum   |      |                    |                   |
| 2  | Centering and shuttering including strutting, propping etc. and removal of form work for: foundation, footings, bases for column.  |       |       |      |                    |                   |
|  | Musto type bench mark  | 5.400 | sqm   |      |                    |                   |
| 3  | Providing & laying in position cement concrete of specified grade excluding the cost of centering & shuttering. All work up to plinth level 1:5:10 (1 cement : 5 coarse sand (Zonell) : 10 graded stone aggregate 40 mm nominal size.  |       |       |      |                    |                   |
|  | Musto type bench mark  | 0.338 | cum   |      |                    |                   |
| 4  | Providing & laying in position cement concrete of specified grade excluding the cost of centering & shuttering. All work up to plinth level 1:2:4 (1 cement : 2 coarse sand (Zonell) : 4 graded stone aggregate 40 mm nominal size.  |       |       |      |                    |                   |
|  | Musto type bench mark  | 1.634 | cum   |      |                    |                   |
| 5  | Stone work ashlar sunk or moulded or sunk and moulded upto floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) including pointing with white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade : White sand stone.  |       |       |      |                    |                   |
|  | Musto type bench mark  | 0.077 | cum   |      |                    |                   |
| 6  | Brick work with common burnt clay FPS (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand).  |       |       |      |                    |                   |
|  | Musto type bench mark  | 1.208 | cum   |      |                    |                   |
| 7  | Providing and filling of stone aggregate (single size) 20 mm nominal size 15 cm over the top of white stone, inside the musto type bench mark.   |       |       |      |                    |                   |
|  | Musto type bench mark  | 0.233 | cum   |      |                    |                   |
| 8  | Providing and filling of sand (35 cm over the filled stone rubbles) upto top of Musto type bench mark.   |       |       |      |                    |                   |
|  | Musto type bench mark  | 0.224 | cum   |      |                    |                   |
| 9  | 12 mm cement plaster finished with a floating coat of neat cement of mix 1:4 (1 cement : 4 fine sand).   |       |       |      |                    |                   |
|  | Musto type bench mark  | 8.510 | sqm   |      |                    |                   |
| 10                                       | Providing & fixing of GI pipe 25 mm diameter for drainage purpose on downhill.   |       |       |      |                    |                   |
|  | Musto type bench mark  | 0.350 | metre |      |                    |                   |
| 11                                       | Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.  |       |       |      |                    |                   |
|  | Musto type bench mark  | 8.510 | sqm   |      |                    |                   |
| 12                                       | Finishing walls with Premium Acrylic Smooth exterior paint with silicone additives of required shade : New work (two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)  |       |       |      |                    |                   |
|  | Musto type bench mark  | 8.510 | sqm   |      |                    |                   |
| Total amount including GST (in figures): |  |       |       |      |                    |                   |
| Total amount including GST (in words):   |  |       |       |      |                    |                   |

Signature of Contractor with Seal