

I/14569/2020(4)

भारत सरकार
जल संसाधन, नदी विकास एवं गंगा संरक्षण
मंत्रालय
केंद्रीय जल आयोग
कार्यालय अधिशासी अभियंता
निचली ब्रह्मपुत्र मण्डल
जल भवन, हाकिमपाड़ा, जलपाईगुड़ी - 735101
दूरभाष / (फैक्स) : 03561-230677, 220770



GOVERNMENT OF INDIA
MINISTRY OF WATER RESOURCES, RIVER DEVELOPMENT
GANGA REJUVENATION
CENTRAL WATER COMMISSION
O/O THE EXECUTIVE ENGINEER
LOWER BRAHMAPUTRA DIVISION
JAL BHAWAN, HAKIM PARA,
JALPAIGURI-735101
email- eelbd-cwc@gov.in

No. LBD/DB-19(14)/2019-20

Dated: 17th January, 2020**Notice Inviting Quotation**

On behalf of President of India, sealed Quotations are invited for the following works by the undersigned from the bonafide/Govt. approved firms/Dealers dealing with said item/works as per the following terms and conditions by **15.00 hrs. on 25.01.2020**. The quotation will be opened on same day i.e. **25.01.2020 at 15.30 hrs.**

Sl No	Description of Works	Quantity	Unit	Rates (in figures as well as in words)	Amount (in Rupees)
1	Structural works in roof trusses with tubular sections conforming to IS: 806-1957 & IS: 1161-1958 connected to one another with bracket, gusset cleats as per design, direction of Engineer-in-charge complete including cutting to requisite size, fabrication with necessary metal arc welding conforming to IS: 816- 1956 & IS: 9595 using electrodes of approved make and brand conforming to IS:814- 1957, haulage, hoisting and erection all complete. The rate includes the cost of rolled steel section, consumables such as electrodes, gas and hire charge of all tools and plants and labour required for the work including all incidental charges such as electricity charges, labour insurance charges etc. Payment to be made on the basis of calculated weight of structural tubular members as specified in relevant IS code in finished work. Payment for gusset, bracket, cleat may be made by adding the actual weight of such items with weight of finished structural members. The rates are considered for a height of erection 8 m. / 2nd floor level from the ground. Add 1.5 % extra over the rate for each additional floor or 4m. beyond the initial 8 m. or part thereof. i) For trusses spanning up to 12.00 m	0.191	MT		
2.	Labour for hoisting and placing in proper position (up to 1st floor level) departmental R.S. joists, channels, angles. Tees, plates etc. including fitting and fixing same with bolts and nuts, if necessary (but excluding cost of such bolts and nuts)	1.914	Qtl.		

I/14569/2020(4)

Sl No	Description of Works	Quantity	Unit	Rates (in figures as well as in words)	Amount (in Rupees)
3.	Fitting and fixing old pieces of asbestos, G.C.I. or C.I. sheets or plain sheets including closing old holes with washers and sheet-bolts and nuts, etc. and including fixing the same to supporting frame with necessary hook-bolts, washers, putty etc. (excluding cost of sheets). (Payment to be made on area of finished work.) (ii) With all new fittings including the cost thereof.(a) In roof	8.94	Sqm.		
4.	Fitting and fixing old pieces of asbestos, G.C.I. or C.I. sheets or plain sheets including closing old holes with washers and sheet-bolts and nuts, etc. and including fixing the same to supporting frame with necessary hook-bolts, washers, putty etc. (excluding cost of sheets). (Payment to be made on area of finished work.) (ii) With all new fittings including the cost thereof. (a) In wall	31.63	Sqm.		
5.	M.S. works in framed gratings of window etc.made of round or square bars and frame work or M.S. flats (with the bars securely fixed to the flat bar frame) with or without intermediate flat bar stiffener and fixed with necessary screws etc. complete , as directed. In ground floor.	1.431	Qtl.		
6.	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm.	3.750	%Cum		
7.	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation.	0.750	%Cum		
8.	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	8.00	Sqm.		
9.	Labour for laying single brick flat soling including ramming and dressing bed to proper level and filling joints with powdered earth.	8.00	Sqm.		
10.	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes.	3.138	Cum.		

I/14569/2020(4)

Sl No	Description of Works	Quantity	Unit	Rates (in figures as well as in words)	Amount (in Rupees)
11.	Brick work with 1st class bricks in cement mortar (1:4) (b) In superstructure, ground floor	1.65	Sqm.		
12.	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	2.50	%Cum		
13	Total				
14	GST (@12% on sl no 13)				
15	Total Including GST				
16	Labour welfare cess @1% on Sl. No.-15				
17	Grand total				

Terms and conditions

- The rates are to be quoted for complete and satisfactory work at Right Bank of Jaldhaka River near Jaldhaka Road Bridge at NH-31 GDSQ Site under JLT Sub-Division, CWC, Jalpaiguri.
- The rates should be valid for **60 (Sixty)** days from the due date of opening of quotation.
- Work shall be completed within **30 (Thirty)** days from the date of issue of work order with the satisfaction of competent authority which shall be final in this regard.
- The rate must be quoted both in figures and in words.
- The work shown above is tentative and may be increased / decreased at the time of placing work order. Final measurement will be taken after completion of work and the payment will be made on the basis of actual work done.
- Any accident during execution of work will be borne by the firms/agency.
- No advance payment will be made before completion of work. The payment will be made by Net Banking on receipt of bills in triplicate after completion of full and satisfactory work.
- Applicable tax as per rule will be deducted from bill.
- The undersigned reserve the right to reject a part or the whole of quotations without assigning any reason thereof.
- The quotations should be attached with PAN card, GST certificate, trade licence and Credentials of the firm for similar nature of work.
- Earnest Money of **Rs. 1309.00 (Rupees one thousand three hundred nine) only** in the form of Treasury Challan, deposit at call receipt or fixed deposit receipt/Demand Draft/Banker's cheque of a schedule bank drawn in favour of Executive Engineer, Lower Bramhaputra Division ,CWC,Jalpaiguri payable at Jalpaiguri should be deposited by the Bidder within the due date and time to the Executive Engineer, Lower Bramhaputra Division ,CWC,Hakimpara, Jalpaiguri-735101.
- The successful bidder will have to deposit (5% of ordered value) as Performance guarantee Deposit before placing the order within 7 days of the receipt of the formal letter of acceptance. The performance guarantee will be furnished in the form of Deposit at Call receipt of any scheduled bank/Banker's cheque of any scheduled bank/Demand Draft of any scheduled bank/ Pay order of any scheduled bank in accordance with the prescribed form in favour of Executive Engineer, Lower Bramhaputra Division , Central Water Commission, Jalpaiguri -735101, West Bengal. The performance guarantee should remain valid for a period of **60 days** beyond the date of completion of all the contractual obligations of the Bidder.
- The envelope containing quotation should be super-scribed **"Quotation for "Construction of temporary hutment at NH-31 Site for telemetry installation"** mentioning due date of opening.

I/14569/2020(4)

14. The quotations should be addressed to **Executive Engineer, Lower Bramhaputra Division , Central Water Commission, Hakimpara, Jalpaiguri -735101.**

(Sudipta Sarkar)

Executive Engineer

For and on behalf of President of India

Copy for kind information to: -

1. Superintending Engineer, Investigation Circle,CWC, Gangtok – 737102 w.r.t e-office letter no. 9/143/2018-DB/IC/SKM/VOL-IV Dated 09.01.2020
2. Assistant Accounts Officer, L.B. Division, CWC, Jalpaiguri
3. Sub-Divisional Engineer(HQ), L.B. Division, CWC, Jalpaiguri

Copy forwarded with the request to display the enclosed NIT on the notice board for wide publicity to: -

1. The Assistant Executive Engineer, JLT .Sub-Division, CWC, Jalpaiguri-735101.
2. The Sub-Divisional Engineer, TRS Sub-Division, CWC, Cooch Behar- 736101.
3. The Sub-Divisional Engineer, UTUM Sub-Division, CWC, Siliguri,
4. Notice Board, L.B. Division, CWC, Jalpaiguri.
5. Website <https://eprocure.gov.in/epublish> & www.cwc.nic.in