

I/69611/2021(1)



भारत सरकार/GOVERNMENT OF INDIA
केंद्रीय जल आयोग/CENTRAL WATER COMMISSION
अधिसासी अभियन्ता कार्यालय/OFFICE OF EXECUTIVE ENGINEER
मेघना अन्वेषण मंडल/MEGHNA INVESTIGATION DIVISION

E-mail: midcwc-meg@nic.in
 midcwc@gmail.com
 Tel: 0364-2521226
 Fax: 0364-2521226

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the President of India for works as detailed below. **The quotations should reach in the Office of the undersigned on or before 08.09.2021 up to 16.00 hrs** and will be opened on **09.09.2021 at 10.30 hrs** in the presence of quotationers or their authorized representatives, if any.

The undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.

S. No.	Description and specifications of work	Quantity	Unit
1.	Installation of Rain Gauge with Fencing at 15 Nos. of sites under Meghna Investigation Division, CWC as per the drawing attached as Annexure- 1	15	Nos.
2.	Estimated cost: ₹ 1,98,000.00 (Rupees One lakh ninety-eight thousand only)		

Terms & Conditions:

- The quotations duly signed should be properly sealed and dropped in quotation Box in the office of the Executive Engineer, Meghna Investigation Division, CWC, 4th Floor MSHFCSL Building, Nongrim Hills, Shilong-793003. The sealed envelope should be super scribed **“Installation of Rain Gauge at 15 Nos. of Sites under MID due on 08.09.2021 up to 16.00 hrs”**.
- Only those firms having GST number are eligible to submit their quotation.
- The undersigned does not bind him to accept the lowest quotation and reserve the right to accept or reject any or all the quotations without assigning any reason thereof.
- All materials required for the work are to be supplied by the contractor. The material must be of standard quality and as per specifications and free from all defects. The material if found defective subsequently or not conforming to the specifications as stated above, have to be replaced by the firm without any additional charges.
- Before starting the work, material shall be got approved from the Sub-Divisional Engineer, MID, CWC, Shillong.
- The work shall have a warranty period of minimum six months from the date of installation.
- The work is estimated to cost ₹ 1,98,000/- (Rupees One lakh ninety-eight thousand only). This estimate, however, is given merely as rough guide.
- The quantity of materials may be increased or decreased at the time of work order without assigning any reason thereof.
- Successful bidder needs to submit the Security deposit @ 5% of Bid amount. Security Deposit will be valid after 6 months from the date of completion of work.
- The work of Installation of Rain Gauge at sites location in all respects should be completed within 60 days from the date of issue of work order.
- The rate quoted should be inclusive of all duties, taxes and other levies as applicable.
- The validity of quotation for acceptance shall be 90 days and rate quoted should be remains valid for 180 days from the date of opening.
- The rate should be quoted both in words and in figures. Corrections/ overwriting in the quotation, if any, shall be made by initialing, dating and re-writing.

I/69611/2021(1)

14. Payment will be made by PFMS, online payment on production of bill in triplicate after satisfactory completion of work in all respect and as per specification. Agency may please produce Bank account details Mandate form along with bill.
15. Security deposit @ 5% of the total amount will be deducted from the bill amount and the same will be released after 30 days beyond the completion of warranty period.

**Executive Engineer
MID, CWC, Shillong**

Copy to:

1. The Superintending Engineer, Meghna Circle, CWC, Silchar.
2. The Sub-Divisional Engineer, MISD-I, CWC, Shillong.
3. Accounts Branch, Meghna Investigation Division, CWC.
4. Notice board of O/o Executive Engineer, MID, CWC, Shillong.
5. Details of this NIQ are also available on CPP/CWC Portal.

I/69611/2021(1)

Bill of Quantities (BOQ)

Installation of Rain Gauge at 15 Nos. of sites under MID, CWC, Shillong:

Sl. No.	Description and specifications of item	Unit	Quantity	Rate (₹)	Amount (₹)
1	Earthwork in excavation upto a depth of 2m below the existing ground level for foundation trenches of foundations, footings of column/ walls, retaining walls, septic tank etc. including bailing out water where necessary and removal of surplus earth with all lead and lifts as directed and specified for the following classification of soils. (c) In soft or laminated rock or medium shale	cum	0.198		
2	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately). (a) In prop. 1:3: 6 (1 cement:3 coarse sand :6 coarse agg. by volume (using mixture machine).	cum	0.132		
3	15 mm thick Cement plaster in single coat on rough side of single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed. (a) In cement mortar 1:3	sqm	0.36		
4	Providing &Supplying of 1.80m high barbed wire fencing fixed to angle iron post at site including drilling of holes every 3.00m apart, E/W & cc of base in propn.1:3:6, painting with black enamel paint, etc. as per CPWD Specifications 16.17 vol-2 complete as directed.	Rm	8		
Amount for installation of 01 Rain Gauge (in ₹)					
Total no. of Rain Gauge =15 Nos.					
Amount for installation of 15 Rain Gauge (in ₹)					
GST					
Grand Total (in ₹)					

(Rupees ----- only)

GST No of the agency:

Pan No .of the agency:

(Signature of agency with seal)