भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग उत्तर - पूर्वी अन्वेषण मंडल -३ ,ईटानगर



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission North Eastern Investigation Division—III, Itanagar

File No. NEID-3/HQ-51/2020-21/ \233-35

Date: 17.11.2020

## NOTICE INVITING QUOTATION

For and on behalf of the President of India, the Executive Engineer, NEID-III, CWC, Itanagar invites the sealed quotation for "R&M Work of Flooring and renovation of Type-II quarter at NEID-III, CWC, Itanagar." from bonafide and reputed firms as per the Technical Details and terms and conditions mentioned below.

Name of the Work: R&M Work of Flooring and renovation of Type-II (Type-II/03) quarter at NEID-III, CWC, Itanagar

## (Terms & Conditions):-

- 1. The rates quoted should be F.O.R. O/o Executive Engineer, NEID-3, CWC, Itanagar inclusive of all the taxes INCLUSIVE GST. No other claims will be entertained in this
- 2. EMD amounting to Rs. 4000/- (Rupees Four Thousand Only) in form of DD or FDR in favor of Executive Engineer, NEID-3, CWC, Itanagar shall be submitted along with bid.
- 3. Bidders are requested to visit the site before submitting the bid to understand the requirements of work.
- 4. The sealed quotation superscripted with the words "R&M Work of Flooring and renovation of Type-II quarter at NEID-III, CWC, Itanagar" duly signed should reach this office on or before 15:00 hours of 24.11.2020 and will be opened on 25.11.2020 at 16:00 hours in the presence of contractor or their authorized representatives.
- 5. The quality of materials used and work must be standard and will be checked before acknowledgement.
- 6. On behalf of the President of India, undersigned reserves the right to reject any or all the quotations and to alter the quantity without assigning any reasons thereof.
- 7. The rates shall be valid for 60 days minimum from the date of opening of the quotation.
- 8. The work shall be carried out within 20 days from the date of issue of the Work Order. Extension of time will be allowed only after submission of sufficient reasons of delay.
- 9. The payment will be made through PFMS after actual measurement of work on successful completion for which bill in triplicate shall be submitted to this Office.
- Rates shall be mentioned both in words and figures.
- 11. All the corrections and over writings should be duly attested.
- 12. Taxes as applicable will be deducted from the bill at the time of payment.
- 13. Any other rules of CPWD codes and its amendments as applicable will be binding on the successful bidder.
- 14. The Quotation shall be in prescribed format as per annexure-1 (Schedule of Quantities/Scope of Work).

पोस्ट ऑफिस बॉक्स सं -१४४ ,चिम्पू ,ईटानगर अरुणाचल प्रदेश - ७९११११ दूरभाप: 0360-2203510 ई मेल: eeneid3-cwc@gov.in जल संरक्षण-सुरक्षित भविष्य



PO Box No. 144, Chimpu, Itanagar Arunachal Pradesh - 791111 Tel: 0360-2203510 E-mail: eeneid3-cwc@gov.in ♦Conserve Water- Save Life ♦

भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission North Eastern Investigation Division—III, Itanagar

15. In view of communication break due to any unforeseen circumstances beyond human उत्तर - पूर्वी अन्वेषण मंडल -३ ,ईटानगर control, intended bidders may also send their sealed quotations through Registered Post/ Speed Post at the following correspondence address-

O/o Executive Engineer, NEID-III, CWC Complex, Chimpu, Near VKV School, Itanagar, Arunachal Pradesh, PIN-791113

17/11/2020

(Executive Engineer) (For and on behalf of President of India)

Copy to:

- 1. Accounts Branch, NEID-III, CWC, Itanagar
- 2. Notice Board, NEID-III, CWC, Itanagar
- 3. JE (HQ) for uploading on CPP portal

(Executive Engineer)

जल संरक्षण-सुरक्षित भविष्य



भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग उत्तर - पूर्वी अन्वेपण मंडल -३ ,ईटानगर



Government of India Ministry of Jal Shakti Department of Water Resources, RD & GR Central Water Commission North Eastern Investigation Division—III, Itanagar

## Annexure-1: Schedule of Quantities/ Scope of Work

SI.No.	Particulars of item	Qty	Unit	Rate (Rs)	Amt (Rs)
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	182.85	sqm		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	134.64	sqm		
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:	182.85	sqm		
	One or more coats on old work		1		
4	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy,bottle green, black of any size as approved by the Engineer-incharge,in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	20,00	sqm		
5	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS: 15622, of approved make, in al colours, shades, except White, Ivory, Grey, Fume rections, laid on 20 mm thick Cement Mortar 1:4 (Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc, complete.	2.38	s sqm		

पोस्ट ऑफिस बॉक्स सं -१४४ ,चिम्पू ,ईटानगर अरुणाचल प्रदेश - ७९११११ दूरभाप: 0360-2203510 ई मेल: eeneid3-cwc@gov.in

जल संरक्षण-सुरक्षित भविष्य



भारत सरकार जल शक्ति मंत्रालय जल संसाधन नदी विकास एवं गंगा संरक्षण विभाग केंद्रीय जल आयोग



Government of India
Ministry of Jal Shakti
Department of Water Resources, RD & GR
Central Water Commission

North Eastern Investigation Division—III, Itanagar

- पूर्वी <sup>३</sup>       	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).  Sizes of Tile 600x600 mm	40.51	sqm	
7	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).	10.59	sqm	
8	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length	0.51	Cum	
	Kiln seasoned and chemically treated hollock wood			
	Total Amount-Including GST	The annual and		



