



84/93-96, प्रताप नगर, सांगानेर, जयपुर -302033  
फोन: 0141-2790065, ई-मेल: chambalcwc@yahoo.co.in

पत्र क्रमांक: चमज/के.ज।आ/मु.-1/2022/ 2381-85

दिनांक: 29/6/2022

### **कोटेशन आमंत्रण सूचना ( NOTICE INVITING QUOTATION )**

भारत के राष्ट्रपति की ओर से अधिशाषी अभियंता, चम्बल मंडल, जयपुर द्वारा अधिकृत तथा योग्य बोली लगाने वालों से "मध्य चम्बल उप मंडल कोटा के कार्यालय भवन के मरम्मत का कोटेशन" लिखा हुआ मुहरबंद कोटेशन आमंत्रित किये जाते हैं।

Sealed quotation super scribed as "Quotation for Repairing of Office Building of Middle Chambal Sub Division, CWC, Kota" are invited for and on behalf of the President of India by the Executive Engineer, Chambal Division, CWC, Jaipur from the authorized and eligible bidders.

#### **नियम एवं शर्तें (Terms & Conditions)**

- मुहरबंद कोटेशन अधिशाषी अभियंता, चम्बल मंडल, केन्द्रीय जल आयोग, जयपुर के कार्यालय में दिनांक 07.07.2022 अपराह्न 15:00 बजे तक या उससे पूर्व प्राप्त हो जानी चाहिए, जो उसी दिन अर्थात् 07.07.2022 अपराह्न 15:30 बजे अधोहस्ताक्षरी तथा बोली लगाने वाले या उसके प्रतिनिधि जो उपस्थित रहना चाहे की उपस्थिति में खोली जाएगी।  
The sealed quotation shall reach to the office of Executive Engineer, Chambal Division, CWC, Jaipur on or before 07.07.2022 upto 15:00 Hrs and will be opened on the same day i.e. 07.07.2022 at 15:30 Hrs in the presence of undersign and bidders or their representative who may likely to be present at the time of opening of quotations.
- मुहरबंद कोटेशन के साथ रुपये 3795/- की ईएमडी डिमांड ड्राफ्ट/बैंकर्स चेक/एफडीआर के रूप में अधिशाषी अभियंता, चम्बल मंडल, केजआ, जयपुर के पक्ष में संलग्न करना अनिवार्य है। बिना ईएमडी के प्राप्त कोटेशन को खारिज कर दिया जाएगा।  
The EMD of Rs. 3795/- in the form of Demand Draft/Bankers Cheque/FDR in favor of Executive Engineer, Chambal Division, CWC, Jaipur should be enclosed with sealed quotation. Quotations received without EMD will be summarily rejected.
- कोटेशन की स्वीकृति पर, सफल बोलीदाता को उद्धृत राशि के 3% की दर से PG जमा करना आवश्यक है। पीजी जमा करने पर कार्य प्रारंभ करने के लिए आवश्यक पत्र जारी किया जाएगा।  
On acceptance of quotation, the successful bidder is required to submit PG @ 3% of Quoted amount. On submission of PG necessary letter for commencement of work will be issued.
- कार्य करने की अवधि कार्यदिश जारी होने के बाद से 30 दिन की रहेगी।  
Work shall be carried within 30 days after issue of work order.
- कोटेशन में दर्शायी दरे अंको तथा शब्दों दोनों में लिखा होना चाहिए।  
Rates shall be quoted both in figure as well as words also in the quotation.

6. उक्त कार्य हेतु इस्तेमाल में लिया गया सामान अच्छी गुणवत्ता का एवं दिए गये विशेष विवरण के अनुसार तथा त्रुटी रहित होना चाहिए।  
The material used for above mentioned work must be of standard quality and as per specifications and free from all the defects.
7. कोटेशन में दर्शायी दरे के कोटेशन खुलने के दिन से कम से कम 60 दिन तक वैध होनी चाहिए।  
Rates quoted should be valid at least for 60 days from date of opening.
8. कोटेशनर के पास PAN/TIN/Service Tax Number/GST No. होना चाहिए।  
Quotationers must have PAN/TIN/Service Tax Number/GST No.
9. अधोहस्ताक्षरी किसी एक या सभी कोटेशन को बिना कारण बताये स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता है।  
Undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
10. कार्य की मात्रा कार्यदिश के समय या कार्य करने के दौरान बढ़ाई या कम की जा सकती है।  
The quantity of work may be increased or decreased at the time of work order or during the time of execution.
11. कार्य के संतोषजनक पूर्ण होने के बाद सम्पूर्ण भुगतान को ECS/RTGS के द्वारा किया जायेगा।  
Payment will be made through ECS/RTGS, only after satisfactory completion of work.
12. आवश्यक कटौती, यदि कोई है तो, को नियमानुसार बीजक में से कर ली जाएगी।  
Necessary deduction, if any, as per rules will be made from the bill.



अधिशायी अभियंता  
चम्बल मंडल, के.ज.आ., जयपुर

प्रतिलिपि सूचनार्थः

1. अधीक्षण अभियंता, ज.वि.प्रे.परि., के.ज.आ., वैशाली।
2. उप मंडलीय अभियंता, म.च. उ.मं., कोटा।
3. आशुलिपिक चम्बल मंडल, जयपुर।
4. सूचना पट्ट, चम्बल मंडल, जयपुर।
5. सीडबल्यूसी वेब पोर्टल।

## Schedule of Quantity

**Name of Work: Repairing of Office Building of Middle Chambal Sub Division, CWC, Kota**

S. No.	Description of items	Qty.	Unit	Rate (incl. GST)	Amount (incl. GST)
1	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and tacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	43.8	sqm		
2	Providing and fixing in wall lining medium density fibre board IS: 14587:1998 marked, Pre-laminated one side decorative lamination and other side balancing lamination, with necessary fixing arrangement and screws etc. complete. 12 mm thick.	34.631	sqm		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	0.18	cum		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	49.41	sqm		
5	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	50.36	sqm		
6	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	408.24	sqm		
7	Finishing walls with Acrylic Smooth exterior paint of required shade : Finishing walls with Acrylic Smooth exterior paint of required shade : 13.46.1 New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	457.65	sqm		



8	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	6.00	Each		
9	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete :9.46.2 20 mm dia	24.9	m		
10	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 40mm nominal dia pipe	10	m		
11	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 15mm nominal dia pipe	16	m		
12	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	6	points		
13	Supplying and fixing PVC batten/ angle holder	6	Each		

	including connections etc. as required.				
14	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required				
I	5/6 A switch	30	Each		
II	15/16 A switch	5	Each		
III	3 pin 5/6 A socket outlet	8	Each		
IV	6 pin 15/16 A socket outlet	5	Each		
V	Telephone socket outlet	1	Each		
15	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	3	Each		
16	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	100	meter		
	<b>Grand Total</b>				

\* Terms & conditions: - As per NIQ

Issuing Authority

Sd/-

Executive Engineer  
Chambal Division

Signature of Contractor

Seal  
Address