



भारत सरकार

Government of India

जल संसाधन, नदी विकास एवं गंगा संरक्षण मंत्रालय

Ministry of Water Resources, River Development & Ganga Rejuvenation

उपमंडलीय अभियन्ता का कार्यालय
साबरमती उप मंडल
केन्द्रीय जल आयोग
अहमदाबाद



Office of The Sub Divisional Engineer
Sabarmati Sub Division
Central Water Commission
Ahmedabad

NIQ NO.:SSD/ABAD/NIQ/09/16-17

दिनांक :

07 | 11 | 16

Notice Inviting Quotations

Sealed quotations are invited for the work of “Renovation of Transit Camp at SSD,Ahmedabad” on behalf of President of India by this office from the reputed firms / contractor as per the enclosed schedule of quantity (annexure-1) and terms & conditions given below:-

Terms & Conditions:

1. The sealed quotation should reach this office latest by **15.00 Hrs. on or before 19/11/2016** and the same will be opened on the same day at **15.30 Hrs.** in presence of the bidders or representative thereof, if any.
2. The sealed cover should be super scribed with words “Renovation of Transit Camp at SSD, Ahmedabad”.
3. Rates for each item shall be furnished in the format as given above in the schedule of quantity. Any correction, overwriting shall be countersigned.
4. The Rate shall be quoted in figure as well as in words.
5. The offer rate must remain **valid for a period of Sixty (60) days** from the date of opening of quotation.
6. Quotations erased and over written will be summarily rejected unless corrections are authenticated with bidder's signature.
7. Sales tax or any other tax on materials in respect of this contract shall be payable by the contractor and department shall not entertain any claim whatsoever in this respect.
8. Taxes as applicable will be deducted at the source from the bill at the time of payment.
9. **The whole work should be completed within 30 days from the date of issue of order.**
10. **Earnest Money Deposit (EMD) amounting to Rs. 1590/- (Rupees one thousand five hundred ninty) only should be deposited** along with the quotation in the form of Cash receipt (if deposited in cash) / DD of a scheduled bank in favour of the Executive Engineer, Mahi Division, CWC, Gandhinagar (Gujarat) payable at State Bank of India, Gandhinagar Branch, Gandhinagar. For unsuccessful quotationers EMD shall be refunded. EMD shall be forfeited, if any quotationer withdraws their offer before the expiry of the validity period or fails to furnish the performance guarantee / complete the work within the stipulated period from the date of order. **In case of non submission of EMD, the offer will be liable for rejection.**

P.T.O.

11. **Performance Guarantee will be submitted with in seven (7) days by successful quotationers for 5% value of the ordered price** claimed by the “Contractor” to cover the standards of performance. The performance guarantee for 5% value may be furnished in the form of A/c payee demand draft from of a scheduled bank in favour of the Executive Engineer, Mahi Division, CWC, Gandhinagar (Gujarat) payable at State Bank of India, Gandhinagar Branch, Gandhinagar. The Performance Guarantee shall be refunded to the contractor soon after completion of the work and recording of the completion certificate.
12. **Security deposit @ 5% of the gross amount of bill shall be deducted** from the final bill of the contractor. The above “Security deposit” shall be refunded after completion of all guarantee / warranty obligation.
13. **The whole work shall be guaranteed for a period of 6 (six) months from the date of actual completion as recorded.** The work should be completed satisfactorily and in all respects as directed by this office. In the event of any defect is found within the guaranteed period due to faulty design or bad workmanship, the whole work or a part thereof will be replaced by the “Contractor” at site free of cost within 10 days of intimation.
14. A copy of proof of registration / PAN no. may be submitted along with their offer.
15. The work site can be inspected by the contractor between 14.00 Hrs to 17.00 Hrs. on any working days except Saturday, Sunday & holidays at Sabarmati Sub Division, CWC, Ahmedabad (Gujarat)
16. The material used in the works should be of good quality and free from defect and if found not suitable the same should be replaced by the contractor at his own cost & risk.
17. The work should be carried out / completed as per the specification mentioned in the work order. If found not satisfactory according to the specification, the same should be dismantled immediately at the own cost & risk of the Contractor for which no claim will be entertained by this department.
18. The quantity will be decreased or increased at the time of work order for which the contractor should bind to execute the works.
19. This office reserves the right to reject any or all the quotations and to alter the quantity without assigning any reasons.
20. Intimation of unsuccessful quotation will not be given to concerned firms and the quotationers shall have no claim of any nature on this office.
21. Canvassing in any form whether directly or indirectly is strictly prohibited.
22. In case of any disputes arises, the decision of the undersigned will be final and binding on the Contractor.
23. The department will not be responsible for any injury sustained to the workers during the performance of their duties on the work and also any damage or compensation due to any disputes between the Contractor and the workers.
24. **No advance payment would be made under any circumstances.** However, after satisfactory completion of the work, on receipt of the bill in triplicate payment shall be made by A/c payee Cheque payable at SBI, Gandhinagar.
25. Any other rules & codes of CPWD and its amendment as applicable will be binding on the successful bidder for this deal.

Signature of the Contractor with seal

-----Sd-----
Sub Divisional Engineer

SCHEDULE OF QUANTITY**Annexure-1****Name of Work:-“Renovation of Transit Camp at SSD,Ahmedabad”.****NIQ NO.:-SSD/ABAD/NIQ/09/16-17 dated 07.11.16.**

Sl. No	Description of item	Unit	Qty	Rate (Rs Ps.)	Amount (Rs Ps.)
1	Dismantling of flushing cistern of all types (C.I/PVC/Vitrious China) including stacking of useful materials near the site and disposal of Unserviceable materials within 50 meters lead.	Each	2		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material with in 50 meters lead. For thickness of tiles 10 mm to 25 mm.	Sqm	17.92		
3	Providing and fixing chlorinated polyvinyl chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, I/C fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of engineer in charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal outer dia. Pipes.	meter	15		
4	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the ,manufacture),of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by engineer in charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	14.44		
5	Providing and laying ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of Ist quality conforming to IS 15622 of approved make in all colours such as White, Ivory, Grey, Fume Red brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse Sand) including pointing the joints with white cement and matching pigment etc. complete.	Sqm	3.48		
6	White vitreous china dual purpose closet (Anglo indian W.C) suitable for use as squatting pan or European type water closet as per manufacturer's specifications	Each	1		
7	Vitreous china surgeon type wash basin of size 660x460 mm	Each	1		
8	Providing and fixing C.P brass shower rose with 15 or 20 mm inlet. 150 mm diameter	Each	1		

9	Other Sanitary item & misc.	Job	1		
10	Supply & fitting of Aluminum Section Windows anodized with outer protection MS Jali	Sqm	4.5		
11	Vinyl flooring 1.5 mm thick with fixing	Sqm	30.67		
12	Finishing walls with textured exterior paint of required shade: New work (Two or more coats applied @3.28 lit/10 sqm) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm	Sqm	30.81		
13	Finishing with deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 Sqm over and including one coat of special primer applied @ 0.75 ltr/10 sqm.	Sqm	17.26		
14	Electrical fitting in Toilet	Job	1		
15	Exhaust fan with conceal wiring in bathroom with switch & alluminium lovers frame with exhaust fan fitting	Job	1		
	Grand Total				

(Rupees

We agree to execute the above works in accordance with the technical specifications and terms & conditions mentioned in NIQ NO.:SSD/ABAD/NIQ/09/16-17 dated 07.11.16 for a total contract price of Rs..... (Rupees.....) within the period specified in the NIQ.

Place:

Date:

Signature of Contractor
Address

