

भारत सरकार
केन्द्रीय जल आयोग
ऊपरी यमुना मंडल

कालिंदी भवन, बी-5, तारा क्रिसेंट रोड,
कुतुब संस्थानिक क्षेत्र, नई दिल्ली-110016

क्रमांक: 01/02/05/2022-23/UYD/ 4208-13

दिनांक: 23 SEP 2022

कोटेशन आमंत्रण सूचना
(NIQ No. 13./2022-23/UYD/Delhi)

भारत के राष्ट्रपति के ओर से अधोहस्ताक्षरी द्वारा संलग्न विवरण के “Providing Plinth Protection and Angled Louver Metal Slats at Delhi Railway Bridge Site under Upper Yamuna Division, New Delhi” में कार्य हेतु कोटेशन आमंत्रित किए जाते हैं। इच्छुक प्रतिष्ठित फर्म संलग्न निर्धारित प्रपत्र में अपनी कोटेशन बंद लिफाफे में दिनांक 03.10.2022 को अपराह्न 15:00 बजे तक जमा करा सकते हैं। कोटेशन उसी दिन अपराह्न 15:30 बजे इच्छुक कोटेशनदाताओं या उनके प्रतिनिधि की उपस्थिति में खोली जाएगी।


कार्य की सूची एवं विशिष्टियाँ (Specifications): संलग्न विवरण के अनुसार।

नियम एवं शर्तें:

1. उपरोक्त कार्य “Providing Plinth Protection and Angled Louver Metal Slats at Delhi Railway Bridge Site under Upper Yamuna Division, New Delhi” कार्य कराने के लिए है।
2. बयाना राशि (Earnest Money Deposit) रु. 6200.00 कोटेशन के साथ अधिशासी अभियंता, ऊपरी यमुना मंडल, केन्द्रीय जल आयोग, नई दिल्ली के पक्ष में डिमांड ड्राफ्ट के रूप में जमा करनी होगी।
3. कार्य विशिष्टियों (Specifications) के अनुसार कार्य आदेश जारी होने के 45 दिनों के अंदर पूरा करना अनिवार्य होगा।
4. मुहरबंद लिफाफे पर कार्य का नाम एवं कोटेशन संख्या आदि लिखा होना चाहिए।
5. कोटेशन संलग्न निर्धारित प्रपत्र में फर्म के लेटर पैड पर होनी चाहिए।
6. कोटेशन आमंत्रण सूचना नंबर एवं खोलने की तारीख लिफाफे के ऊपर लिखी होनी चाहिए।
7. दरों को शब्दों एवं संख्या दोनों में लिखा होना चाहिए।
8. दरें सभी कर तथा अन्य प्रभार आदि यदि कोई हो तो इसका विवरण अलग से दिया जाना चाहिए।
9. सभी कटिंग्स एवं ओवर राइटिंग्स प्रतिष्ठान के अधिकृत व्यक्ति द्वारा हस्ताक्षरित होने चाहिए।
10. कोटेशन में दर्शायी गयी दरें 90 दिन तक लागू होगी इस मुद्दे पर किसी कोटेशनदाता की चुप्पी उसकी सहमति मानी जाएगी।
11. कार्य आदेश जारी होने के बाद प्रभारी अभियंता के दिशा निर्देशों के साथ पूरा करना अनिवार्य होगा। कार्य को बीच में छोड़कर जाने की स्थिति में अथवा संतोषजनक न होने की स्थिति में अथवा किसी शर्त के ना पालन करने पर फर्म को विभाग में ब्लेकलिस्टेड/ बेन कर दिया जाएगा एवं ऐसी स्थिति में अधोहस्ताक्षरी द्वारा तय की गयी पेनल्टी फर्म को मान्य करनी होगी।
12. कार्य का भुगतान वास्तविक कार्य के आधार पर जाँच उपरांत किया जाएगा।
13. कार्य पूरा होने पर इस कार्यालय में पूर्व प्राप्ति बिल (प्री-रिसिटेड बिल) दो प्रतियों में भेजना होगा बिल में धनराशि अंको तथा शब्दों दोनों में लिखा होना चाहिए। तत्पश्चात भुगतान PFMS के माध्यम से किया जाएगा।
14. मात्रा की अनुसूची फॉर्म संख्या-2 में दिया गया है।
15. शर्तों के साथ भेजे गए कोटेशन स्वीकार नहीं किए जाएंगे।
16. कार्य आदेश की मात्रा घटाने या बढ़ाने का अधिकार अधोहस्ताक्षरी के पास सुरक्षित है। इस संबंध में अधोहस्ताक्षरी का निर्णय अंतिम एवं बाध्यकारी होगा।

17. अधोहस्ताक्षरी के पास बिना कोई कारण बताए किसी अथवा सभी कोटेशन को स्वीकृत/अस्वीकृत करने एवं सम्पूर्ण कोटेशन प्रक्रिया को निरस्त करने का अधिकार सुरक्षित है। इस संबंध में उनका निर्णय अंतिम एवं बाध्यकारी होगा।
18. निर्धारित तिथि एवं समय के उपरान्त प्राप्त होने वाला कोटेशन को स्वीकार नहीं किया जाएगा।
19. फ़र्म GST पंजीकृत होनी चाहिए एवं GST संख्या कोटेशन में दर्शायी होनी चाहिए।
20. कोटेशन फार्म-1 एवं 2 को पूर्णतया: भरकर ही जमा करना होगा, संशयात्मक स्थिति एवं अधूरी सूचना की स्थिति में कोटेशन को अस्वीकार कर दिया जाएगा।
विस्तृत जानकारी के लिए वेबसाइट <https://www.cwc.gov.in> देखें।

संलग्नक: उपरोक्तानुसार।


अधिशायसी अभियंता
ऊपरी यमुना मंडल

प्रतिलिपि:

1. अधीक्षण अभियंता (समन्वय), यमुना बेसिन संगठन, केन्द्रीय जल आयोग, नई दिल्ली।
2. अधीक्षण अभियंता, जल विज्ञानीय प्रेक्षण परिमंडल, केन्द्रीय जल आयोग, वैशाली।
3. वेतन एवं लेखाधिकारी, केन्द्रीय जल आयोग, सेवा भवन, नई दिल्ली।
4. उप-मंडलीय अभियंता (मु.), ऊपरी यमुना मंडल, केन्द्रीय जल आयोग, नई दिल्ली।
5. लेखानुभाग।
6. सूचना पट्ट।

कार्य का नाम: Providing Plinth Protection and Angled Louver Metal Slats at Delhi Railway Bridge Site under Upper Yamuna Division, New Delhi

1	Name of Company/ Firm / Agency (Attach certificate of registration):	
2	Name of proprietor / Director of Company / Firm / agency:	
3	Full Address of Reg. Office :	
4	Telephone No.	
5	FAX No.	
6	E-Mail Address :	
7	Full address of Operating / Branch Office :	
	Telephone No.	
	FAX No.	
	E-Mail Address :	
8	PAN No. (Attach attested copy)	
9	GST Registration No. (Attach attested copy)	
10	Give details of the major similar contracts handled by the tendering Company/Firm/Agency during the last five years (attach copy)	
11	Additional information, if any (Attach separate sheet, if required)	

स्थान:

अधिकृत व्यक्ति के हस्ताक्षर:

दिनांक:

अधिकृत व्यक्ति का नाम:

एजेंसी/ फर्म की सील:

मात्रा की अनुसूची

कार्य का नाम: Providing Plinth Protection and Angled Louver Metal Slats at Delhi Railway Bridge Site under Upper Yamuna Division, New Delhi

S. No.	Description of Items	Quantity	Unit	Rate (in Rs.)		Amount (in Rs.)
				Figures	Words	
Electric Meter Cover						
1	Providing and fixing Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately). 18 mm thick	0.945	sqm			
2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 25 mm thick (for cupboard) including ISI marked nickel plated bright finished M.S. Piano hinges IS: 3818 marked with necessary screws	0.675	sqm			
Water Motor Cover						
3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement : 4 coarse sand)	0.70	sqm			
4	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	1.05	sqm			
5	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	1.05	sqm			
6	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick ase cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to	0.50	sqm			

	edges to give high gloss finish etc. complete at all levels.					
	Granite stone slab colour black, Cherry/Ruby red					
	Area of slab over 0.50 sqm					
7	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters.	0.70	sqm			
	25 mm thick (for cupboard) including ISI marked nickel plated bright finished M.S. Piano hinges IS : 3818 marked with necessary screws					
Telemetry Tower Painting						
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :	325.00	sqm			
	Two or more coats on new work					
Telemetry Room Chajja						
9	Fiber glass reinforced plastic chajja	6.12	sqm			
Plantation against external outer wall						
10	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.	12.365	sqm			
	Cement mortar 1:4 (1 cement :4 coarse sand)					
11	12 mm cement plaster of mix :	24.730	sqm			
	1:4 (1 cement: 4 fine sand)					
12	Finishing walls with Acrylic Smooth exterior paint of required shade :	12.365	sqm			
	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)					
13	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	4.289	cum			
Plinth Protection						
14	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.	7.358	cum			
	All kinds of soil.					
15	Centering and shuttering including strutting, propping etc. and removal of form work for :	17.430	sqm			
	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.					

16	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level	3.679	cum			
	1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size derived from natural sources)					
17	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	3.679	cum			
Angled Louver Metal Slats						
18	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7D, F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design, (sectional weight of only steel members shall be measured for payment).	659.023	kg			
	Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)					
19	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture	52.800	sqm			
Words CWC with Logo on Roof Wall Projection						
20	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	7.15	sqm			
21	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	7.15	sqm			
22	Cleaning, painting and writing including logo with retro-reflective paint and finishing complete as per direction of Engineer-in-Charge	4.00	No.			
राशि (रुपये में)						
जी.एस.टी. @..... %						
सकल योग (रुपये में)						
कुल राशि (रुपये में)						

अधिशाली अभियंता
रूपरी यमुना मंडल