



पत्र सं. ऊवैउम/नाग /कोटेशन-02 /2019/ 334-38

दिनांक :- 03 / 06 / 2019

NOTICE INVITING QUOTATION


Sealed quotations are hereby invited from registered firms / parties of repute to civil work "Installation of gauge posts(S/Gline,U/Sline,D/Sline)at new site: Maggardarra, Bakhari, Nainpur, Sarekha, Mungapar, Zilmilli,Sigodi,Sarrah, Waraseoni under UWSD,CWC,Nagpur" as per details given in Annexure - I ,Annexure-II,Annexure-III as per terms and conditions described below:-

Terms and conditions:

1. दरों को एफ.ओ.आर. गंतव्य पैकिंग, अग्रेषण, माल, बीमा, यदि कोई हो, के समावेशी उपमंडलीय अभियंता,ऊपरी वैनगंगा उपमंडल, सीडब्ल्यूसी, तृतीय तल, ब्लॉक 'सी', सीजीओ कॉम्प्लेक्स, सेमिनरी हिल्स, नागपुर (महाराष्ट्र) 440006 के अन्तर्गत साईट कार्य स्थल तक होना चाहिये जो कि Annexure - I ,Annexure-II, Annexure-III में दिया गया है।
2. कोटेशन के खुलने की तारीख से न्यूनतम 30 दिनों के लिए दरें मान्य होंगी।
3. गेज पोस्टों की स्थापना कार्य आदेश से 30 दिनों के भीतर की जानी चाहिए।
4. दरों में सभी करों और लेवी को शामिल किया जाना चाहिए। किसी भी खाते पर कोई अतिरिक्त भुगतान नहीं किया जायेगा।
5. कोटेशन राशि का 5% बिल से रखा जाएगा क्योंकि छह महीने की वारंटी अवधि तक प्रदर्शन की गारंटी होगी जो कि फ़ाइनल बिल से काटा जायेगा।
6. गेज पोस्टों की स्थापना को विनिर्देशों के अनुसार कड़ाई से होना चाहिए, अन्यथा अस्वीकृति के लिए उत्तरदायी होगा।
7. तीन प्रतियों में पूर्व-प्राप्त बिल को सामग्री के संतोषजनक वितरण के बाद भुगतान करने के लिए प्रस्तुत करना होगा पूरे में पीएफएमएस ऑनलाइन पोर्टल द्वारा भुगतान किया जाएगा, इसके लिए बिल की रसीद पूरी तरह से जमा करनी होगी।
8. बिडर को पी.डब्ल्यू.डी. या सी.पी. डब्ल्यू.डी से प्राप्त राजिस्ट्रेशन प्रमाण पत्र प्रस्तुत करना होगा।
9. बोलीदाताओं को इस दस्तावेज़ में उल्लिखित सभी नियमों और शर्तों को ध्यान में रखते हुए दरों का उद्धरण करना चाहिए।
10. NIQ को एक मोहरबंद बड़े लिफाफे में जमा किया जाना चाहिए।
11. बिडर को जीएसटी पंजीकरण प्रमाणपत्र प्रस्तुत करना चाहिए।


Sealed quotation duly superscribed "Quotation for Installation of gauge posts (S/G line,U/S line,D/S line) at new sites : : Maggardarra, Bakhari, Nainpur, Sarekha, Mungapar, Zilmilli,Sigodi,Sarrah, Waraseoni under UWSD,CWC,Nagpur, " will be received by the undersigned till **11.30Hrs on 10/06/2019** and will be opened on **10/06/2019** at **12.30 Hrs** in the presence of interested parties. Quotations received after scheduled time will not be considered.

Undersigned reserves the right to reject any or all the quotations without assigning any reasons therefor.


(जे.के. चन्द्रवन्शी)
उपमंडलीय अभियंता
Sub Divisional Engineers
ऊपरी वैनगंगा उपमंडल
Upper Wainganga Sub Division
के.ज.आ. नागपुर
C.W.C., Nagpur

जानकारी और प्रचार के लिए कॉपी :

1. अधीक्षण अभियंता (C), एम.सी.ओ. C.W.C. नागपुर।
2. कार्यकारी अभियंता, वैनगंगा डिवीजन, सीडब्ल्यूसी, द्वितीय तल, ब्लॉक 'सी', नागपुर।
3. लेखा शाखा, डब्ल्यू.डी.सी.डब्ल्यू.सी नागपुर।
4. कानिष्ट अभियंता, वैनगंगा मंडल, सीडब्ल्यूसी, नागपुर। सीडब्ल्यूसी निविदा पोर्टल पर अपलोड करने हेतु।
5. ऑफिस नोटिस बोर्ड.


(जे.के. चन्द्रवन्शी)
उपमंडलीय अभियंता, 3/6/19
ऊपरी वैनगंगा उपमंडल
केंद्रीय जल आयोग
नागपुर।

BILL OF QUANTITY

Installation of gauge posts (S/G line,U/S line,D/S line) at new sites :Maggardarra (18 gauge posts) under
Division : Wainganga Division , C.W.C.,Nagpur.

Sl. No.	Description of Work	Qty.	Unit	Rate In Rupees		Amount
				In Fig.	In Words	
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge:All kinds of soil.	0.216	CUM			
2	Providing and laying in position cement concrete of specified gradeexcluding the cost of centering and shuttering - All work up to plinthlevel1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size).	0.216	CUM			
3	Centering and shuttering including strutting, propping etc. and removal of form work for :4.3.1 Foundations, footings, bases for columns.	0.16	Sqm			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size).	0.016	Cum			
6	Painting and marking on Gauge post Painting of gauge post 1.8 m long with synthetic enamel of approved brand & manufacture to give an even shade by two or more coats and making the gauge with japan paint red,black and white with stranded metric gradation making of 5mm thickness in black & white alternately & red synthetic enamel of width 5mm at every 50 mm	1 No	Per day			
Total cost for installation of one gauge post						
For 18 nos. gauge post						
7	Transportation of RCC gauge posts from Rajegaon to Keolari via Magardarra , Waraseoni,Sarekha	220	Km			

TOTAL Rs.

(Rupees -----) Only.

Signature :
Name :
Address :

BILL OF QUANTITY

Installation of gauge posts (S/G line,U/S line,D/S line) at new sites :Bakhari (18 gauge posts) under
Division : Wainganga Division , C.W.C.,Nagpur.

Sl. No.	Description of Work	Qty.	Unit	Rate In Rupees		Amount
				In Fig.	In Words	
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge:All kinds of soil.	0.216	CUM			
2	Providing and laying in position cement concrete of specified gradeexcluding the cost of centering and shuttering - All work up to plinthlevel1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size).	0.216	CUM			
3	Centering and shuttering including strutting, propping etc. and removal of form work for :4.3.1 Foundations, footings, bases for columns.	0.16	Sqm			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size).	0.016	Cum			
6	Painting and marking on Gauge post Painting of gauge post 1.8 m long with synthetic enamel of approved brand & manufacture to give an even shade by two or more coats and making the gauge with japan paint red,black and white with stranded metric gradation making of 5mm thickness in black & white alternately & red synthetic enamel of width 5mm at every 50 mm	1 No	Per day			
Total cost for installation of one gauge post						
For 18 nos. gauge post						
7	Transportation of RCC gauge posts from Keolari to Bakhari via Ganeshganj	200	Km			

TOTAL Rs.

(Rupees -----) Only.

Signature :

Name :

Address :

BILL OF QUANTITY

Installation of gauge posts (S/G line, U/S line, D/S line) at new sites :

Nainpur, Sarekha, Mungapar, Zillimilli, Singodi, Sarrah, Wareseoni (18 gauge posts) under UWSD, CWC, Nagpur
Division : Wainganga Division, C.W.C., Nagpur.

Sl. No.	Description of Work	Qty.	Unit	Rate In Rupees		Amount
				In Fig.	In Words	
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge: All kinds of soil.	0.216	CUM			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size).	0.216	CUM			
3	Centering and shuttering including strutting, propping etc. and removal of form work for : 4.3.1 Foundations, footings, bases for columns.	0.16	Sqm			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size).	0.016	Cum			
6	Painting and marking on Gauge post Painting of gauge post 1.8 m long with synthetic enamel of approved brand & manufacture to give an even shade by two or more coats and making the gauge with japan paint red, black and white with stranded metric gradation making of 5mm thickness in black & white alternately & red synthetic enamel of width 5mm at every 50 mm	1 No	Per day			
	Total cost for installation of one gauge post					
	For 18 nos. gauge post					
7	Transportation of RCC gauge posts from Sarrah to singodi	50	Km			

TOTAL Rs.

(Rupees -----) Only.

Signature :

Name :

Address :