

**GOVERNMENT OF INDIA  
CENTRAL WATER COMMISSION  
WARDHA SUB-DIVISION**

PH/FAX : 07172-250845  
E.Mail: sdecwc123 @ gmail.com

Near Dist. Stadium,  
Civil Line, Chandrapur-442401.

NO. WSD/CWC/ A-9/ 2019/ 367 - 73

DATE : 22 / 7 / 2019

**NOTICE INVITING QUOTATION**


Sealed quotations are hereby invited from registered firms/ reputed parties to carry out the civil work for construction of MTBM "at new sites: Purad, Mungoli Township, Nagri and Patansaongi under WSD, CWC, Chandrapur", as per details given in Annexure -I

**Terms and conditions:-**

1. दलों को एफ.ओ.आर. गंतव्य पैकिंग, अग्रेषण, माल, बीमा, यदि कोई हो, के समावेशी उपमंडलीय अभियंता, वर्धा उपमंडल के.ज. आ., चंद्रपुर के अन्तर्गत साईट कार्य स्थल तक होना चाहिए जो कि Annexure -I. में दिया गया है।
2. कोटेशन के खुलने की तारीख से न्यूनतम 30 दिनों के लिए दरें मान्य होंगी।
3. MTBM construction का कार्य आदेश से 25 दिनों के भीतर किया जाना चाहिए।
4. दलों में सभी करों और लेवी को शामिल किया जाना चाहिए किसी भी खाते पर कोई अतिरिक्त भुगतान नहीं किया जायेगा।
5. कोटेशन राशि का 5% बिल से रखा जायेगा क्योंकि छः महीने कि वारंटी अवधि तक प्रदर्शन कि गारंटी होंगी जो कि फाइनल बिल से काटा जायेगा।
6. MTBM construction का कार्य विनिर्देशों के अनुसार कड़ाई से होना चाहिए, अन्यथा अस्वीकृति के लिए उत्तरदायी होगा।
7. तीन प्रतियों में पूर्व-प्राप्त बिल को सामग्री के संतोषजनक वितरण के बाद भुगतान करने के लिए प्रस्तुत करना होगा तथा पुरे में पिएफएमएस ऑनलाइन पोर्टल द्वारा भुगतान किया जायेगा, इसके लिए बिल कि रसीद पूरी तरह से जमा करनी होंगी।
8. बोलीदाताओं को इस दस्तावेज में उल्लेखित सभी नियम और शर्तों को ध्यान में रखते हुए दलों को उद्धरण करना चाहिए।
9. NIQ को एक मोहरबंद बड़े लिफाफे में जमा किया जाना चाहिए।
10. बिडर को जीमटी पंजीकरण प्रमाणपत्र प्रस्तुत करना चाहिए।


Sealed quotation duly superscribed "Quotation for construction of MTBM at new sites: Purad, Mungoli Township, Nagri and Patansaongi under WSD, CWC, Chandrapur will be received by the undersigned till **11.00 Hrs** on **30.07.19** and will be opened on **30.7.19** at **12.30 hrs** in the presence of interested parties. Quotation received after schedule time will not be considered.

Undersigned reserves the right to reject any or all the quotation without assigning any reason therefore.

  
(B.M.BORKAR)  
AEE, WSD, Chandrapur

Copy for information and publicity to:-

1. The Superintending Engineer(C), M.C.O. CWC Nagpur.
2. The Executive Engineer, Wainganga Division, CWC, Nagpur.
3. Account branch, WD, CWC, Nagpur.
4. Junior Engineer, WD, CWC, Nagpur, to upload on CWC Tender portal.
5. The SDEs UWSD Nagpur/LWSD Chandrapur/ PGSD Yavatmal
6. Office Notice Board.

  
(B.M.BORKAR)  
AEE, WSD, Chandrapur

**BILL OF QUANTITY**

**Construction of MTBM for 4 sites ( Purad,Mungoli township,Nagri and Patansaongi)under WSD, CWC, Chandrapur.**

**Division: Wainganga Division, CWC, Nagpur.**

| SN  | Sub head and items of work   | Qty           | Rate<br>Rs | Amount<br>Rs | Total<br>Rs |
|---|--|---------------|------------|--------------|-------------|
| 1   | Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge:All kinds of soil                                  | 3.688<br>cum  |            |              |             |
| 2   | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :<br>1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)  | 0.256<br>sqm  |            |              |             |
| 3   | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :<br>1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)       | 2.3005<br>cum |            |              |             |
| 4   | Brick work with common burnt clay selected F.P.S. (non modular) bricks of class designation 7.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand)<br>Above plinth level upto floor V level | 1.080<br>cum  |            |              |             |
| 5   | 18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand)   | 8.64<br>sqm   |            |              |             |
| 6   | Supply of good quality red sand stone (0.3x0.3x1 m) fixing as per instruction of site in charge  | 0.09<br>cum   |            |              |             |
| 7   | Finishing wall with water proffing cement paint of required shade: New work ( two or more coats applied @3.84 Kg/10 sqm)   | 8.94<br>sqm   |            |              |             |
| 8   | Coarse sand zone III<br>sand filling inside of MTBM  | 0.3825<br>sqm |            |              |             |
| Total amount for one MTBM   |  |               |            |              |             |
| Total amount for four MTBMs at sites Purad,Mungoli township,Nagri and Patansaongi |  |               |            |              |             |

(Rupees -----only)

**Signature:-**

**Name:-**

**Address:-**