



भारत सरकार
केन्द्रीय जल आयोग
मध्य चंबल उप मण्डल

कोय बेराज के पास, सकतपुरा
डाकघर. कुन्हाडी, कोय(राज0)324008
दूरभाष:0744-2371877

No.: MCSD/Kota/NIQ/2019/ 393-97

Dated: 14-06-2019

NOTICE INVITING QUOTATION


Sealed/closed quotations are hereby invited by the undersigned on behalf of President of India from the contractors for the following work - **Fabrication and installation of RCC gauge posts at Permanent centre line, 150 Meters upstream and 150 meters downstream from Permanent centre line of river Kalisind at Jhalawar site, District Jhalawar (Raj.).** as per bill of quantity enclosed.

The quotation should reach in the office of the undersigned on or before 01.07.2019 up to 15:00 hrs and will be opened on the same day at 15:30 hrs in the presence of Concern Junior Engineer, intending quotationers, if any. If quotations could not be opened on aforesaid date due to unavoidable circumstances, then same will be opened on next working day without any further notice.

Terms & Conditions

1. The work should be done as per CPWD specification & direction of Engineer in-charge.
2. Rates should be quoted both in figure and words.
3. Income tax & other tax etc. shall be deducted from the bill as per rule and relevant documents and experience certificate of civil work/installation and fabrication of R.C.C and cement concrete gauge Post should be attached.
4. The work should be completed within Thirty days from the date of issue of work order.
5. The payment will be made by through RTG/NEFT to A/C of firm after satisfactory completion of work.
6. No advance payment shall be made.
7. GST will be paid as per actual.

Encls: Bill of Quantity


Assistant Executive Engineer
o/c (MCSD Kota)

Copy to:-

1. The Executive Engineer, CD, CWC, Jaipur
2. Account Branch, CD, CWC, Jaipur.
3. Notice Board, MCSD Kota, CWC, Kota.
4. Junior Engineer, Jhalawar site (Raj) for publicity.
5. M/S

with the request that please Display on C.W.C.Gh.

SCHEDULE OF QUANTITY

Name of work: - Fabrication and installation of RCC gauge posts at Permanent centre line of river Kalisind at Jhalawar site, District Jhalawar (Raj.)

S. no.	Description of items	Quantity	Unit	Rates in rupees		Amount in Rupees
				In figures	In words	
1	<p>Fabrication and installation of gauge posts at river banks including cost of civil works in foundation embedded in 1 : 2 : 4 reinforced cement concrete pedestal block of size 60 cm x 60 cm x 60 cm including the cost of steel reinforcement, centering, shuttering, finishing, reinforcement over the 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) cement concrete base of size 80 cm x 80 cm x 15 cm with 12 mm thick plastering complete and marking the gauge post with synthetic enamel with standard metric gradation of 5 mm thickness in black and white alternately & red synthetic enamel of 5 mm width at every 100 mm etc. complete.</p> <p>Reinforced cement concrete gauge post of size 15 cm x 10 cm (one side tapered in 5 cm length) made with 1:2:4 concrete mix (1 cement : 2 coarse sand : 4 grade stone aggregate 20 mm nominal size)- 1.80 m long. (12 x 1 = 12).</p>	12	Nos.			
Total						
Amount (A)						
Contractor Profit						
@.....(B)						
Add						
GST@.....						
Grand Total						
GST as applicable shall be quoted						

Issuing authority

Assistant Executive Engineer
Middle Chambal Sub Division, Kota

Signature of Contractor
Seal
Address