



84/93-96, प्रताप नगर, सांगानेर, जयपुर -302033
फोन: 0141-2790065, ई-मेल: chambalcwc@yahoo.co.in

पत्र क्रमांक: चमज/ के.ज.आ./मु.-1/2023/4586-89

दिनांक: 02/12/2023

कोटेशन आमंत्रण सूचना (NOTICE INVITING QUOTATION)

भारत के राष्ट्रपति की ओर से अधिशाषी अभियंता, चम्बल मंडल, जयपुर द्वारा अधिकृत तथा योग्य बोली लगाने वालों से "निचली चम्बल उपमंडल जयपुर के अधीन पाली स्थल पर कार्यालय भवन की मरम्मत तथा नवीनीकरण कार्य हेतु कोटेशन" लिखा हुआ मुहरबंद कोटेशन आमंत्रित किये जाते हैं।

Sealed quotation super scribed as "Quotation For "Repair & Renovation of Pali office under Lower Chambal Sub-division, CWC, Jaipur" are invited for and on behalf of the President of India by the Executive Engineer, Chambal Division, CWC, Jaipur from the authorized and eligible bidders.

नियम एवं शर्तें (Terms & Conditions)

- मुहरबंद कोटेशन अधिशाषी अभियंता, चम्बल मंडल, केन्द्रीय जल आयोग, जयपुर के कार्यालय में दिनांक 13.12.2023 पूर्वान्ह 11:00 बजे तक या उससे पूर्व प्राप्त हो जानी चाहिए, जो उसी दिन अर्थात् 13.12.2023 दोपहर 12:00 बजे अधोहस्ताक्षरी तथा बोली लगाने वाले या उसके प्रतिनिधि जो उपस्थित रहना चाहे की उपस्थिति में खोली जाएगी।
The sealed quotation shall reach to the office of Executive Engineer, Chambal Division, CWC, Jaipur on or before 13.12.2023 upto 11:00 A.M. and will be opened on the same day i.e. 13.12.2023 at 12:00 P.M. in the presence of undersign and bidders or their representative who may likely to be present at the time of opening of quotations.
- मुहरबंद कोटेशन के साथ रुपये 7952/- की ईएमडी डिमांड ड्राफ्ट/बैंकर्स चेक/एफडीआर के रूप में अधिशाषी अभियंता, चम्बल मंडल, के.ज.आ. जयपुर के पक्ष में संलग्न करना अनिवार्य है। बिना ईएमडी के प्राप्त कोटेशन को खारिज कर दिया जाएगा।
The EMD of Rs. 7952/- in the form of Demand Draft/Bankers Cheque/FDR in favor of **Executive Engineer, Chambal Division, CWC, Jaipur** should be enclosed with sealed quotation. Quotations received without EMD will be summarily rejected.
- कार्य करने की अवधि कायदेशि जारी होने के बाद से 30 दिन की रहेगी।
Work shall be carried within 30 days after issue of work order.
- कोटेशन में दर्शायी गयी राशि सभी प्रकार के टैक्स (GST etc.) के साथ होनी चाहिए तथा Annexure-1 में निर्धारित जगह पर ही राशि को दर्शाये।
Rates shall be quoted including of all Taxes (GST etc.) and rates should be mentioned in Annexure-1 at their shown place only.
- इस कार्य हेतु इस्तेमाल में लिया गया सामान अच्छी गुणवत्ता का एवं दिए गये विशेष विवरण के अनुसार तथा त्रुटी रहित होना चाहिए।
The material used for this work must be of standard quality and as per specifications and free from all the defects.

6. कोटेशन में दर्शायी दरे के कोटेशन खुलने के दिन से कम से कम 60 दिन तक वैध होनी चाहिए ।
Rates quoted should be valid at least for 60 days from date of opening.
7. उक्त कार्य पाली स्थल (जिला-सवाई माधोपुर, राजस्थान) पर होना हैं, जिनका दरें डालने से पूर्व निरीक्षण किया जा सकता हैं ।
The above work is to be done at Pali site (Dist.- Sawai Madhopur, Rajasthan), which Place can be inspected before quoting the rates.
8. कोटेशनर के पास Firm Registration certificate/PAN/TIN/GST No. (जो लागु हो) होना चाहिए ।
Quotationer must have Firm Registration certificate/PAN/TIN/GST No. (whichever is applicable)
9. अधोहस्ताक्षरी किसी एक या सभी कोटेशन को बिना कारण बताये स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता हैं।
Undersigned reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
10. कार्य की मात्रा कार्यदिश के समय या कार्य करने के दौरान बढ़ाई या कम की जा सकती हैं ।
The quantity of work may be increased or decreased at the time of work order or during the time of execution.
11. कोटेशन स्वीकृत होने पर, फर्म/एजेंसी को किसी भी वाणिज्यिक बैंक से Account Payee D.D/ Fixed Deposit Receipt/ Banker's cheque or Bank Guaranty के रूप में निविदा राशि के 3% की दर से परफॉरमेंस गारंटी जमा करनी होगी जो की अधिशाषी अभियंता, चंबल मण्डल, के.ज.आ., जयपुर को देय होगी। परफॉरमेंस गारंटी कार्य समाप्त होने के 60 दिन बाद तक वैध होनी चाहिए।
On acceptance of the quotation, the Firm/Agency shall have to submit performance Guarantee @ 3% of the tendered amount in the form of an Account Payee D.D/ Fixed Deposit Receipt/ Banker's cheque or Bank Guaranty from any of the commercial bank in favour of Executive Engineer, Chambal Division, CWC, Jaipur payable at Jaipur. This should remain valid for a period of sixty days beyond the date of completion of work.
12. कार्य के संतोषजनक पूर्ण होने के बाद सम्पूर्ण भुगतान में से आवश्यक कटौती (2.5 % Security Deposit, 2 % GST, 2% TDS, 1% Labour Cess) पश्चात भुगतान को ECS/RTGS के द्वारा किया जायेगा । अमानत राशी (Security Deposit) का भुगतान कार्य समाप्त होने के 06 माह के पश्चात किया जायेगा ।
Payment will be made through ECS/RTGS, only after satisfactory completion of work and deduction of necessary Deductions (2.5% Security Deposit, 2% GST, 2% TDS, 1% Labour Cess). Security Deposit amount will be given after 06 months of completion of work.

Hminku
02.12.23

अधिशाषी अभियंता
चम्बल मंडल, के.ज.आ., जयपुर

प्रतिलिपि सूचनार्थ:

1. सहायक लेखाधिकारी, लेखा शाखा, चम्बल मंडल, जयपुर।
2. उप मंडलीय अभियंता, नि.च.उ.मं., जयपुर।
3. सहायक, पत्राचार शाखा, चम्बल मंडल, जयपुर।
4. सूचना पट्ट, चम्बल मंडल, जयपुर AND CWC Web Portal.

Schedule of Quantity

Name of work: Repair & Renovation of Pali office under Lower Chambal Sub-division, CWC, Jaipur

Item No.	Sub-head and items of work	Qty or No.	Unit	Rate in Rs. (Including GST)	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	956.37	Sqm		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm (JE Room)	13.46	sqm.		
3	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	143.45	sqm.		
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	149.35	sqm.		
5	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	956.37	sqm.		
6	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and confirming to IS:15622, of approved make, in all colors and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc complete Size of tile 600*600 mm	13.46	sqm.		
7	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	1.03	Sqm		

8	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	44.28	sqm.		
9	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufactured of density at 25°C, 0.87 - 0.89 kg/litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto - 2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorized applicator of the manufacturer of membrane: 3 mm thick	68.53	sqm.		
10	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	64.17	sqm.		
11	Supplying and fixing PVC batten/ angle holder including connections etc. as required.	16.00	Each		
12	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connection but excluding modular plate etc. as required.				
	5/6 A switch	9.00	Each		
	15/16 A switch	7.00	Each		
	3 pin 5/6 A socket outlet	9.00	Each		
	6 pin 15/16 A socket outlet	7.00	Each		
13	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	4.00	Each		
14	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit along with 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	20.00	Meter		

15	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.				
	1 or 2 Module (75mmX75mm)	6.00	Each		
	4 Module (125mmX75mm)	2.00	Each		
	6 Module (200mmX75mm)	2.00	Each		
16	Supplying and fixing of 25 mm of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.	60.00	Meter		
17	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/ Isolator): 12 way , Double door	1.00	Each		
18	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of Single pole in the existing MCB DB complete with connections, testing and commissioning etc. as required.	6.00	Each		
Total Amount Rs.					
(In Word) Rs.					

Terms & conditions: - As per NIQ
Issuing Authority

Sd/-

Executive Engineer
Chambal Division

Signature of Contractor

Seal
Address