



NEID-II/JE(HQ)/NIQ/2021-22/477-79

Date: 21.07.2022

**NOTICE INVITING QUOTATION**

For and on behalf of the President of India, sealed quotations are invited by the undersigned from the authorized / reputed contractor/firms for the work of **"Repair and Maintenance of Retaining wall under NEID-II, CWC, Aizawl for the financial year 2022-23."** The Sealed Quotation will be received in the office of undersigned i.e. O/o Executive Engineer, NEID-II, CWC, Aizawl during working hours up to 15:30 hrs. on or before 03/08/2022 & shall be opened on same day by 16:30 hrs. by the undersigned/authorized official in presence of interested quotations or their authorized representatives who desired to remain present at the time of opening of quotations.

Description of the work.	Estimate cost	Last date & time for receiving quotation.	Date & time for opening quotation	Location
Repair and Maintenance of Retaining wall under NEID-II, CWC, Aizawl.	1,29,048/-	03/08/2022 15:30	03/08/2022 16:30	NEID-II, CWC, Aizawl

**Terms and Conditions :-**

1. The work should be done as per the schedule of quantity within 15 days from the date of issue of work order.
2. The material using for the work should be of standard quality and free from all defects and if found not suitable the same shall be asked for replacement at his own cost.
3. The rates shall be kept valid for minimum period of 60 days from the date of opening of quotation.
4. The rates should be inclusive of all local taxes such as Service Tax/GST etc.





5. Rates of Service tax/GST should be mentioned as applicable.
6. The rate of works should be quoted both in figures as well as in words.
7. The quotation number with date of its opening has to be clearly mentioned on the top of the quotation and sealed cover.
8. The quantities mentioned are likely to increase or decrease at the time of placing of work order.
9. Any correction in the quotation should be clearly attested.
10. Request for any advance payment will not be entertained.
11. The work carried out by the firm shall be guaranteed. The undersigned reserves the right to cancel/reject in part or full or any/all the quotation without assigning any reason thereof and without any financial involvement from either side.
12. Payment will generally be made via online mode through PFMS directly on the bank account of the bidder on production of bills.
13. Only those firms having PAN/GST etc. can be eligible to submit their quotation.
14. In case of any dispute, the decision of The Executive Engineer, NEID-II, CWC, Aizawl shall be final and binding on all concerned.

(Awdhesh Kumar)

Executive Engineer  
NEID-II, CWC, Aizawl

Copy along with copies of quotation for information and wide circulation to:

1. The SDE(HQ), NEID-II, CWC, Aizawl.
2. The Accounts Branch, NEID-II, CWC, Aizawl.
3. Notice Board.





### Schedule of Quantities

**Name of work:-** Repair and Maintenance of Retaining wall under NEID-II, CWC, Aizawl.

Items of work	Unit	Qty.	Rate	Amount
<b><u>Earthwork in excavation</u></b> --Earthwork in excavation trenches or drain etc.(Not exceeding 1.5m width or 10sqm on plan)including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out excavated soil and disposal of surplus excavated soil as directed within a lead of 50m. Ordinary soil.	Cum	3.360		
<b><u>Bed concrete</u></b> --Providing and laying imposition cement concrete of specified grade excluding cost of centring and shuttering -All work upto plinth level (a)1:5:10(1cement:5fine sand:10 coarse aggregate 40mm nominal size)	Cum	0.560		
<b><u>Random Rubble</u></b> -- masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:5:10 (20mm nominal size) upto plinth level with: (b) in cement mortar 1:3 (1cement :3 course sand) Width of the retaining wall are taken average of the top and bottom width same as in the height of the retaining wall.	Cum	2.80		
<b><u>Coursed rubble</u></b> -- coursed rubble masonry (first sort) with hard stone in superstructure above the plinth level and up to floor V level (a) cement mortar 1:3(1cement:3coarse sand)	Cum	7.350		





<b>Weep Hole--</b> Providing weep hole in stone masonry with 100mm dia AC Pipe extending through the full width of the structure with sloop 1(V):20(H) towards drawing face complete as per drawing and specifications.	Rm	4.550		
Providing 13 nos. Weep Hole in full width of the retaining wall				
<b>Pointing--</b> pointing on stone work with cement mortar 1:3(1cement:3fine sand) (B) Raised and cut pointing.	Sqm	21.00		

Rupees.....  
.....)only

(Signature of contractor with seal)

