

भारत सरकार

Government of India

केन्द्रीय जल आयोग

Central Water Commission

उप मंडलीय अभियंता का कार्यालय

Office of the Sub-Divisional Engineer

निचली गंगा उप मंडल

Lower Ganga Sub-Division



सत्यमेव जयते



कार्यालय भवन संख्या-3

फरक्का बांध परियोजना

फरक्का, मुर्शिदाबाद

पश्चिम बंगाल- 742212

दूरभाष/फैक्स: 03485253551

ई-मेल: lgfarakka@gmail.com

No. LGSF/Quot./2017/ **437-42**

Dated: 20/11/2017

NOTICE INVITING QUOTATION

Sealed quotations are invited by the undersigned for and on behalf of the President of India from reputed agencies for the work: 'Construction of Pedestal at Feeder Canal site at right bank, CWC, Farakka' under L.G. Sub-Division, CWC, Farakka as per the terms and conditions given below. The quotations should reach this office on or before 1500 hrs. of **29.11.2017**. The quotations will be opened on the same day at 1600 hrs. in the presence of quotationers or their representatives. The envelope containing quotation should be superscribed with "Construction of Pedestal at Feeder Canal site at right bank, CWC, Farakka" with NIQ No. and date.

Sl. No.	Particulars	Quantity	Unit	Rate (Rs.)
1.	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains not exceeding 1.5m in width or 10 sqm in plan including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and dispose of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	1.273	Cum.	
2.	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work upto plinth level 1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate)	1.273	Cum.	
3.	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete: Thermo-Mechanically Treated (TMT) Bars.	34.976	Kg.	
4.	Centering and shuttering including strutting, propping etc. and removal of form for: Foundation, footing, base of column etc for mass concrete.	5.572	Sqm.	
5.	At Left Bank Providing and laying in position specified grade of cement concrete, excluding the cost of centering, shuttering - All work upto plinth level 1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate) behind the existing pedestal at left bank	0.425	Cum.	
6.	Centering and shuttering including strutting, propping etc. and removal of form for: Foundation, footing, base of column etc for mass concrete	2.322	Sqm.	

Terms & conditions:-

1. The rate should be quoted in figures as well as in words. Any overwriting/erasing should be attested.
2. The rate quoted by the agency shall be inclusive of all. No extra charges viz. Carriage of materials, Service tax etc. will be entertained.
3. The right to accept/reject of all the quotations in whole/part without assigning any reason thereof is reserved by the undersigned and also not to bind accept the lowest quotation.
4. The Engineer-in-Charge of the work reserves the right to accept/reject the executed work according to his/her judgment.
5. No claims will be entertained for additional/extra work.
6. The payment will be made by crossed Cheque /Demand Draft of State Bank of India, Berhampore (WB) on presentation of bills in triplicate after deducting bank commission/ income tax/ education cess/ security deposit etc. as applicable as per Govt. rule.


Sub-Divisional Engineer
L.G. Sub-Division, CWC
Farakka, Murshidabad,
(W.B.) Pin- 742212

P. T. O.

Sub-Divisional Engineer

Copy to:-

1. The Superintending Engineer, HOC, CWC, Maithon (Dhanbad) with request for floating on Central Public Procurement Portal for wide publicity.
- ✓ 2. The Director, SMD with request for uploading on CWC website.
3. The Executive Engineer, Lower Ganga Division-3, CWC, Berhampore
4. The Executive Engineer, Damodar Division, CWC, Asansol.
5. The Sub-Divisional Engineer, B.J. Sub-Division, CWC, Krishnagar.
6. Notice board.